

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	99-00124-02-PV	COLES	229	22
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ROADWAY	STATION	OFFSET	SIGN TYPE	PANEL SIZE	SIGN PANEL TYPE 1	SIGN PANEL TYPE 2	SIGN PANEL TYPE 3	NUMBER OF POSTS	METAL POST TYPE A	METAL POST TYPE B	WOOD SIGN SUPPORT 4"x6"	STRUCTURAL STEEL SIGN SUPPORT BREAKAWAY	STRUCTURAL STEEL SIGN SUPPORT BREAKAWAY	STRUCTURAL STEEL SIGN SUPPORT BREAKAWAY	DRILLED SHAFT CONCRETE FOUNDATIONS
				IN X IN	SQ FT	SQ FT	SQ FT	EA	FOOT	FOOT	FOOT	W SECTION	FOOT	POUND	CU YD
CH-18	230+00	RT	M2-I(INTER)	21X15	2.2			1		19					
CH-18	230+00	RT	M1-1	36X36	9.0			1		20					
CH-18	234+50	LT	W6-1	36X36	9.0			1		18					
CH-18	235+50	MEDIAN	W6-3	24X30	5.0			1		14					
CH-18	238+50	RT	R4-7	24X30	5.0			2				W10X22	48	1056	2.36
CH-18	240+25	RT	A-01	144X114				1							
CH-18	240+25	RT	R3-2	36X36	9.0			1		17					
CH-18	242+25	LT	R3-1	36X36	9.0			1		17					
CH-18	243+00	MEDIAN	R4-7B	24X30	5.0			1		15					
CH-18	243+50	LT	A-04	144X60				2				W6X15	38	570	1.4
CH-18	247+25	RT	M3-I(INTER)	30X15	3.1			1		18					
CH-18	247+50	MEDIAN	M1-1	36X36	9.0			1		13					
CH-18	251+00	MEDIAN	M5-I(L,T,INT)	30X18	3.8			1		13					
CH-18	251+50	LT	R3-I100	24X24	4.0			1		13					
CH-18	254+50	RT	M3-I(INTER)	30X15	3.1			1		20					
CH-18	254+60	MEDIAN	M1-1	36X36	9.0			1							
CH-18	256+00	RT	M5-I(L,T,INT)	30X18	3.8			2				W6X15	46	690	1.4
CH-18	258+50	LT	A-03	144X60				1		13					
CH-18	260+00	RT	R4-7B	24X30	5.0			1							
CH-18	263+00	MEDIAN	R3-1	36X36	9.0			1							
CH-18	264+00	RT	R3-2	36X36	9.0			1		16					
CH-18	264+00	MEDIAN	LT	R3-2	36X36	9.0		2				W8X18	47	846	1.4
CH-18	264+00	RT	A-02	144X114				1		14					
CH-18	268+00	LT	R4-7	24X30	5.0			1							
CH-18	268+00	LT	W6-3	36X36	9.0			1		18					
CH-18	268+00	LT	W6-1	36X36	9.0			1		20					
CH-18	278+00	BARRICADE	M2-I(INTER)	21X15	2.2			1		18					
CH-18	278+00	BARRICADE	M1-1	36X36	9.0										
CH-18	278+00	BARRICADE	R11-2	48X30		10.0									
RAMP A	15+50	RT	W13-3	48X60		20.0		2		42					
RAMP A	18+90	LT	A-06	96X60			40.0	2		40					
RAMP A	28+75	RT	W3-1a	48X48		16.0		2		42					
RAMP A	31+50	RT	A-09	87X37		22.4		2				W6X9	33	297	1.4
RAMP A	33+50	LT	R5-1a	42X30	8.8			2		36					
RAMP A	33+50	RT	R5-1a	42X30	8.8			2		36					
RAMP A	34+75	LT	R5-1	48X48		16.0		2		42					
RAMP A	34+75	RT	R5-1	48X48		16.0		2		40					
RAMP A	ISLAND	RT	R1-1	36X36	9.0			1							
RAMP A	ISLAND	RT	R6-1R	36X12	3.0					17					
RAMP A	ISLAND	RT	R6-1(L)	36X12	3.0										
RAMP B	22+00	RT	R5-I100	48X60		20.0		2		44					
RAMP B	35+10	LT	W4-1(RT)	48X48		16.0		2		42					
RAMP C	35+00	RT	W13-3	48X60		20.0		2		44					
RAMP C	37+30	LT	A-06	96X60			40.0	2		44					
RAMP C	48+75	RT	W3-1a	48X48		16.0		2		32					
RAMP C	51+00	RT	A-10	87X37		22.4		2				W6X9	33	297	1.4
RAMP C	53+50	LT	R5-1a	42X30	8.8			2		38					
RAMP C	53+50	RT	R5-1a	42X30	8.8			2		36					
RAMP C	55+00	LT	R5-1	48X48		16.0		2		38					
RAMP C	55+00	RT	R5-1	48X48		16.0		2		40					
RAMP C	ISLAND	RT	R1-1	36X36	9.0			1							
RAMP C	ISLAND	RT	R6-1(R)	36X12	3.0					17					
RAMP C	ISLAND	RT	R6-1(L)	36X12	3.0										
RAMP D	42+00	RT	R5-I100	48X60		20.0		2		42					
RAMP D	55+60	LT	W4-1(RT)	48X48		16.0		2		38					
				SUB TOTAL	219.4	262.8	428		26	56	971		3756		9.36

ROADWAY	STATION	OFFSET	SIGN TYPE	PANEL SIZE	SIGN PANEL TYPE 1	SIGN PANEL TYPE 2	SIGN PANEL TYPE 3	NUMBER OF POSTS	METAL POST TYPE A	METAL POST TYPE B	WOOD SIGN SUPPORT 4"x6"	STRUCTURAL STEEL SIGN SUPPORT BREAKAWAY	STRUCTURAL STEEL SIGN SUPPORT BREAKAWAY	STRUCTURAL STEEL SIGN SUPPORT BREAKAWAY	DRILLED SHAFT CONCRETE FOUNDATIONS
				IN X IN	SQ FT	SQ FT	SQ FT	EA	FOOT	FOOT	FOOT	W SECTION	FOOT	POUND	CU YD
CH-18 / 700E INTERSECTION															
CH-18	167+50	RT	W2-1	30X30	6.3			1			16				
CH-18	167+75	LT	R2-1	24X30	5.0			1			16				
CH-18	169+25	LT	M3-4	24X12	2.0			1			17				
CH-18	170+47	LT	M1-6	24x24	4.0			1			14				
CH-18	171+02	RT	R1-1	30X30	6.3			1			14				
CH-18	172+25	RT	M3-2	24X12	2.0			1			17				
CH-18	173+75	RT	M1-6	24x24	4.0			1			16				
CH-18	174+00	LT	R2-1	24X30	5.0			1			16				
CH-18	174+00	LT	W2-1	30X30	6.3			1			16				
CH-18 / 780E INTERSECTION															
CH-18	208+25	RT	W2-2R	30X30	6.3			1			16				
CH-18	208+50	LT	R2-1	24X30	5.0			1			16				
CH-18	210+00	LT	M3-4	24X12	2.0			1			17				
CH-18	211+74	RT	M1-6	24x24	4.0			1			14				
CH-18	214+75	LT	R1-1	30X30	6.3			1			16				
CH-18	214+75	LT	W2-2L	30X30	6.3			1			16				
CH-18 / 800E INTERSECTION															
CH-18	221+24	RT	W2-2L	30X30	6.3			1			16				
CH-18	224+28	LT	R1-1	30X30	6.3			1			14				
CH-18	226+00	RT	M3-2	24X12	2.0			1			17				
CH-18	227+50	RT	M1-6	24x24	4.0			1			16				
CH-18	227+74	LT	R2-1	24X30	5.0			1			16				
CH-18	227+74	LT	W2-2R	30X30	6.3			1			16				
CH-18 / 870E INTERSECTION															
CH-18	262+25	RT	W2-2R	30X30	6.3			1			16				
CH-18	262+50	LT	R2-1	24X30	5.0			1			16				
CH-18	264+00	LT	M3-4	24X12	2.0			1			17				
CH-18	265+71	RT	M1-6	24x24	4.0			1			14				
CH-18	268+75	LT	R1-1	30X30	6.3			1			18				
CH-18	268+75	LT	W2-2L	30X30	6.3			1			18				
CH-18 / 900E INTERSECTION															
CH-18	272+95	RT	W2-2L	30X30	6.3			1			16				
CH-18	275+97	LT	R1-1	30X30	6.3			1			14				
CH-18	277+70	RT	M3-2	24X12	2.0			1			17				
CH-18	277+70	RT	M1-6	24x24	4.0			1			16				
CH-18	279+20	RT	R2-1	24X30	5.0			1			16				
CH-18	279+45	LT	W2-2R	30X30	6.3			1			16				
I-57	828+62	RT	A-08	144X96			96.0	2				W8X18	44	846	1.4
I-57	855+02	RT	A-07	144X96			96.0	2				W8X18	44	846	1.4
I-57	878+25	RT	A-05	180X78			97.5	2				W8X18	43	774	1.4
I-57	923+50	LT	A-05	180X78			97.5	2				W6X15	32	480	1.4
I-57	946+81	LT	A-07	144X96			96.0	2				W8X18	44	846	1.4
I-57	973+21	LT	A-08	144X96			96.0	2				W8X18	44	846	1.4
				SUB TOTAL	160.5	0	579	38	0	0	444		4638		8.4
				TOTAL	379.9	262.8	1007		26	56	1415		8394		17.8

07/13/2005
 15970065597_620206/CNV/Sheet 6-63-SC-H-02.dgn
 SMA 12/26/03
 MVM 12/26/03
 REVIEWED SMA 01/03/05



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SIGNING PLAN SCHEDULE
 FAI-57, FAS 642
 SEC NO. 15-23K, 99-00124-02-PV
 COLES COUNTY, ILLINOIS

SCALE: NOT TO SCALE
 DATE 07/13/2005
 DRAWN BY MVM
 CHECKED BY SKM