F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	99-00124-02-PV	COLES	229	23
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CULVERT DRAINAGE SCHEDULE

STATION	ROADWAY	PIPE CULVERTS					BOX CULVERTS			END SECTIONS							GRATING FOR END SECTIONS			INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	MANHOLES, TY A, 4' DIA, TY 1 FRAME, CLOSED LID	FLARED END SECTION REMOVAL
		RCCP, TY 1 (FOOT)			TYPE 1, CS/A EQ RS (FOOT)		PRECAST CONC. (FOOT)			PRECAST REINF. CONC. FLARED END SECTIONS (EACH)			METAL END SECT., ERS (EA)		PRECAST CONC. BOX CULV. END SECTIONS (EA)		PRECAST REINF. CONC. FLARED END SECTIONS (EACH)	PRECAST CONC. BOX CULV. END SECTIONS (EA)				
		15"	24"	36"	24"	36"	6'x3'	6'X3' (M273)	8'x4' (M273)	15"	24"	36"	24"	36"	6'x3'	8'x4'	36"	6'x3'	8'x4'			
170+12.00	CH18			87								2										
171+37.00	CH18			91								2										
176+40.00	CH18, F.E.				32								2									
185+00.00	CH18, F.E.				32								2									
185+00.00	CH18, F.E.				32								2									
190+37.00	CH18								3 @ 90							6			6			
205+00.00	CH18, F.E.				48								2									
205+00.00	CH18, F.E.				48								2									
213+00.00	CH18, F.E.				40								2									
223+61.00	CH18			60								2										
224+49.16	CH18, F.E.					43								2								
248+44.00	CH18			111								2										
250+09.00	CH18			119								2										
265+00.00	CH18						151								2							
275+60.00	CH18			60								2										
276+19.52	CH18, F.E.				42								2									
68+26.83	700E, F.E.					48								2								
68+26.83	700E, P.E.					38								2								
73+22.40	700E, P.E.				30								2									
10+44.00	800E					54								2								
11+25.00	800E, F.E.				29								2									
10+38.00	900E				59								2									
11+25.00	900E, F.E.				29								2									
15+00.00	RAMP A	38								1										1		
16+00.00	RAMP A	40								1										1		
18+41.00	RAMP A			27								1					1					1
18+77.00	RAMP A																				1	
23+50.00	RAMP A			2 @ 48								4										
30+00.00	RAMP B							76							2			2				
36+75.00	RAMP B	33								1										1		
*39+81.61	RAMP B																					
*31+36.72	RAMP C																					
34+00.00	RAMP C	40								1										1		
34+37.00	RAMP C		8								1											1
35+75.00	RAMP C	47								1										1		
39+21.00	RAMP C			62								1					1					1
41+00.00	RAMP C			57								2										
50+00.00	RAMP C			143								2										
41+36.00	RAMP D						206								2			2				
56+81.50	RAMP D																				1	
57+27.58	RAMP D			12								1					1					1
57+50.00	RAMP D	36								1										1		
	TOTAL	234	8	925	421	183	357	76	270	6	1	23	22	8	6	6	3	4	6	6	2	4

* SEE BOX CULVERT EXTENSION PLANS, SHEETS 135 & 136.

© Copyright Hanson Professional Services Inc. 2005

HANSON

07/13/2005
I:\57.0BS\Sft\2028NCN\NS\sheet\c-60_02d.mdgn

LAYOUT	SKM	12/26/03
LIBRARY	MNM	12/26/03
REVIEWED	JWM	01/05/04

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

CULVERT DRAINAGE SCHEDULE
FAI-57, FAS 642
SEC NO. 15-23K, 99-00124-02-PV
COLES COUNTY, ILLINOIS

SCALE: NOT TO SCALE — DRAWN BY MNM
DATE 07/13/2005 — CHECKED BY SKM