

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642 99-00124-02-PV	COLES		229	63
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STATION	RAMP C				I-57 S.B. EXISTING E.O.P.		NEUTRAL AREA		
	RAMP C ELEVATION	OFFSET TO PROPOSED LT. E.O.P.	LEFT E.O.P. ELEVATION	RIGHT E.O. AGG. SHLDR. ELEVATION	LEFT E.O.S. ELEVATION	OFFSET FROM RAMP C	SURVEYED ELEV.	OFFSET FROM RAMP C	ELEVATION
30+00.00	683.45			682.87		1.02	683.46		
30+25.00	683.35			682.98		2.36	683.39		
30+50.00	683.24			682.92		3.69	683.30		
30+75.00	683.17			682.85		5.03	683.25		
31+00.00	683.14			682.82		6.36	683.24		
31+25.00	683.07			682.75		7.69	683.19		
31+50.00	682.98			682.66		9.03	683.12		
31+75.00	682.93			682.61		10.36	683.09		
32+00.00	682.89			682.57		11.69	683.07		
32+25.00	682.83			682.51		13.02	683.03		
32+50.00	682.76			682.44		14.36	682.98		
32+75.00	682.71			682.39		15.69	682.95		
32+99.57	682.70	16.00	682.94	682.38		17.00	682.94		
33+25.00	682.66	16.00	682.90	682.34		18.36	682.90		
33+50.00	682.62	16.00	682.86	682.30		19.69	682.86		
33+75.00	682.66	16.00	682.90	682.34		21.02	682.90		
34+00.00	682.72	16.00	682.96	682.40		22.36	682.96	19.17	682.91
34+25.00	682.82	16.00	683.06	682.50		23.69	683.06	19.74	683.00
34+50.00	682.94	16.00	683.18	682.62		25.03	683.18	20.31	683.11
34+75.00	683.04	16.00	683.28	682.72		26.43	683.28	20.88	683.20
35+00.00	683.14	16.00	683.38	682.82		27.94	683.38	21.45	683.28
35+25.00	683.19	16.00	683.43	682.87		29.57	683.43	22.02	683.32
35+50.00	683.20	16.00	683.44	682.88		31.30	683.44	22.59	683.31
35+75.00	683.21	16.00	683.45	682.89		33.14	683.45	23.16	683.30
36+00.00	683.26	16.00	683.50	682.94		35.09	683.50	23.72	683.33
36+25.00	683.31	16.00	683.55	682.99		37.15	683.55	24.29	683.36
36+50.00	683.32	16.00	683.56	683.00		39.31	683.56	24.86	683.34
36+60.96	683.32	16.00	683.56	683.00		40.30	683.56	25.11	683.33
36+75.00	683.31	16.00	683.60	682.99	683.45	41.59	683.60		
37+00.00	683.30	16.00	683.67	682.98	683.52	43.98	683.67		
37+25.00	683.26	16.00	683.72	682.94	683.58	46.47	683.72		
37+50.00	683.19	16.00	683.74	682.87	683.60	49.08	683.74		
37+75.00	683.15	16.00	683.78	682.83	683.65	51.79	683.78		
38+00.00	683.14	16.00	683.86	682.78	683.73	54.62	683.86		
38+25.00	683.13	16.00	683.93	682.73	683.80	58.11	683.93		
38+50.00	683.08	16.00	683.97	682.63	683.85	62.56	683.97		
38+70.96	683.05	16.00	684.01	682.57	683.89	67.04	684.01		



© Copyright Hanson Professional Services Inc. 2005

LAYOUT: EJP/SKM/03/28/03
 DRAWN: JLW 04/28/03
 REVISIONS: SKM 11/22/02
 07/13/2005
 R:07 J065 97 s20280C:\M\SketchC-503A.mpdgn

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 RAMP C TERMINAL DETAIL
 FAI-57, FAS 642
 SEC NO. 15-23K, 99-00124-02-PV
 COLES COUNTY, ILLINOIS
 SCALE: NOT TO SCALE
 DATE 07/13/2005
 DRAWN BY JLW
 CHECKED BY SKM