

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			BOI.FED. 201. STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		X028-2A		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	16	16		
20200100	EARTH EXCAVATION	CU YD	513	513		
20400800	FURNISHED EXCAVATION	CU YD	111	111		
25000210	SEEDING, CLASS 2A	ACRE	0.2	0.2		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	15	15		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	15	15		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	15	15		
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.3	0.3		
25100115	MULCH, METHOD 2	ACRE	0.2	0.2		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	17	17		
28000300	TEMPORARY DITCH CHECKS	EACH	4	4		
28100107	STONE RIPRAP, CLASS A4	SQ YD	395	395		
28200200	FILTER FABRIC	SQ YD	395	395		
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	173	173		
35650700	BASE COURSE WIDENING	SQ YD	459	459		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	31	31		
44000100	PAVEMENT REMOVAL	SQ YD	59	59		
44001113	BITUMINOUS CONCRETE SURFACE REMOVAL (ASBESTOS)	SQ YD	139	139		
44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	235	235		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1		
50200100	STRUCTURE EXCAVATION	CU YD	68	68		
50300225	CONCRETE STRUCTURES	CU YD	11.6	11.6		
50500505	STUD SHEAR CONNECTORS	EACH	60	60		
* 50700209	UNTREATED TIMBER LAGGING	SQ FT	270	270		
* 50700211	FURNISHING SOLDIER PILES (HP SECTION)	FOOT	127	127		
50800105	REINFORCEMENT BARS	POUND	49,090	49,090		
51500100	NAME PLATES	EACH	1	1		
54003000	CONCRETE BOX CULVERTS	CU YD	207.9	207.9		
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	30	30		
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	650	650		
* 63000005	STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	50	50		
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	75	75		
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4		
70500100	STEEL PLATE BEAM GUARD RAIL TYPE A	FOOT	85	85		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	7	7		
67100100	MOBILIZATION	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		

SUMMARY OF QUANTITIES			BOI.FED. 201. STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		X028-2A	SFTY-3A	
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	2	2		
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	76	76		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	25	25		
70400500	TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	380	380		
70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	320	320		
70500200	TEMPORARY STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	37.5	37.5		
70500685	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 10	EACH	2	2		
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1670	1670		
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	13	13		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1584	1584		
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	380	380		
* X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	104	104		
* X0324456	DRILLING AND SETTING SOLDIER PILES (IN ROCK)	CU FT	113	113		
X0348700	AGGREGATE DITCH CHECK	EACH	1	1		
X0392300	DITCH CHECK REMOVAL	EACH	1	1		
X4024000	TEMPORARY ACCESS (FIELD ENTRANCE)	EACH	2	2		
X4073161	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 14"	SQ YD	312	312		
X4080020	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50	TON	4	4		
X6330103	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, TANGENT	EACH	1	1		
Z0002600	BAR SPLICERS	EACH	169	169		
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2			2
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2			2

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

DRAWN BY  
CHECKED BY

SCALE: VERT. HORIZ.  
DATE

district  
 10/26/2005  
 ct:\p\_projects\94434\d04599pa.dgn  
 SOO

PLOT DATE = 10/26/2005  
 PLOT SCALE = #SCALE#  
 USER NAME = district

Rev.