

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
328	109B-1	WHITE	26	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION	FILL	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EARTHWORK BALANCE, WASTE (+) SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
SN 097-2012				
72+00 TO 72+50	14	16	11	-5
72+50 TO 73+00	15	20	11	-9
73+00 TO 73+50	8	11	6	-5
73+50 TO 74+00	10	5	8	3
74+00 TO 75+00	16	1	0	-1
75+00 TO 75+52.5	1	0	0	0
EXCAVATION AT STRUCTURE	400	400	300	-100
74+87.5 TO 75+00	4	0	3	3
75+00 TO 75+50	15	6	11	6
75+50 TO 76+00	12	12	9	-3
76+00 TO 76+50	10	10	8	-2
76+50 TO 76+90	7	3	5	3
SN 097-2012 TOTAL	513	484	372	-111

GUARDRAIL SCHEDULE

LOCATION	STEEL PLATE BEAM GUARDRAIL, TYPE A	STEEL PLATE BEAM GUARDRAIL, TYPE B	TEMPORARY TRAFFIC BARRIER TERMINAL TYPE 10	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL TANGENT	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL TYPE 1 TANGENT	TEMPORARY STEEL PLATE BEAM GUARDRAIL	TERMINAL MARKER - DIRECT APPLIED	GUARDRAIL MARKERS, TYPE A	TEMPORARY STEEL PLATE BEAM GUARD RAIL, TYPE B	STEEL PLATE BEAM GUARDRAIL ATTACHED TO STRUCTURE
	FOOT	FOOT	EACH	EACH	EACH	FOOT	EACH	EACH	FOOT	FOOT
STAGE I										
NW CORNER		50	1	1		35			37.5	
SW CORNER			1	1		50				
OVER STRUCTURE										37.5
NE CORNER	156.25			1			1			
SE CORNER	206.25			1			1			
STAGE II										
NW CORNER	175						1	7		
SW CORNER	112.5						1			
OVER STRUCTURE					1			6		37.5
NE CORNER										
SE CORNER										
TOTAL	650	50	2	4	1	85	4	13	37.5	75

SEEDING SCHEDULE

SEEDING CLASS 2	0.2 ACRES
NITROGEN FERTILIZER	15 LBS
PHOSPHORUS FERTILIZER NUTRIENT	15 LBS
POTASSIUM FERTILIZER NUTRIENT	15 LBS
AGRICULTURAL GROUND LIMESTONE	0.3 TONS
MULCH METHOD 2	0.2 ACRES
TEMPORARY EROSION CONTROL SEEDING	17 POUND

TEMPORARY DITCH CHECKS

LOCATION	QUANTITY
NW CORNER	1
NE CORNER	1
SW CORNER	1
SE CORNER	1
TOTAL	4 EACH

AGGREGATE DITCH CHECK

OFFSET	STATION	QUANTITY
50' LT	74+50	1 EACH

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. DATE  
HORIZ.

DRAWN BY  
CHECKED BY