

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
*	**	SALINE	119	3
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

•SAHARA WOODS SFWA CONTRACT NO. 98834
 **INTERNAL PARK ROADS - SFWA

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				FO00	YO30-1E
				100% STATE	100% STATE
20100500	TREE REMOVAL, ACRES	ACRE	1.30	1.30	
20200100	EARTH EXCAVATION	CU YD	3818	3818	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1489	1489	
20400100	BORROW EXCAVATION	CU YD	8905	8905	
20900310	POROUS GRANULAR BACKFILL	TON	248	248	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	840	840	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	840	840	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	840	840	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	14	14	
25001700	SEEDING, CLASS 3 (MODIFIED)	ACRE	7.0	7.0	
25100115	MULCH, METHOD 2	ACRE	7.0	7.0	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2100.0	2100.0	
28000300	TEMPORARY DITCH CHECKS	EACH	70	70	
28000400	PERIMETER EROSION BARRIER	FOOT	4058	4058	
28000500	INLET AND PIPE PROTECTION	EACH	14	14	
28100207	STONE RIPRAP, CLASS A4	TON	356	356	
28200200	FILTER FABRIC	SQ YD	534	534	
35100100	AGGREGATE BASE COURSE, TYPE A	TON	24,890	24,890	
35800100	PREPARATION OF BASE	SQ YD	33,781	33,781	
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	46,244	46,244	
40300300	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	GALLON	126,738	126,738	1
40300500	COVER COAT AGGREGATE	TON	2,129	2,129	
40300600	SEAL COAT AGGREGATE	TON	1,064	1,064	
50100100	REMOVAL OF EXISTING STRUCTURE	EACH	1	1	
50105220	PIPE CULVERT REMOVAL	FOOT	356	356	
542D0217	PIPE CULVERTS, CLASS D, TYPE 1, 12"	FOOT	118	118	
542D0220	PIPE CULVERTS, CLASS D, TYPE 1, 15"	FOOT	182	182	
542D0223	PIPE CULVERTS, CLASS D, TYPE 1, 18"	FOOT	84	84	
542D0229	PIPE CULVERTS, CLASS D, TYPE 1, 24"	FOOT	169	169	
542D0241	PIPE CULVERTS, CLASS D, TYPE 1, 36"	FOOT	72	72	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9	
67100100	MOBILIZATION	L SUM	1	1	

△ Rev. 1-9-06

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
*	**	SALINE	119	9
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*SAHARA WOODS SFWA CONTRACT NO. 98834
 **INTERNAL PARK ROADS - SFWA

SURFACING SCHEDULE

LOCATION STATION TO STATION	PREPARATION OF BASE	BITUMINOUS MATERIALS (PRIME COAT)	BITUMINOUS MATERIALS (COVER AND SEAL COAT)	COVER COAT AGGREGATE	SEAL COAT AGGREGATE	AGGREGATE BASE COURSE, TYPE A
	SQYD	GALLON	GALLON	TON	TON	TON
TIPPLE ROAD 100+00 TO 123+00		3067	8433	138	69	2700
123+00 TO 124+31.94	928	468	1392	24	12	
HAULAGE ROAD 300+00 TO 374+78.82	18282	9971	27423	458	229	
374+78.82 TO 384+06.97	2270	1238	3406	57	28	
LAKE RD. 400+00 TO 442+54.54	10441	5693	15602	264	132	
0+00 TO 16+82.12		2238	6153	104	52	1897
16+82.12 TO 76+03.08		5263	13818	232	116	4398
SHAY RD. 500+24 TO 531+00		4152	11433	192	96	3538
531+00 TO 571+76.39		3624	9513	160	80	3028
SPUR RD. 200+00 TO 204+42		1615	4554	76	38	1421
SHOOTING RANGE ROAD 600+00 TO 627+71		3695	10161	170	85	3100
BOAT LOT		1911	5460	92	46	1732
HEADQUARTERS LOT	1860	1023	2790	50	25	884
CAR LOT 1		244	666	12	6	242
CAR LOT 2		279	753	14	7	270
CAR LOT 3		257	693	12	6	252
CAR LOT 4		1506	4428	74	37	1428
TOTALS	33781	46244	126738	2129	1064	24890

SEEDING SCHEDULE

LOCATION STATION TO STATION	SEEDING, CLASS 3 (MODIFIED)	NITROGEN FERTILIZER NUTRIENT	PHOSPHOROUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH, METHOD 2
	ACRE	POUND	POUND	POUND	TON	ACRE
TIPPLE ROAD RT. STA. 100+00 TO STA. 124+42.9	0.5	60	60	60	1.0	0.5
TIPPLE ROAD LT. STA. 100+00 TO STA. 124+42.9	1.0	120	120	120	2.0	1.0
LAKE ROAD RT. STA. 0+00 TO STA. 76+03.08	0.7	84	84	84	1.4	0.7
LAKE ROAD LT. STA. 0+00 TO STA. 76+03.08	0.7	84	84	84	1.4	0.7
SHAY ROAD RT. STA. 500+13.26 TO STA. 571+76.39	1.5	180	180	180	3.0	1.5
SHAY ROAD LT. STA. 500+13.26 TO STA. 571+76.39	1.4	168	168	168	2.8	1.4
SPUR RD. STA. 200+00 TO STA. 204+42.23	1.0	120	120	120	2.0	1.0
BOAT LOT STA. 4+21.14 TO STA. 10+00	0.2	24	24	24	0.4	0.2
TOTAL	7.0	840	840	840	14.0	7.0

Rev. 1-9-06