

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SALINE	119	2
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

\*SAHARA WOODS SFWA CONTRACT NO. 98834  
 \*\*INTERNAL PARK ROADS - SFWA

## INDEX OF SHEETS

1	COVER SHEET
2	INDEX OF SHEETS, MIX DESIGN, GENERAL NOTES, HIGHWAY STANDARDS, SIGNATURE BLOCK
3-4	SUMMARY OF QUANTITIES
5	SITE MAP
6-7A	TYPICAL SECTIONS
8	SCHEDULE - TREE REMOVAL, DRAINAGE STRUCTURE
9	SCHEDULE - SURFACING, SEEDING
10	SCHEDULE - EARTHWORK, LIGHTING, PAVEMENT MARKING, GATE, BOLLARD
11	SCHEDULE - TEMPORARY DITCH CHECK, PERIMETER EROSION BARRIER, INLET AND PIPE PROTECTION, SIGNING
12-13	PLAN & PROFILE - TIPPLE RD.
14-16	PLAN & PROFILE - HAULAGE RD.
16A-16B	PLAN SHEETS - SHOOTING RANGE RD.
17-24	PLAN & PROFILE - LAKE RD.
25-29	PLAN & PROFILE - SHAY RD.
30	PLAN, PROFILE & TYPICAL - SPUR RD.
31	PLAN, PROFILE & TYPICAL - BOAT LOT
32	PLAN, STRIPING & TYPICAL - HEADQUARTERS LOT
33	PLAN & TYPICAL - CAR LOT 1, 2 & 3, BOLLARD DETAIL
33A	PLAN & TYPICAL - CAR LOT 4 AND BOLLARD DETAIL
34-35	EROSION CONTROL - TIPPLE RD.
36-41	EROSION CONTROL - LAKE RD.
42-46	EROSION CONTROL - SHAY RD.
47	EROSION CONTROL - SPUR RD.
48	EROSION CONTROL - BOAT LOT
49	TRAFFIC CONTROL PLAN
49A	SIGNING PLAN & DETAIL
50	DETAIL - GATE & LIGHT POLE FOUNDATION
50A	DETAIL - GATE, SEEDING & HANDICAPPED PARKING SYMBOL
51-59	CROSS SECTIONS - TIPPLE RD.
60-86	CROSS SECTIONS - LAKE RD.
87-112	CROSS SECTIONS - SHAY RD.
113-116	CROSS SECTIONS - SPUR RD.
117-119	CROSS SECTIONS - BOAT LOT

## HIGHWAY STANDARDS

000001-04	701306-01	B.L.R. 21-6
280001-02	720001	
701006-02	720006	
701301-02	780001-01	

## GENERAL NOTES

FACTORS USED FOR ESTIMATING PLAN QUANTITIES ARE AS FOLLOWS AND SHALL NOT BE USED FOR THE BASIS OF FINAL QUANTITIES:

ALL AGGREGATE EXCEPT COVER AND SEAL COATS	2.05 TONS/CU. YD. (2.43 METRIC TONS/CU. METER)
BITUMINOUS MATERIALS:	
PRIME COAT	0.5 GAL./SQ. YD. (2.0 LITERS/SQ. METER)
COVER AND SEAL COATS	0.5 GAL./SQ. YD. (2.0 LITERS/SQ. METER)
COVER COAT AGGREGATE	25 LB./SQ. YD. (14 KG/SQ. METER)
SEAL COAT AGGREGATE	25 LB./SQ. YD. (14 KG/SQ. METER)
RIPRAP	1.50 TONS/CU. YD. (1.78 METRIC TONS/CU. METER)

TREES SHALL BE PRESERVED THROUGHOUT THIS SECTION AS SHOWN ON THE PLANS AND AS DIRECTED BY THE ENGINEER. GENERALLY, TREES OUTSIDE THE CLEAR ZONE, AND WHICH DO NOT INTERFERE WITH CONSTRUCTION, SHALL NOT BE DISTURBED.

FINAL LOCATION FOR ALL LIGHTING SHALL BE DETERMINED BY THE RESIDENT ENGINEER.

COMMITMENTS:

NONE.

## MIX DESIGN

LOCATION(S):	BITUMINOUS MIXTURE COMPLETE
MIXTURE USE(S):	
AC/PG:	PG64-22
RAP % (MAX):	50
DESIGN AIR VOIDS:	3.0 %, 50 GYRATION SUPERPAVE DESIGN
MIXTURE COMPOSITION: (GRADATION MIXTURE)	BITUMINOUS AGGREGATE MIXTURE, SUPERPAVE
FRICTION AGGREGATE:	NONE