F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	SALINE	119	12
STA. 100+00	TO STA. 115+00			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*SAHARA WOODS SFWA CONTRACT NO. 98834
**INTERNAL PARK ROADS - SFWA

PLAN
SURVEYED
PLOTTED
ALIGNMENT CHECKED
PT. OF WAY CHECKED
CADD FILE NAME
NOTE BOOK
NO.
DATE

PROFILE
SURVEYED
PLOTTED
GRADE CHECKED
VAL NOTED
STRUCTURE NOTING CHKD
NOTE BOOK
NO.
DATE BY

PROJECT BEGINS
TIPPLE RD. STA. 100+00

POT Sta 100+00.00

PROPOSED PIPE CULVERT
CLASS D, TYPE 1, 15"
U.S.F.L. = 428.13
D.S.F.L. = 427.39

PROPOSED BITUMINOUS SURFACE TREATMENT A-3

SEE SHEET 32 OF 119 FOR DETAILS

PIPE CULVERT REMOVAL
EXISTING 8" STEEL PIPE

SEE SHEET 32 OF 119 FOR REMOVAL DETAILS

SCALE
50' 0 25' 50'

RADIO TOWER

MH

8" STEEL PIPE

100+00 105+00 110+00 115+00

22'

STA. 106+73
PIPE CULVERT REMOVAL
EXISTING 8" STEEL PIPE
PROPOSED PIPE CULVERT
CLASS D, TYPE 1, 24"
U.S.F.L. = 427.33
D.S.F.L. = 427.17

8" STEEL PIPE

PROPOSED BITUMINOUS SURFACE TREATMENT A-3

TOWN PARK RD.

BM 652 - ELEV.= 428.906
RR SPIKE IN PP IN SE QUAD
OF TOWN PARK RD AND
TIPPLE RD

PROPOSED PROFILE (TIPPLE RD.)

EXISTING PROFILE (TIPPLE RD.)

175.00' V.C.

-5.40% -3.00% -3.83% +0.64% -0.20% -0.10% -0.41% +1.30% -0.41% -0.30% -0.30%

105+00
432.4

VPI STA. 106+12.50
ELEVATION 430.30

106+69
427.33

108+00
429.1

3' UNDERCUT AREA

SPECIAL DITCH LT.

DITCH LT.

114+00
426.8

3' UNDERCUT AREA

	100+00	101+00	102+00	103+00	104+00	105+00	106+00	107+00	108+00	109+00	110+00	111+00	112+00	113+00	114+00	115+00
EXIST.	429.28	430.59	434.29	439.44	439.04	433.54	430.14	429.94	429.83	428.33	426.73	426.33	426.00	427.30	427.40	427.10
PROP.	429.29	431.51	435.21	440.36	439.96	434.46	431.50	430.86	430.75	430.35	429.94	429.53	429.13	428.73	428.32	428.02

•DATE-TIME•
•DGN FILE•
•LEVEL MASK•
XREF tqaq01
XREF

PLAN PROFILE SHEET - TIPPLE RD. STA 100+00 TO 115+00