

RESURFACING SCHEDULE

VARIOUS ROUTES
D-9 CONT. MAINT. FY 06-3
VARIOUS CO.
CONTRACT #98924
SHEET 13 OF 42

LOCATION				LENGTH (FEET)	WIDTH (FEET)	BIT SURF REMOVAL (SQ YD)	AVG DEPTH (INCH)	VOLUME (CU YD)	BIT CONC SURF CRSE MIX "C" (TON)	BIT CONC SURF CRSE MIX "D" (TON)	BIT CONC BASE CRSE WIDENING, 9" (SQ YD)	BIT CONC BASE CRSE WIDENING, 10" (SQ YD)	AGG BASE CRSE, TY A, 12" (SQ YD)	AGG SHOULDERS TY B (TON)
LOCATION #1														
STA. 751+00	TO	STA. 768+00		1,700	22	4,155.56	1.5	173.15	349.07	0.00	0.00	0.00	0.00	0.00
SUBTOTAL LOCATION #1 =						4,156			350	0	0	0	0	0
LOCATION #2														
STA. 417+40	TO	STA. 417+60		20	31	68.89	1.5	2.87	5.79	0.00	0.00	0.00	0.00	1.01
STA. 417+60	TO	STA. 440+65		2,305	22	5,634.44	1.5	234.77	473.29	0.00	0.00	0.00	0.00	116.67
STA. 440+65	TO	STA. 446+07		542	22	1,324.89	1.5	55.20	111.29	0.00	0.00	0.00	0.00	13.72
STA. 446+07	TO	STA. 452+16.8 BK =		610	20	1,355.11	1.5	56.46	113.83	0.00	0.00	0.00	0.00	0.00
STA. 452+97.5 AH	TO	STA. 456+05		308	20	683.33	1.5	28.47	57.40	0.00	0.00	0.00	0.00	0.00
STA. 456+05	TO	STA. 462+87		682	18.5	1,401.89	1.5	58.41	117.76	0.00	0.00	0.00	0.00	0.00
STA. 462+87	TO	STA. 467+57		470	19.5	1,018.33	1.5	42.43	85.54	0.00	0.00	0.00	0.00	11.90
STA. 467+57	TO	STA. 471+42		385	20	855.56	1.5	35.65	71.87	0.00	0.00	0.00	0.00	0.00
SUBTOTAL LOCATION #2 =						12,343			1,037	0	0	0	0	144
LOCATION #3														
STA. 729+75 LT	TO	STA. 733+75 LT		400	4	0.00	0.0	0.00	0.00	0.00	0.00	177.78	177.78	0.00
STA. 729+60 RT	TO	STA. 731+60 RT		200	4	0.00	0.0	0.00	0.00	0.00	0.00	88.89	88.89	0.00
STA. 734+25 LT	TO	STA. 735+00 LT		75	4	0.00	0.0	0.00	0.00	0.00	0.00	33.33	33.33	0.00
STA. 742+00 RT	TO	STA. 742+90 RT		90	4	0.00	0.0	0.00	0.00	0.00	0.00	40.00	40.00	0.00
STA. 743+20 RT	TO	STA. 744+35 RT		115	4	0.00	0.0	0.00	0.00	0.00	0.00	51.11	51.11	0.00
STA. 744+70 RT	TO	STA. 746+30 RT		160	4	0.00	0.0	0.00	0.00	0.00	0.00	71.11	71.11	0.00
SUBTOTAL LOCATION #3 =						0			0	0	0	463	463	0
LOCATION #4														
STA. 980+86	TO	STA. 1014+86		3,400	21	7,933.33	1.5	330.56	666.40	0.00	1,512.00	0.00	0.00	86.05
SUBTOTAL LOCATION #4 =						7,934			667	0	1,512	0	0	87
LOCATION #5														
STA. 68+89	TO	STA. 71+88		299	50	1,661.11	1.5	69.21	0.00	139.53	0.00	0.00	0.00	0.00
SUBTOTAL LOCATION #5 =						1,662			0	140	0	0	0	0
LOCATION #6														
STA. 1+40	TO	STA. 8+28		688	20	1,528.89	1.5	63.70	128.43	0.00	0.00	0.00	0.00	34.82
STA. 8+28	TO	STA. 18+00							OMISSION					
STA. 18+00	TO	STA. 39+46		2,146	20	4,768.89	1.5	198.70	400.59	0.00	0.00	0.00	0.00	108.62
SUBTOTAL LOCATION #6 =						6,298			530	0	0	0	0	144
LOCATION #7														
STA. 533+00	TO	STA. 535+50		250	11	305.56	1.5	12.73	25.67	0.00	0.00	0.00	0.00	0.00
STA. 535+50	TO	STA. 560+20							OMISSION					
STA. 560+20	TO	STA. 570+20		1,000	11	1,222.22	1.5	50.93	102.67	0.00	0.00	0.00	0.00	0.00
STA. 570+20	TO	STA. 607+27							OMISSION					
STA. 607+27	TO	STA. 612+00		473	11	578.11	1.5	24.09	48.56	0.00	0.00	0.00	0.00	0.00
STA. 612+00	TO	STA. 626+00							OMISSION					
STA. 626+00	TO	STA. 630+00		400	11	488.89	1.5	20.37	41.07	0.00	0.00	0.00	0.00	0.00
STA. 630+00	TO	STA. 649+00							OMISSION					
STA. 649+00	TO	STA. 659+00		1,000	11	1,222.22	1.5	50.93	102.67	0.00	0.00	0.00	0.00	0.00
STA. 659+00	TO	STA. 761+50							OMISSION					
STA. 761+50	TO	STA. 777+00		1,550	11	1,894.44	1.5	78.94	159.13	0.00	0.00	0.00	0.00	0.00
STA. 777+00	TO	STA. 876+00							OMISSION					
STA. 876+00	TO	STA. 894+50		1,850	11	2,261.11	1.5	94.21	189.93	0.00	0.00	0.00	0.00	0.00
SUBTOTAL LOCATION #7 =						7,973			670	0	0	0	0	0
TOTAL LOCATIONS #1-7 =						40,366			3,254	140	1,512	463	463	375