

EARTHWORK SCHEDULE
LOCATION #1

LOCATION				EMBANKMENT	FURNISHED EXCAVATION
MAINLINE				(CU YD)	(CU YD)
STA. 749+00	TO	STA. 752+65		112	132.2
STA. 752+65	TO	STA. 761+00		202	238.4
TOTAL (CU YD) =				371	

SEEDING SCHEDULE
LOCATION #1

LOCATION				SEEDING, CLASS 2 (MODIFIED)	SEEDING, CLASS 7	TEMP EROSION CONTROL SEEDING	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGG GR LIMESTONE	MULCH, METHOD 2
				ACRE	ACRE	POUND	POUND	POUND	POUND	TON	ACRE
RIGHT											
STA. 749+00	TO	STA. 752+65		0.14	0.14	39.9	21.3	15.9	15.9	0.27	0.14
STA. 752+65	TO	STA. 761+00		0.25	0.25	88.9	47.6	35.7	35.7	0.61	0.25
LEFT											
STA. 749+00	TO	STA. 752+65		0.05	0.05	16.1	8.6	6.6	6.6	0.11	0.05
STA. 752+65	TO	STA. 761+00		0.12	0.12	36.4	19.4	13.9	13.9	0.25	0.12
TOTALS				0.6	0.6	182	97	73	73	1.3	0.6