SCHEDULE OF QUANTITIES

SHEET 1 OF 2

CODE NUMBER	PAY ITEM	UNIT	100% STATE TOTAL QUANTITY	5-01 5C092 I074 L208.35	5-02 5C092 I074 R214.25	5-03 5C010 I074 L183.90	5-04 5B010 U045 L012.58	5-05 5S010 I057 L235.32	5-06 5S010 I057 R238.14	5-07 5C020 I074 R155.62	5-08 5C020 I074 L158.44	5-09 5S057 I074 L134.10	5-10 5S057 I055 R156.20	5-11 5S057 U055 R000.20	5-12 5C057 U055 L000.40	5-13 5S057 U055 L001.70	5-14 SB 5S057 I039 R000.50	5-14 NB 5S057 I039 R000.50	5-15 SB 5S057 I039 R001.00	5-15 NB 5S057 I039 R001.00	5-16 SBa 5S057 I039 R001.90	5-16 SBb 5S057 I039 R001.90	5-16 NB 5S057 I039 R001.90	5-17 5S057 U051 R006.80	5-18 5C057 U051 L008.90	5-19 5C057 U051 L007.30	5-20 5B057 U051 R007.10	5-21 MONO TUBE #227	5-22 MONO TUBE #228	5-23 MONO TUBE #230	5-24 MONO TUBE #231	5-25 MONO TUBE #232
General Location:				VERMILION CNTY		CHAMPAIGN COUNTY				DEWITT COUNTY		MCLEAN COUNTY - SW SPAGHETTI BOWL					MCLEAN COUNTY - I-39							MCLEAN COUNTY - US 51 Busn				EDGAR COUNTY - MONOTUBES - Paris				
Scope of Work:				C	C	GM	GM	SS	SS	C	SR	SS	SS	SS	C	GM	SS	-	SS	-	BM	GM	GM	GM	GM	GM	BM-Rem	M	M	M	M	M
20400800	FURNISHED EXCAVATION	CUYD	269.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	269.00	-	-	-	-	-	-	-	-	-	-	-	-	-
60618320	CONCRETE MEDIAN SURFACE, 6 INCH	SQFT	158.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	158.00	-	-	-	-	-	-	-	-
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	212.50	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	212.50	-	-	-	-	-	-	-	-	-	-	-	-	-
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1.00	-	-	-	-	-	-	-	-	-	-	-	-	-
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1.00	-	-	-	-	-	-	-	-	-	-	-	-	-
63200310	GUARDRAIL REMOVAL	FOOT	1271.00	-	-	-	-	-	-	-	-	-	-	-	-	387.00	-	65.00	191.00	192.00	115.00	-	116.00	205.00	-	-	-	-	-	-	-	-
63400105	GUARD POSTS	EACH	10.00	-	-	-	-	10.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
64300450	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	6.00	-	-	-	-	2.00	2.00	-	-	-	-	-	-	-	-	-	2.00	-	-	-	-	-	-	-	-	-	-	-	-	-
64301090	ATTENUATOR BASE	SQYD	306.00	-	-	-	-	102.00	102.00	-	-	-	-	-	-	-	-	-	102.00	-	-	-	-	-	-	-	-	-	-	-	-	-
67100100	MOBILIZATION	L SUM	1.00	0.04	0.04	0.03	0.03	0.04	0.04	0.04	0.03	0.04	0.04	0.04	0.04	0.03	0.04	0.03	0.03	0.03	0.03	0.03	0.03	0.04	0.04	0.04	0.03	0.03	0.03	0.03	0.03	0.03
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	16.00	1.00	-	1.00	-	1.00	1.00	1.00	1.00	1.00	1.00	1.00	-	-	1.00	1.00	1.00	1.00	1.00	1.00	1.00	-	-	-	-	-	-	-	-	-
70100315	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	EACH	2.00	-	-	-	-	-	-	-	-	-	-	-	1.00	1.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	19.00	1.00	1.00	1.00	-	1.00	-	1.00	1.00	1.00	1.00	1.00	3.00	-	1.00	1.00	1.00	1.00	1.00	1.00	1.00	-	-	-	-	-	-	-	-	-
70100430	TRAFFIC CONTROL AND PROTECTION, STANDARD 701446	EACH	1.00	-	-	-	-	-	-	-	-	-	1.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1.00	-	1.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
70102822	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	0.50	-	-	-	0.50
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1.00	-	-	-	0.14	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	0.14	0.14	0.14	0.14	-	0.15	-	0.15	-
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1.00	-	-
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1.00	-	-	-	-	0.10	0.10	-	-	0.10	0.10	-	-	-	0.10	0.10	0.10	0.10	0.10	-	0.10	-	-	-	-	-	-	-	-	-
72000300	SIGN PANEL - TYPE 3	SQFT	6020.00	84.00	188.00	115.50	93.25	339.75	433.00	84.00	84.00	699.50	622.00	510.00	120.00	59.50	481.00	-	407.00	-	293.25	246.00	133.00	115.00	66.00	115.00	-	163.75	164.25	195.75	139.50	108.00
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	7310.50	71.50	113.50	134.75	55.00	249.00	430.50	47.50	47.50	721.00	710.75	441.00	92.00	333.50	550.00	257.25	518.75	275.00	643.75	-	153.75	362.75	78.00	221.25	84.00	151.50	144.00	186.00	120.00	117.00
72400710	RELOCATE SIGN PANEL - TYPE 1	SQFT	99.30	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	7.00	31.56	30.75	12.00	18.00
72400720	RELOCATE SIGN PANEL - TYPE 2	SQFT	24.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	12.00	-	-	-	12.00
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	10093.00	-	-	2128.00	457.50	-	-	-	-	-	-	-	-	521.25	-	-	-	-	-	3097.00	1468.50	979.00	495.00	946.00	-	-	-	-	-	-
73300200	OVERHEAD SIGN STRUCTURE - SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	384.00	-	-	-	-	94.00	75.00	-	-	-	-	70.00	-	-	74.00	-	71.00	-	-	-	-	-	-	-	-	-	-	-	-	-
73300300	OVERHEAD SIGN STRUCTURE - SPAN, TYPE III-A (5'-0" X 7'-0")	FOOT	86.00	-	-	-	-	-	-	-	-	86.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
73301810	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	374.00	-	-	-	-	41.00	39.00	-	-	65.00	71.00	58.00	-	-	52.00	-	48.00	-	-	-	-	-	-	-	-	-	-	-	-	-
73301840	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A	FOOT	79.00	17.00	24.00	-	-	-	-	17.00	-	-	-	-	21.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
73302170	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (36" X 5'-6")	FOOT	112.00	28.00	29.00	-	-	-	-	28.00	-	-	-	-	27.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
73303000	OVERHEAD SIGN STRUCTURE - MONOTUBE	FOOT	252.80	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	59.90	43.10	51.90	43.90	54.00
73304000	OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	FOOT	32.50	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	32.50			-	-	-	-	-	-	-	-	-
73400100	CONCRETE FOUNDATIONS	CUYD	22.90	-	-	4.18	1.40	-	-	-	-	-	-	-	-	1.40	-	-	-	-	-	6.27	3.54	2.36	1.40	2.36	-	-	-	-	-	-
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CUYD	201.50	9.00	9.00	-	-	25.00	25.00	9.00	-	22.00	23.00	21.50	9.50	-	21.50	-	27.00	-	-	-	-	-	-	-	-	-	-	-	-	-

BM = Overhead Sign Structure Replacement w/ Bridge Mount
BM-Rem = Existing Bridge Mount Removal only
C = Overhead Sign Structure Replacement w/ Cantilever
GM = Overhead Sign Structure Replacement w/ Breakaway Ground Mount
SS = Overhead Sign Structure Replacement w/ Simple Span
M = Overhead Sign Structure Replacement w/ Monotube
SR = Sign Replacement - Only

** 6 day (3 days before fdn's + 3 days before remove and erect) advanced notice with CMS for all of I-39 covered under 5-14 SB & 5-14 NB (5S057I039R000.50)

* VARIOUS
** D-5 OVD SIN STR REPL 2012-06

FILE NAME = c:\pw_work\pwidot\cearlockjd\d0266557\D046179-sht-schedule.dgn	USER NAME = cearlockjd	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 40.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 10/27/2011	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: N/A | SHEET NO. 1 OF 1 SHEETS | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	Various	178	8
		CONTRACT NO. 46179		
		ILLINOIS FED. AID PROJECT		