

# SCHEDULE OF QUANTITIES

## SHEET 2 OF 2

SCHEDULE OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	100% STATE TOTAL QUANTITY	General Location:																																		
				VERMILION CNTY					CHAMPAIGN COUNTY					DEWITT COUNTY					MCLEAN COUNTY - SW SPAGHETTI BOWL					MCLEAN COUNTY - I-39					MCLEAN COUNTY - US 51 Busn					EDGAR COUNTY - MONOTUBES - Paris				
				C	C	GM	GM	SS	SS	C	SR	SS	SS	SS	C	GM	SS	-	SS	-	BM	GM	GM	GM	GM	GM	GM	BM-Rem	M	M	M	M	M					
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	9.00	-	-	-	-	1.00	1.00	-	-	1.00	-	1.00	-	1.00	0.50	0.50	0.50	0.50	0.50	-	0.50	1.00	-	-	-	-	-	-	-							
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	7.00	1.00	1.00	1.00	-	-	-	1.00	-	-	-	-	1.00	-	-	-	-	-	-	-	-	-	1.00	1.00	-	-	-	-	-							
73601100	REMOVE OVERHEAD SIGN STRUCTURE, MONOTUBE - SPAN	EACH	5.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1.00	1.00	1.00	1.00	1.00								
73602000	REMOVE OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	EACH	2.00	-	-	-	1.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1.00	-	-	-	-								
73700100	REMOVE GROUND MOUNTED SIGN SUPPORT	EACH	2.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	2.00	-	-	-	-	-	-								
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	2.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	2.00	-	-	-	-	-	-								
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	27.00	1.00	1.00	1.00	-	2.00	2.00	1.00	-	2.00	2.00	2.00	1.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	2.00	1.00	1.00	-	-	-	-								
73800100	STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE - SPAN	EACH	2.00	-	-	-	-	-	-	-	-	-	-	2.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-								
73801100	REMOVE AND REERECT OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00	-	-	-	-	-	-	-	-	-	-	1.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-								
78200410	GUARDRAIL MARKERS, TYPE A	EACH	5.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-								
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-								
81028360	UNDERGROUND CONDUIT, PVC, 2 1/2" DIA.	FOOT	29.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	4.00	25.00	-	-	-	-								
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	2.00	-	-	-	-	-	1.00	-	-	-	-	-	-	1.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-								
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	500.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	42.00	458.00	-	-	-	-								
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	248.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	248.00	-	-	-	-								
87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	2.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1.00	1.00	-	-	-	-	-								
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	26.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	13.00	13.00	-	-	-	-	-								
87900200	DRILL EXISTING HANDHOLE	EACH	2.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1.00	1.00	-	-	-	-	-								
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	4.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	2.00	2.00	-	-	-	-	-								
88030070	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	2.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1.00	1.00	-	-	-	-	-								
88030080	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	2.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1.00	1.00	-	-	-	-	-								
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	259.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	259.00	-	-	-	-	-								
89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	110.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	110.00	-	-	-	-	-								
X4403800	MEDIAN SURFACE REMOVAL	SQFT	158.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	158.00	-	-	-	-	-	-	-								
X6320100	GUARDRAIL REMOVAL SPECIAL	FOOT	546.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	546.00	-	-	-	-	-	-								
X6340205	GUARD POSTS REMOVAL	EACH	18.00	-	-	-	-	10.00	8.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-								
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	68.00	6.00	5.00	6.00	-	6.00	6.00	6.00	3.00	6.00	6.00	6.00	-	-	6.00	6.00	**	**	**	**	**	-	-	-	-	-	-	-								
X7330070	OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	10.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	2.00	2.00	2.00	2.00	2.00								
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	18.00	1.00	1.00	1.00	1.00	1.00	-	1.00	1.00	1.00	1.00	1.00	-	1.00	-	1.00	-	1.00	-	-	1.00	1.00	1.00	1.00	-	-	-	-								
X8950305	REMOVE EXISTING SIGNAL HEAD	EACH	6.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	3.00	3.00	-	-	-	-								
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.00	0.04	0.04	0.03	0.03	0.04	0.04	0.04	0.03	0.04	0.04	0.04	0.04	0.03	0.04	0.03	0.03	0.03	0.03	0.03	0.04	0.04	0.04	0.03	0.03	0.03	0.03	0.03								
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	4.00	-	-	-	-	2.00	2.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-								

BM = Overhead Sign Structure Replacement w/ Bridge Mount  
 BM-Rem = Existing Bridge Mount Removal only  
 C = Overhead Sign Structure Replacement w/ Cantilever  
 GM = Overhead Sign Structure Replacement w/ Breakaway Ground Mount  
 SS = Overhead Sign Structure Replacement w/ Simple Span  
 M = Overhead Sign Structure Replacement w/ Monotube  
 SR = Sign Replacement - Only

\*\* 6 day (3 days before fdn's + 3 days before remove and erect) advanced notice with CMS for all of I-39 covered under 5-14 SB & 5-14 NB (SS0571039R000.50)

• VARIOUS  
 •• D-5 OVD SIN STR REPL 2012-06

FILE NAME =	USER NAME = oerlockjd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ca:\pw\work\p\dot\oerlockjd\0266557\046179-shr-schedule.dgn		DRAWN -	REVISED -			•	••	Various	178	9	
PLOT SCALE = 40.0000' / 1" =		CHECKED -	REVISED -			SCALE: N/A		SHEET NO. 1 OF 1 SHEETS		STA. TO STA.	
PLOT DATE = 10/7/2011		DATE -	REVISED -			ILLINOIS FED. AID PROJECT CONTRACT NO. 46179					