

SCHEDULE OF QUANTITIES
VERMILION COUNTY – INDIVIDUAL LOCATIONS

Location No.	5-01		
Structure No.	5 C 092 I074 L208.35		
County / Route	VERMILION CO. - I-74 WB - Salt Kettle Rest Area		
Scope of Work	This overhead cantilever is being replaced on a new drilled shaft foundation.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00
72000300	SIGN PANEL - TYPE 3	SQFT	84.00
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	71.50
73301840	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A	FOOT	17.00
73302170	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (36" X 5'-6")	FOOT	28.00
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CUYD	9.00
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	1.00
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	6.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00
Pay Item for CMS is for the advanced interstate notice only. CMS shown on Standards are included in the cost of the Standard.			

Location No.	5-02		
Structure No.	5 C 092 I074 R214.25		
County / Route	VERMILION CO. - I-74 EB - in collector lane for IL 1 interchange		
Scope of Work	This overhead cantilever is being replaced on a new drilled shaft foundation.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1.00
72000300	SIGN PANEL - TYPE 3	SQFT	188.00
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	113.50
73301840	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A	FOOT	24.00
73302170	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (36" X 5'-6")	FOOT	29.00
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CUYD	9.00
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	1.00
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	5.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00
3 day advanced notice CMS not needed. CMS to be placed back toward to Exit 214 "G-Street" and utilized during construction activities.			

- VARIOUS
- D-5 OVD SIN STR REPL 2012-06

FILE NAME =	USER NAME = ceerlockjd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES VERMILION COUNTY – INDIVIDUAL LOCATIONS	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pwork\pwork\ceerlockjd\0266957\046179-sh1-schedule.dgn	DRAWN -	REVISED -	•			••	Various	178	10	
PLOT SCALE = 40.0000' / 1" =	CHECKED -	REVISED -	CONTRACT NO. 46179							
PLOT DATE = 10/7/2011	DATE -	REVISED -	SCALE: N/A			SHEET NO. 1 OF 1 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT		