

## SCHEDULE OF QUANTITIES CHAMPAIGN COUNTY – INDIVIDUAL LOCATIONS

Location No.	5-03		
Structure No.	5 C 010 I074 L183.90		
County / Route	CHAMPAIGN CO. - I-74 WB - at Cunningham Ave. / US 45		
Scope of Work	This overhead cantilever is to be removed & replaced with a breakaway ground mount.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00
72000300	SIGN PANEL - TYPE 3	SQFT	115.50
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	134.75
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	2128.00
73400100	CONCRETE FOUNDATIONS	CUYD	4.18
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	1.00
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	6.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00

Pay Item for CMS is for the advanced interstate notice only. CMS shown on Standards are included in the cost of the Standard.

Location No.	5-05		
Structure No.	5 S 010 I057 L235.32		
County / Route	CHAMPAIGN CO. - I-57 SB - just North of the I-72 interchange		
Scope of Work	This overhead sign structure is being replaced on new drilled shaft foundations.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
63400105	GUARD POSTS	EACH	10.00
64300450	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2.00
64301090	ATTENUATOR BASE	SQYD	102.00
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1.00
72000300	SIGN PANEL - TYPE 3	SQFT	339.75
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	249.00
73300200	OVERHEAD SIGN STRUCTURE - SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	94.00
73301810	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	41.00
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CUYD	25.00
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	2.00
X6340205	GUARD POST REMOVAL	EACH	10.00
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	6.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	2.00

Note: new end supports are included in the cost of OVERHEAD SIGN STRUCTURE - SPAN per Section 733 of the Std. Specs.

Pay Item for CMS is for the advanced interstate notice only. CMS shown on Standards are included in the cost of the Standard.

Location No.	5-04		
Structure No.	5 B 010 U045 L012.58		
County / Route	CHAMPAIGN CO. - Cunningham Ave. / US 45 SB under I-74 bridge 010-0024		
Scope of Work	This bridge mounted truss is to be removed & replaced with a breakaway ground mount.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	0.14
72000300	SIGN PANEL - TYPE 3	SQFT	63.25
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	55.00
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	457.50
73400100	CONCRETE FOUNDATIONS	CUYD	1.40
73602000	REMOVE OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	EACH	1.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00

Electric Service Disconnect shall also include removal of all conduit and attachment clamps along the bottom flange of the fascia beam.

Location No.	5-06		
Structure No.	5 S 010 I057 R236.14		
County / Route	CHAMPAIGN CO. - I-57 NB - at Mile Marker 233.7 between Curtis Rd. & I-72		
Scope of Work	This overhead sign structure is being replaced on new drilled shaft foundations.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
64300450	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2.00
64301090	ATTENUATOR BASE	SQYD	102.00
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1.00
72000300	SIGN PANEL - TYPE 3	SQFT	433.00
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	430.50
73300200	OVERHEAD SIGN STRUCTURE - SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	75.00
73301810	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	39.00
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CUYD	25.00
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	2.00
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1.00
X6340205	GUARD POST REMOVAL	EACH	8.00
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	6.00
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	2.00

Note: new end supports are included in the cost of OVERHEAD SIGN STRUCTURE - SPAN per Section 733 of the Std. Specs.

Pay Item for CMS is for the advanced interstate notice only. CMS shown on Standards are included in the cost of the Standard.

- VARIOUS
- D-5 OVD SIN STR REPL 2012-06

FILE NAME =	USER NAME = ceerlookjd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES CHAMPAIGN COUNTY – INDIVIDUAL LOCATIONS</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\pw_work\pwidot\ceerlookjd\0266557\046179-shr-schedule.dgn	DRAWN -	REVISED -	•			••	Various	178	23	
PLOT SCALE = 40.0000' / in.	CHECKED -	REVISED -	CONTRACT NO. 46179							
PLOT DATE = 10/7/2011	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							
				SCALE: N/A	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.			