

**SCHEDULE OF QUANTITIES**  
**MCLEAN COUNTY – S.W. SPAGHETTI BOWL – INDIVIDUAL LOCATIONS**  
**SHEET 2 OF 2**

Location No.	5-12		
Structure No.	5 C 057 U055 L000.40		
County / Route	MCLEAN CO. - SB Business Loop 55 / Veterans Pkwy - over the off-ramp to I-74 EB		
Scope of Work	This overhead cantilever is being replaced on a new drilled shaft foundation.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
70100315	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	EACH	1.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	3.00
72000300	SIGN PANEL - TYPE 3	SQFT	120.00
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	92.00
73301840	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A	FOOT	21.00
73302170	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (36" X 5'-6")	FOOT	27.00
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CUYD	9.50
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	1.00
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	1.00

Prop. fdn. depths and elev. take into account a future profile adjustment of 1.5'. No changes to fdn. depths or top elev. will be allowed.

Location No.	5-13		
Structure No.	5 S 057 U055 L001.70		
County / Route	MCLEAN CO. - SB Bus Loop 55 / Vets Pkwy - between Fox Creek Rd & Morris Ave		
Scope of Work	This overhead sign truss is to be removed & replaced with a breakaway ground mount.		
CODE NUMBER	PAY ITEM	UNIT	QUANTITY
63200310	GUARDRAIL REMOVAL	FOOT	387.00
70100315	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	EACH	1.00
72000300	SIGN PANEL - TYPE 3	SQFT	59.50
72400330	REMOVE SIGN PANEL - TYPE 3	SQFT	333.50
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	521.25
73400100	CONCRETE FOUNDATIONS	CUYD	1.40
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	2.00
84500120	REMOVAL OF ELECTRICAL SERVICE INSTALLATION	EACH	1.00

- VARIOUS
- D-5 OVD SIN STR REPL 2012-06

FILE NAME =	USER NAME = ceerlookjd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES MCLEAN COUNTY – S.W. SPAGHETTI BOWL – INDIVIDUAL LOCATIONS</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ce:\pw\work\p\midot\ceerlookjd\0266557\0266557-46179-sht-schedule.dgn		DRAWN -	REVISED -		SCALE: N/A	SHEET NO. 2 OF 2 SHEETS	STA.	TO STA.	*	**	Various	178	60
PLOT SCALE = 40.0000' / 1" =		CHECKED -	REVISED -							CONTRACT NO. 46179			
PLOT DATE = 10/7/2011		DATE -	REVISED -							ILLINOIS FED. AID PROJECT			