

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION  
Schedule of Quantities

Location No.: 1		State I.D. No.: 6S084I055R099.4					
County:	SANGAMON	Route:	I-55	M.P.:	99.4	Direction:	NB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
OVERHEAD SIGN STRUCTURE-SPAN, TYPE I-A	FOOT	65.00					
REMOVE SIGN PANEL - TYPE 3	SQ FT	344.50					
REMOVE & REINSTALL WALKWAY	FOOT	37.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	8.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	13.40					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00					
REMOVE SAFETY CHAIN	EACH	2.00					
STEEL PLATE BEAM GUARD RAIL, TYPE A 6 FT POSTS	FOOT	25.00					
REMOVE REERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, (TANG	EACH	1.00					
DISCONNECT SIGN LIGHTING AND REMOVE WIRING TO NEARSET SPLICE	EACH	1.00					
CONSTRUCTION LAYOUT	L SUM	0.17					
NIGHTTIME WORK ZONE LIGHTING	L SUM	0.17					
GUARDRAIL MARKERS, TYPE A	EACH	2.00					
FURNISH & ERECT SIGN PANEL	SQ FT	339.00					
SAFETY CHAIN	EACH	2.00					
DRILLED SHAFT IN ROCK	CU YD	5.40					
This structure is being completely replaced.							

Location No.: 2		State I.D. No.: 6S084I072L104.2					
County:	SANGAMON	Route:	I-72	M.P.:	104.2	Direction:	WB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A	FOOT	116.00					
REMOVE SIGN PANEL - TYPE 3	SQ FT	608.75					
REMOVE & REINSTALL WALKWAY	FOOT	56.75					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	12.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	10.40					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00					
REMOVE SAFETY CHAIN	EACH	2.00					
STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FT POSTS	FOOT	25.00					
REMOVE REERECT TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1.00					
DISCONNECT SIGN LIGHTING AND REMOVE WIRING TO NEAREST SPLICE	EACH	1.00					
CONSTRUCTION LAYOUT	L SUM	0.17					
NIGHTTIME WORK ZONE LIGHTING	L SUM	0.17					
GUARDRAIL MARKERS, TYPE A	EACH	2.00					
FURNISH & ERECT SIGN PANEL	SQ FT	512.75					
SAFETY CHAIN	EACH	2.00					
DRILLED SHAFT IN ROCK	CU YD	8.50					
This structure is being completely replaced.							
REMOVE AND REUSE HOSPITAL SIGN - INCIDENTAL							