

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION  
*Schedule of Quantities*

Location No.: 5		State I.D. No.: 6C0841055L096.4					
County:	SANGAMON	Route:	I-55	M.P.:	96.4	Direction:	SB
Description of Work		Unit	Quantity				
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER		EACH	1.00				
OVERHEAD SIGN STRUCTURE-CANTILEVER, TYPE III-C-A		FOOT	35.00				
REMOVE SIGN PANEL - TYPE 3		SQ FT	166.25				
REMOVE & REINSTALL WALKWAY		FOOT	20.00				
REPAIR HANDRAIL LOCKING PIN CONNECTION		EACH	4.00				
DRILLED SHAFT CONCRETE FOUNDATIONS		CU YD	8.00				
REMOVE CONCRETE FOUNDATION-OVERHEAD		EACH	1.00				
REMOVE SAFETY CHAIN		EACH	2.00				
STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FT POSTS		FOOT	25.00				
FURNISH AND ERECT SIGN PANEL		SQ FT	165.00				
REMOVE REERECT TRAFFIC BARRIER TERMINAL, TYPE 2		EACH	1.00				
DISCONNECT SIGN LIGHTING AND REMOVE WIRING TO NEAREST SPLICE		EACH	1.00				
CONSTRUCTION LAYOUT		L SUM	0.17				
NIGHTTIME WORK ZONE LIGHTING		L SUM	0.17				
GUARDRAIL MARKERS, TYPE A		EACH	2.00				
RELOCATE & REINSTALL VIDEO CAMERA & EQUIPMENT		EACH	1.00				
SAFETY CHAIN		EACH	2.00				
TREE REMOVAL (OVER 15 UNITS DIAMETER)		UNIT	1.00				
This structure is being completely replaced							

Location No.: 6		State I.D. No.: 6C0841055R096.5					
County:	SANGAMON	Route:	I-55	M.P.:	96.5	Direction:	NB
Description of Work		Unit	Quantity				
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER		EACH	1.00				
OVERHEAD SIGN STRUCTURE-CANTILEVER, TYPE III-C-A		FOOT	35.00				
REMOVE SIGN PANEL - TYPE 3		SQ FT	203.50				
REMOVE & REINSTALL WALKWAY		FOOT	22.00				
REPAIR HANDRAIL LOCKING PIN CONNECTION		EACH	5.00				
DRILLED SHAFT CONCRETE FOUNDATIONS		CU YD	9.10				
REMOVE CONCRETE FOUNDATION-OVERHEAD		EACH	1.00				
REMOVE SAFETY CHAIN		EACH	2.00				
STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FT POSTS		FOOT	25.00				
FURNISH AND ERECT SIGN PANEL		SQ FT	228.00				
REMOVE REERECT TRAFFIC BARRIER TERMINAL, TYPE 2		EACH	1.00				
DISCONNECT SIGN LIGHTING AND REMOVE WIRING TO NEAREST SPLICE		EACH	1.00				
CONSTRUCTION LAYOUT		L SUM	0.15				
NIGHTTIME WORK ZONE LIGHTING		L SUM	0.15				
GUARDRAIL MARKERS, TYPE A		EACH	2.00				
SAFETY CHAIN		EACH	2.00				
This structure is being completely replaced.							