

SUMMARY OF QUANTITIES			URBAN				CONSTRUCTION TYPE CODE				SUMMARY OF QUANTITIES			URBAN				CONSTRUCTION TYPE CODE											
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80% FED. 20% STATE	100% MCHENRY CO.	80% FED. 13% STATE 7% COUNTY						CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80% FED. 20% STATE	100% MCHENRY CO.	80% FED. 13% STATE 7% COUNTY											
				0004	0004	0021										0004	0004	0021											
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	11002	11002								* 81400200	HEAVY-DUTY HANDHOLE	EACH	6														
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	360	360								* 81400300	DOUBLE HANDHOLE	EACH	1														
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	550	550								* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	665														
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	272	272								* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1														
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	78	78								* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1613														
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	12034	12034								* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	672														
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	76	76								* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1208														
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	5035	5035								* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	56														
* 72000100	SIGN PANEL - TYPE 1	SO FT	89.5	73					16.5			* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	453														
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	1	1								* 87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	4														
* 72900100	METAL POST - TYPE A	FOOT	176	176								* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	1														
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	154.8	154.8								* 87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	1														
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11002	11002								* 87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	1														
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	360	360								* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	20														
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	550	550								* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4														
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	272	272								* 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	10														
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	78	78								* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	13														
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	111	111								* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	3														
* 78200420	GUARDRAIL MARKERS, TYPE B	EACH	2	2								* 88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	3														
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1	1								* 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	1														
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	59	59								* 88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1														
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	510						510			* 88030310	SIGNAL HEAD, LED, 3-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1														
81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	87						87			* 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	4														
81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	52						52			* 88500100	INDUCTIVE LOOP DETECTOR	EACH	5														
81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	104						104			* 88600100	DETECTOR LOOP, TYPE I	FOOT	470														
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	167						167			* A2002920	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	5	5													
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	222						222																				
* 81400100	HANDHOLE	EACH	1						1																				

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ILLINOIS ROUTE 120 AT FLEMING ROAD
SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
333	15-N-6	MCHENRY	67	4
CONTRACT NO.			60L27	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

Rev. 1-4-12