

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80% FED. 20% STATE IL. 120 ROADWAY 0004	100% MCHENRY CO. FLEMING RD. ROADWAY 0004	80% FED. 13% STATE 7% COUNTY TRAFFIC SIGNAL 0021				URBAN TOTAL QUANTITIES	80% FED. 20% STATE IL. 120 ROADWAY 0004	100% MCHENRY CO. FLEMING RD. ROADWAY 0004	80% FED. 13% STATE 7% COUNTY TRAFFIC SIGNAL 0021			
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) (TANGENT)	EACH	1	1						40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	723	723		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	160	24	136					40701876	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9 3/4"	SO YD	3306		3306	
20101100	TREE TRUNK PROTECTION	EACH	5		5					42001300	PROTECTIVE COAT	SO YD	107	29	78	
20101200	TREE ROOT PRUNING	EACH	11	4	7					44000100	PAVEMENT REMOVAL	SO YD	4464		4464	
20200100	EARTH EXCAVATION	CU YD	8302	4020	4282					44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	5845	5845		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	409	334	75					44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	458	253	205	
20800150	TRENCH BACKFILL	CU YD	33	16	17					44004250	PAVED SHOULDER REMOVAL	SO YD	2506	1811	695	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SO YD	1249		1249					44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	350	350		
* 21101625	TOPSOIL FURNISH AND PLACE, 6"	SO YD	3735	3170	565					44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	525	525		
* 25000210	SEEDING, CLASS 2A	ACRE	0.7	0.55	0.15					44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	876	876		
* 25000300	SEEDING, CLASS 3	ACRE	0.2	0.2						44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2470	1450	1020	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	82	68	14					48101600	AGGREGATE SHOULDERS, TYPE B 8"	SO YD	1197	845	352	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	82	68	14					48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	5		5	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	82	68	14					48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	1510	1045	465	
* 25100630	EROSION CONTROL BLANKET	SO YD	3735	3170	565					50105220	PIPE CULVERT REMOVAL	FOOT	170	123	47	
25100900	TURF REINFORCEMENT MAT	SO YD	12		12					54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2		2	
* 25200110	SODDING, SALT TOLERANT	SO YD	3735	3170	565					54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	9	8	1	
* 25200200	SUPPLEMENTAL WATERING	UNIT	38	32	6					54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1		1	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	80	65	15					542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	90		90	
28000305	TEMPORARY DITCH CHECKS	FOOT	420	320	100					542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	199	199		
28000400	PERIMETER EROSION BARRIER	FOOT	4985	3270	1715					542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	83		83	
28000500	INLET AND PIPE PROTECTION	EACH	14	8	6					60107600	PIPE UNDERDRAINS 4"	FOOT	299	200	99	
28100105	STONE RIPRAP, CLASS A3	SO YD	550	435	115					60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1		1	
28200200	FILTER FABRIC	SO YD	550	435	115					60600095	CLASS SI CONCRETE (OUTLET)	CU YD	2		2	
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SO YD	634	414	220					63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	50	50		
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SO YD	419	419						63200310	GUARDRAIL REMOVAL	FOOT	50	50		
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	422	275	147					67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	2	4	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	9	6	3					67100100	MOBILIZATION	L SUM	1	0.25	0.75	
40600300	AGGREGATE (PRIME COAT)	TON	39	25	14					70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	1	4	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	14	9	5					70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1	0.25	0.75	
40600895	CONSTRUCTING TEST STRIP	EACH	2	1	1					70300100	SHORT TERM PAVEMENT MARKING	FOOT	942	217	725	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	62	40	22					70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	154.8	77.4	77.4	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	74	48	26											

\* SPECIALTY ITEMS

FILE NAME =	USER NAME = gabanjr	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>ILLINOIS ROUTE 120 AT FLEMING ROAD</b> <b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE. 333	SECTION 15-N-6	COUNTY MCHENRY	TOTAL SHEETS 37	SHEET NO. 3
CONTRACT NO. 60L27	SCALE:	SHEET NO. OF SHEETS	STA. TO STA.			FED. ROAD DIST. NO. 1	ILLINOIS FED. AID PROJECT			
PLOT SCALE = 50,000' / 1" /	CHECKED -	REVISED -								
PLOT DATE = 10/25/2011	DATE -	REVISED -								