

SUMMARY OF QUANTITIES			URBAN	100% CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			URBAN	100% CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80% FED. 20% STATE IL. 120 ROADWAY 0004	MCHENRY CO. FLEMING RD. ROADWAY 0004	80% FED. 13% STATE 7% COUNTY TRAFFIC SIGNAL 0021	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80% FED. 20% STATE IL. 120 ROADWAY 0004	MCHENRY CO. FLEMING RD. ROADWAY 0004	80% FED. 13% STATE 7% COUNTY TRAFFIC SIGNAL 0021
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	11002	7330	3672		* 81400200	HEAVY-DUTY HANDHOLE	EACH	6			6
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	360	280	80		* 81400300	DOUBLE HANDHOLE	EACH	1			1
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	550	550			* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	665			665
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	272	157	115		* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1			1
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	78	46	32		* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1613			1613
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	12034		12034		* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	672			672
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	76		76		* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1208			1208
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	5035	2905	2130		* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	56			56
* 72000100	SIGN PANEL - TYPE 1	SO FT	89.5	12	61	16.5	* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	453			453
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	1		1		* 87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	4			4
* 72900100	METAL POST - TYPE A	FOOT	176	32	144		* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	1			1
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	154.8	77.4	77.4		* 87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	1			1
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11002	7330	3672		* 87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	1			1
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	360	280	80		* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	20			20
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	550		550		* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4			4
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	272	157	115		* 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	10			10
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	78	46	32		* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	13			13
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	111	66	45		* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	3			3
* 78200420	GUARDRAIL MARKERS, TYPE B	EACH	2	2			* 88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	3			3
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1	1			* 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	1			1
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	59	59			* 88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1			1
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	510		510		* 88030310	SIGNAL HEAD, LED, 3-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1			1
81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	87		87		* 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	4			4
81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	52		52		* 88500100	INDUCTIVE LOOP DETECTOR	EACH	5			5
81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	104		104		* 88600100	DETECTOR LOOP, TYPE I	FOOT	470			470
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	167		167		* A2002920	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	5		5	
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	222		222								
* 81400100	HANDHOLE	EACH	1			1							

* SPECIALTY ITEMS

* SPECIALTY ITEMS

FILE NAME =	USER NAME = galbanjr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				ILLINOIS ROUTE 120 AT FLEMING ROAD SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cd:\work\pwl\dd\galbanjr\1007803\FR3707-Des\gndm		DRAWN -	REVISED -									333	15-N-6	MCHENRY	67	4
PLOT SCALE = 50,000' / 1"		CHECKED -	REVISED -									CONTRACT NO. 60L27				
PLOT DATE = 10/3/2011		DATE -	REVISED -									FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				