

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	80% FED. 20% STATE 0005						CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	80% FED. 20% STATE 0005					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	655	655						67100100	MOBILIZATION	L SUM	1	1					
25200110	SODDING, SALT TOLERANT	SO YD	655	655						70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	42	42						70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
40600300	AGGREGATE (PRIME COAT)	TON	202	202						70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	76	76						70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1793	1793						70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2						70300100	SHORT TERM PAVEMENT MARKING	FOOT	6558	6558					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	155	155						70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	795	795					
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	1850	1850						70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	24420	24420					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	10	10						70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4475	4475					
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	135	135						70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	200	200					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	5115	5115						70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1000	1000					
42001300	PROTECTIVE COAT	SO YD	2408	2408						70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	510	510					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	2344	2344						70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1052	1052					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	5915	5915					*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	795	795					
44000600	SIDEWALK REMOVAL	SO FT	2344	2344					*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	24420	24420					
44002210	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 1/2"	SO YD	70	70					*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4475	4475					
44003100	MEDIAN REMOVAL	SO FT	3720	3720					*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	200	200					
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SO FT	26900	26900					*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1000	1000					
44022029	PARTIAL DEPTH REMOVAL 3"	SO YD	800	800					*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	510	510					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	1354	1354					*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	700	700					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	556	556					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	315	315						
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	546	546					*	88600600	DETECTOR LOOP REPLACEMENT	FOOT	1508	1508					
60250200	CATCH BASINS TO BE ADJUSTED	EACH	34	34					89502378	REBUILD EXISTING HANDHOLE TO HEAVY-DUTY HANDHOLE	EACH	4	4						
60251740	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	4	4					X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SO YD	119	119						
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1															
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1															
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1															
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	36	36															
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	10	10															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															