

ROUTE: IL 38: Roosevelt Rd (Mannheim Rd to Center St) - Jointed Pavement PATCHING = CLASS B

CROSSSTREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
FROM	TO						
Roosevelt		EB	3	12	11	132	15
	Mannheim	EB	1, 2, TL	22	6	132	15
Mannheim		WB	1, 2	25	7	175	19
	Roosevelt	WB	3	10	6	60	7
Intersection at	Mannheim	EB	1	12	12	144	16
		EB	LTL	12	6	72	8
		EB	1	12	10	120	13
		EB	2	12	6	72	8
		EB	LTL 1	12	6	72	8
		EB	LTL 2	12	6	72	8
		WB	1	12	8	96	11
		WB	2	12	7	84	9
		WB	3	12	6	72	8

MAINLINE QUANTITIES: 69 30 55  
 INTERSECTION QUANTITIES: 108 67 89  
 TOTALS: 177 97 145  
 FT FT SY

ROUTE: Ramp (IL 50: Cicero Ave to US 34: Ogden Ave) - Jointed Pavement PATCHING = CLASS B

CROSSSTREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
FROM	TO						
		WB	LTL 2	6	12	72	8
		WB	L2	6	12	72	8
		WB	L1	6	8	48	5
		EB	L1	6	8	48	5

TOTALS: 40 27  
 FT SY

ROUTE: IL 171: Archer Ave (55th St to 65th St) - Jointed Pavement PATCHING = CLASS B

CROSSSTREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
FROM	TO						
58th St		EB	L1	6	8	48	5
58th St		EB	L2	20	6	120	13
58th St		EB	L2	6	12	72	8
58th St		EB	L1	10	10	100	11

TOTALS: 36 38  
 FT SY

ROUTE: Mannheim Rd (IL 38: Roosevelt Rd to 50 ft south) - Jointed Pavement PATCHING = CLASS B

CROSSSTREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
FROM	TO						
Roosevelt		SB	1,2,3	36	11	396	44
	50' south	SB	3,4	11	50	550	61
50' south	Roosevelt	NB	Tlane	9	6	54	6
Intersection at	IL 38: Roosevelt Rd	NB	LTL	12	6	72	8
		NB	LTL	8	6	48	5
		SB	1	12	10	120	13
		SB	2	12	10	120	13
		SB	3	16	12	192	21

MAINLINE QUANTITIES: 56 67 111  
 INTERSECTION QUANTITIES: 60 44 61  
 TOTALS: 116 111 172  
 FT FT SY

ROUTE: First Ave (North Ave to Chicago Ave) - Jointed Pavement PATCHING = CLASS B

CROSSSTREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
FROM	TO						
Chicago Ave.		NB	1	12	9	108	12
		NB	1	12	6	72	8
	North Ave	NB	2	12	6	72	8
North Ave	Chicago Ave.	SB	2	12	6	72	8
Intersection at	Chicago Ave.	SB	2	12	8	96	11
		SB	2	12	8	96	11
Intersection at	North Ave.	WB	RTL	12	10	120	13
		SB	1 & 2	24	6	144	16
		SB	2	12	6	72	8

MAINLINE QUANTITIES: 48 27 36  
 INTERSECTION QUANTITIES: 72 38 59  
 TOTALS: 120 65 95  
 FT FT SY

FILE NAME =	USER NAME = velichkovv	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>PATCHING SCHEDULE</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\velichkovv\40259794\design.dgn		DRAWN -	REVISED -		<b>ARCHER AVE, IL 50 RAMP, MANNHEIM RD, IL 38, IL 171 &amp; FIRST AVE</b>			VAR.	2011-002-PP	COOK	22	6
PLOT SCALE = 100.0000 / 1 in.		CHECKED -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	<b>CONTRACT NO. 60N90</b>	
PLOT DATE = 9/26/2011		DATE -	REVISED -					FED. ROAD DIST. NO. 1   ILLINOIS   FED. AID PROJECT				