

SCHEDULE OF QUANTITIES - SIGNS

SIGN	SIGN PANEL ASSEMBLY REMOVAL (EACH)	SIGN ID #	SIZE (inches)	SIGN PANEL TYPE 1 (SQ.FT.)
Illinois/Adopt-A-Highway	1	I-107	30 x 36	7.5
Speed Limit	8	R2-1	24 x 30	40
Intersection Warning	3	W2-2R	30 x 30	18.75
Intersection Warning	2	W2-2L	30 x 30	12.5
Advance Street Name (1-line)	5	W16-8P	24 x 9	7.5
Stop	5	R1-1	30 x 30	31.25
Object Marker (Type 2)	1	N/A	6 x 12	0.5
Unlawful to Pass School Bus	2	S4-I105	30 x 30	12.5
No Parking (On Shoulder)	1	R8-2a	24 x 30	5
No Passing Zone (pennant)	4	W14-3	48 x 48 x 36	16
Cardinal Direction	1	M3-1	24 x 12	2
Illinois Route Sign (2 digits)	1	M1-I100	24 x 24	4
Truck	1	W11-10	30 x 30	6.25
Horizontal Alignment	1	W1-2L	30 x 30	6.25
Horizontal Alignment	2	W1-4R	30 x 30	12.5
Accident Marker	1	XM-1	18 x 18	2.25
Total	39			184.75

NOTES:

ALL SIGN PANELS AND SIGN SUPPORTS ARE TO BE REPLACED BETWEEN STATION 500+00 AND STATION 592+32.

SIGN LOCATIONS AS SHOWN IN THE PLANS ARE APPROXIMATE AND ARE TO BE FIELD VERIFIED PRIOR TO REMOVAL.