January 10, 2012

SUBJECT: FAU Route 2937 (IL 83)

Project HSIP-2937 (005) Section 2011-040-TS

Cook County

Contract No. 60P46

Item No. 18, January 20, 2012 Letting

Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- Replaced the Schedule of Prices.
- Revised the Table of Contents to the Special Provisions.
- 3. Added pages 124 125 to the Special Provisions.
- 4. Revised sheets 2, 3, 10 & 12 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.

Acting Engineer of Design and Environment

By: Ted B. Walschleger, P. E.

Tet Deluklye A.E.

Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Mike Renner; Estimates

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT NUMBER - 60P46

State Job # - C-91-544-11

PPS NBR - 1-78672-0000

County Name - COOK- -

Code - 31 - -

District - 1 - Section Number - 2011-040-TS

Project Number

HSIP-2937/005/

Route

FAU 2937

*REVISED: JANUARY 05, 2012

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|----------------|-----------------------|--------------------|-----------|---|------------|---|-------------|
| X8620200 | UNINTER POWER SUP SPL | EACH | 1.000 | | | | |
| X8730250 | ELCBL C 20 3C TW SH | FOOT | 250.000 | | | | |
| Z0030850 | TEMP INFO SIGNING | SQ FT | 51.400 | | | | |
| Z0073510 | TEMP TR SIGNAL TIMING | EACH | 1.000 | | | | |
| * ADD 66900200 | NON SPL WASTE DISPOSL | CU YD | 45.000 | | | | |
| * ADD 66900450 | SPL WASTE PLNS/REPORT | L SUM | 1.000 | | | | |
| * ADD 66900530 | SOIL DISPOSAL ANALY | EACH | 6.000 | | | | |
| * REV 67000400 | ENGR FIELD OFFICE A | CAL MO | 6.000 | | | | |
| 67100100 | MOBILIZATION | L SUM | 1.000 | | | | |
| 70102620 | TR CONT & PROT 701501 | L SUM | 1.000 | | | | |
| 70102635 | TR CONT & PROT 701701 | L SUM | 1.000 | | | | |
| 72000100 | SIGN PANEL T1 | SQ FT | 35.500 | | | | |
| 78000200 | THPL PVT MK LINE 4 | FOOT | 1,121.000 | | | | |
| 78000600 | THPL PVT MK LINE 12 | FOOT | 39.000 | | | | |
| 78000650 | THPL PVT MK LINE 24 | FOOT | 127.000 | | | | |

ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT 60P46 **NUMBER -**

*REVISED: JANUARY 05, 2012

C-91-544-11 State Job # -

PPS NBR -1-78672-0000

County Name -COOK--Code -31 - -

1 - -District -

Section Number - 2011-040-TS

Project Number

HSIP-2937/005/

Route

FAU 2937

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|----------------|-----------------------|--------------------|-----------|---|------------|---|-------------|
| 78300100 | PAVT MARKING REMOVAL | SQ FT | 176.000 | | | | |
| 81028200 | UNDRGRD C GALVS 2 | FOOT | 1,473.000 | | | | |
| 81028210 | UNDRGRD C GALVS 2 1/2 | FOOT | 108.000 | | | | |
| 81028220 | UNDRGRD C GALVS 3 | FOOT | 57.000 | | | | |
| 81028240 | UNDRGRD C GALVS 4 | FOOT | 241.000 | | | | |
| 81400100 | HANDHOLE | EACH | 4.000 | | | | |
| 81400200 | HD HANDHOLE | EACH | 9.000 | | | | |
| 81400300 | DBL HANDHOLE | EACH | 1.000 | | | | |
| 85700200 | FAC T4 CAB | EACH | 1.000 | | | | |
| 87301225 | ELCBL C SIGNAL 14 3C | FOOT | 250.000 | | | | |
| 87301245 | ELCBL C SIGNAL 14 5C | FOOT | 1,453.000 | | | | |
| 87301255 | ELCBL C SIGNAL 14 7C | FOOT | 1,367.000 | | | | |
| 87301305 | ELCBL C LEAD 14 1PR | FOOT | 2,175.000 | | | | |
| 87301805 | ELCBL C SERV 6 2C | FOOT | 224.000 | | | | |
| 87301900 | ELCBL C EGRDC 6 1C | FOOT | 791.000 | | | | |

ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT 60P46 **NUMBER -**

C-91-544-11 State Job # -

PPS NBR -1-78672-0000

County Name -COOK--

Code -31 - - **Project Number**

HSIP-2937/005/

Route

FAU 2937

| District - Section Number - | 1 2011-040-TS | *REVISED: JANUARY 05, 2012 | | | | | | |
|--------------------------------|----------------------|----------------------------|----------|---------|------------|--------------|-------|--|
| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total | |
| | <u> </u> | | | | 1 | | ···· | |

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | II | Total Price |
|----------------|-----------------------|--------------------|----------|---|------------|----|-------------|
| 87502480 | TS POST GALVS 14 | EACH | 2.000 | | | | |
| 87502500 | TS POST GALVS 16 | EACH | 2.000 | | | | |
| 87700170 | S MAA & P 26 | EACH | 2.000 | | | | |
| 87700210 | S MAA & P 34 | EACH | 1.000 | | | | |
| 87700220 | S MAA & P 36 | EACH | 1.000 | | | | |
| 87800100 | CONC FDN TY A | FOOT | 12.000 | | | | |
| 87800150 | CONC FDN TY C | FOOT | 4.000 | | | | |
| 87800400 | CONC FDN TY E 30D | FOOT | 20.000 | | | | |
| 87800415 | CONC FDN TY E 36D | FOOT | 22.000 | | | | |
| 88030020 | SH LED 1F 3S MAM | EACH | 4.000 | | | | |
| 88030050 | SH LED 1F 3S BM | EACH | 2.000 | | | | |
| 88030110 | SH LED 1F 5S MAM | EACH | 4.000 | | | | |
| 88030240 | SH LED 2F 1-3 1-5 BM | EACH | 4.000 | | | | |
| 88200210 | TS BACKPLATE LOU ALUM | EACH | 8.000 | | | | |
| 88500100 | INDUCTIVE LOOP DETECT | EACH | 10.000 | | | | |

ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF PRICES CONTRACT NUMBER - 60P46

State Job # - C-91-544-11

PPS NBR - 1-78672-0000 Project Number Route

County Name - COOK- -

HSIP-2937/005/ FAU 2937

Code - 31 - -

District - 1 - - *REVISED: JANUARY 05, 2012

Section Number - 2011-040-TS

| Item Number | Pay Item Description | Unit of Measure | Quantity | х | Unit Price | = | Total Price |
|----------------|----------------------|--------------------|----------|---|------------|---|-------------|
| 88600100 | DET LOOP T1 | FOOT | 660.000 | | | | |
| 88700200 | LIGHT DETECTOR | EACH | 2.000 | | | | |
| 88700300 | LIGHT DETECTOR AMP | EACH | 1.000 | | | | |
| 89000100 | TEMP TR SIG INSTALL | EACH | 1.000 | | | | |
| 89502375 | REMOV EX TS EQUIP | EACH | 1.000 | | | | |
| 89502380 | REMOV EX HANDHOLE | EACH | 8.000 | | | | |
| 89502385 | REMOV EX CONC FDN | EACH | 7.000 | | | | |

TABLE OF CONTENTS

| LOCATION OF PROJECT | 1 |
|---|-----|
| DESCRIPTION OF PROJECT | 1 |
| TEMPORARY INFORMATION SIGNING | 1 |
| TRAFFIC CONTROL PLAN | 2 |
| REMOVE EXISTING HANDHOLE | 3 |
| REMOVE EXISTING CONCRETE FOUNDATION | 3 |
| TRAFFIC SIGNAL SPECIFICATIONS | 3 |
| TEMPERATURE CONTROL FOR CONCRETE PLACEMENT (DISTRICT ONE) | 54 |
| AGREEMENT TO PLAN QUANTITY (BDE) | |
| CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE) | |
| CONSTRUCTION AIR QUALITY - DIESEL VEHICLE EMISSIONS CONTROL (BDE) | |
| CONSTRUCTION AIR QUALITY - IDLING RESTRICTIONS (BDE) | 57 |
| DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) | |
| PAYMENTS TO SUBCONTRACTORS (BDE) | |
| PORTLAND CEMENT CONCRETE (BDE) | |
| QUALITY CONTROL/QUALITY ASSURANCE OF CONCRETE MIXTURES (BDE) | 103 |
| SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) | 114 |
| TRAFFIC CONTROL DEFICIENCY DEDUCTION (BDE) | 114 |
| UTILITY COORDINATION AND CONFLICTS (BDE) | |
| WORKING DAYS (BDE) | |
| STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) | 120 |
| PAVEMENT MARKING REMOVAL (BDE) | |
| REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE) | 124 |
| REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES | 124 |

Revised 01/10/12

FAU 2937 (IL 83) Project HSIP-2937 (005) Section 2011-040 TS Cook County Contract 60P46

PAVEMENT MARKING REMOVAL (BDE)

Effective: April 1, 2009

Add the following to the end of the first paragraph of Article 783.03(a) of the Standard Specifications:

"The use of grinders will not be allowed on new surface courses."

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)

Effective: January 1, 2012

Revise Article 669.01 of the Standard Specifications to read:

"669.01 Description. This work shall consist of the transportation and proper disposal of contaminated soil and water. This work shall also consist of the removal, transportation, and proper disposal of underground storage tanks (UST), their content and associated underground piping to the point where the piping is above the ground, including determining the content types and estimated quantities."

Revise the second paragraph of Article 669.16 of the Standard Specifications to read:

"The transportation and disposal of soil and other materials from an excavation determined to be contaminated will be paid for at the contract unit price per cubic yard (cubic meter) for NON-SPECIAL WASTE DISPOSAL, OR HAZARDOUS WASTE DISPOSAL."

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES

This work shall be according to Article 669 of the Standard Specifications and the following:

Qualifications. The term environmental firm shall mean an environmental firm with at least five (5) documented leaking underground storage tank (LUST) cleanups or that is pre-qualified in hazardous waste by the Department. Documentation includes but not limited to verifying remediation and special waste operations for sites contaminated with gasoline, diesel, or waste oil in accordance with all Federal, State, or local regulatory requirements and shall be provided to the Engineer for approval. The environmental firm selected shall not be a former or current consultant or have any ties with any of the properties contained within and/or adjacent to this construction project.

<u>General.</u> This Special Provision will likely require the Contractor to subcontract for the execution of certain activities.

All contaminated materials shall be managed as non-special waste. <u>This work shall include monitoring and potential sampling, analytical testing, and management of a material contaminated by regulated substances.</u>

Added 01/10/12

FAU 2937 (IL 83) Project HSIP-2937 (005) Section 2011-040 TS Cook County Contract 60P46

- A) The Environmental Firm shall continuously monitor for worker protection and the Contractor shall manage any excavated soils within the construction limits of this project as fill. All storm sewer excavated soils can be placed back into the excavated trench as backfill unless trench backfill is specified. If the soils cannot be utilized within the construction limits as fill then they must be managed off-site as a non-special waste. The following areas can be managed within the construction limits as fill.
 - 1. All excavated soils (Site 2422-1, -2, -6, -7, -8, and -9) non-special waste. Contaminants of concern sampling parameters: VOCs, SVOCs, and Metals.

Added 01/10/12