

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE		CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005						CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	15	15						Δ 20018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	2	2					
40600300	AGGREGATE (PRIME COAT)	TON	75	75						20030850	TEMPORARY INFORMATION SIGNING	SO FT	102.8	102.8					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	28	28						60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	3	3					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1						X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	3	3					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	124	124						21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	60	60					
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	80	80						25200110	SODDING, SALT TOLERANT	SQ YD	60	60					
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1589	1589															
42001300	PROTECTIVE COAT	SO YD	137	137															
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	17460	17460															
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SO YD	374	374															
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SO YD	281	281															
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SO YD	281	281															
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	217	217															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4															
67100100	MOBILIZATION	L SUM	1	1															
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1															
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1															
70300100	SHORT TERM PAVEMENT MARKING	FOOT	3700	3700															
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	18350	18350															
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	26	26															
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	411	411															
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	18350	18350															
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	26	26															
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	131	131															
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	111	111															
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	106	106															
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD) IL-4.75, N50	TON	781	781															
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SO YD	282	282															
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	410	410															

Δ NON-PARTICIPATING (100% STATE)