



ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
VARIOUS	2011-062-I	WILL & COOK	22	2

INDEX OF SHEETS

- 1 TITLE SHEET
- 2 INDEX OF SHEETS, STATE STANDARDS AND GENERAL NOTES
- 2A GENERAL NOTES
- 3 SUMMARY OF QUANTITIES
- 4-7 LOCATION MAPS
- 8-10 BRIDGE PLANS LOCATION 1 (SN 016-0133)
- 11-15 BRIDGE PLANS LOCATION 2 (SN 016-0121) & LOCATION 3 (SN 016-0122)
- 16 BRIDGE PLANS LOCATION 4 (SN 016-2405)
- 17 BRIDGE PLANS LOCATION 5 (SN 099-9904)
- 18 BRIDGE PLANS LOCATION 6 (SN 099-0101)
- 19 BRIDGE PLANS LOCATION 7 (SN 099-0239)
- 20 BRIDGE PLANS LOCATION 8 (SN 099-0166)
- 21 BRIDGE PLANS LOCATION 9 (SN 099-9903)
- 22 ARTERIAL ROAD INFORMATION SIGN (TC-22)

STATE STANDARDS

- 701006-03  LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
- 701301-04
- 701101-02  URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
- 701501-06
- 701601-07 URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN
- 701606-08 URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
- 701801-05
- 701901-02 TRAFFIC CONTROL DEVICES

CONTRACTOR TO COORDINATE WITH ILLINOIS DEPARTMENT OF TRANSPORTATION BUREAU OF LAND ACQUISITION, PROPERTY MANAGEMENT SECTION, MIKE CULLIAN AT (847) 705-4280 AT LEAST 14 DAYS PRIOR TO BEGINNING WORK.

GENERAL NOTES

CONTRACT NO: 60P81

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" (JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION) AT 800-892-0123 OR 811 OR "CUAN" (CHICAGO UTILITY ALERT NETWORK) AT 312-744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE & GAS FACILITIES. (48 HOURS NOTIFICATION REQUIRED)

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES, THE CITIES OF CHICAGO AND JOLIET, AND THE VILLAGE OF WORTH.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE OR TOLLWAY PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 FOR ARTERIALS A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

IT SHALL BE THE CONTRACTORS' RESPONSIBILITY TO VERIFY ALL DIMENSIONS & CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION & ORDERING OF MATERIAL.

THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.

DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.


CONTRACTOR SHALL REMOVE OR FIRMLY ATTACH ANY TRAFFIC CONTROL DEVICES TO THE BASCULE BRIDGE DECK THROUGHOUT THE DURATION OF THE IMPROVEMENT, SO THEY WILL NOT FALL OFF THE DECK WHEN THE BRIDGE SPANS ARE RAISED.

THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVED FROM THE BUREAU OF MAINTENANCE, BRIDGE INSPECTORS.

CONTRACTOR SHALL PROVIDE SAFE TEMPORARY ACCESS TO THE TENDER HOUSES THROUGHOUT CONSTRUCTION PERIOD.

ILLINOIS DEPARTMENT OF TRANSPORTATION

INDEX OF SHEETS
STATE STANDARDS
GENERAL NOTES

 Rev. 1-4-12

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
VARIOUS	2011-062-I	WILL & COOK	22	3

CONTRACT NO. 60P81

CONSTRUCTION TYPE CODE 0014

COOK COUNTY

WILL COUNTY

CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	URBAN: 100 % STATE										
				LOC 1: 016-0133	LOC 2: 016-0121	LOC 3: 016-0122	LOC 4: 016-2405	LOC 5: 099-9904	LOC 6: 099-0101	LOC 7: 099-0239	LOC 8: 099-0166	LOC 9: 099-9903		
59200101	BRIDGE WASHING NO. 1	EACH	1	1										
59200102	BRIDGE WASHING NO. 2	EACH	1		1									
59200103	BRIDGE WASHING NO. 3	EACH	1			1								
59200104	BRIDGE WASHING NO. 4	EACH	1				1							
59200105	BRIDGE WASHING NO. 5	EACH	1					1						
59200106	BRIDGE WASHING NO. 6	EACH	1						1					
59200107	BRIDGE WASHING NO. 7	EACH	1							1				
59200108	BRIDGE WASHING NO. 8	EACH	1								1			
59200109	BRIDGE WASHING NO.9	EACH	1										1	
67100100	MOBILIZATION	L SUM	1	0.12	0.11	0.11	0.11	0.11	0.11	0.11	0.11	0.11	0.11	0.11
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1					0.34		0.33				0.33
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	0.5			0.5							
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		0.33	0.33	0.34							
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1		0.17	0.17			0.33			0.33		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	0.25	0.25	0.25	0.25							
Z0015550	DEBRIS REMOVAL	CU YD	115	46	6	6	10							47
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	359.8	51.4	25.7	25.7	51.4	51.4	25.7	51.4	25.7	51.4		
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1				1							

ILLINOIS DEPARTMENT OF
TRANSPORTATION
SUMMARY OF QUANTITIES