SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80% FED. 20% STATE 0005					
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	12	12					
20101000	TEMPORARY FENCE	FOOT	269	269					
20800150	TRENCH BACKFILL	CU YD	2	2					
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	454	454					
21400100	GRADING AND SHAPING DITCHES	FOOT	254	254					
25000210	SEEDING, CLASS 2A	ACRE	0.25	0.25					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	17	17					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	17	17					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	17	17					
25100125	MULCH, METHOD 3	ACRE	0.25	0.25					
25100630	EROSION CONTROL BLANKET	SQ YD	454	454					
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	18	18					
28000305	TEMPORARY DITCH CHECKS	FOOT	30	30					
28000500	INLET AND PIPE PROTECTION	EACH	2	2					
28000510	INLET FILTERS	EACH	6	6					
28100705	STONE DUMPED RIPRAP, CLASS A3	SQ YD	20	20					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	20	20					
44201863	CLASS D PATCHES, TYPE II, 18 INCH	SQ YD	9	9					
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1					
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	1	1					
55100500	STORM SEWER REMOVAL 12"	FOOT	156	156					
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1					
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	1	1					
60500050	REMOVING CATCH BASINS	EACH	1	1					
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	20	20					
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1					
Z0056648	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 12"	FOOT	7	7					
Z0056654	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 24"	FOOT	210	210					

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT							

⚠ Added Sheet 1-5-12

FILE NAME = c:\pw_work\pwidot\tarlqfm\d0273169\D162911-sht-plan.dgn	USER NAME = tarlqfm	DESIGNED -	REVISED - ⚠ FT 12/22/11
		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 12/27/2011	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ILL 53 (75TH STREET TO WILL COUNTY LINE)
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
870	534-RS-5	DUPAGE	19	3A
		CONTRACT NO. 60P91		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT