

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	80% FED. 20% STATE 0005						CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	80% FED. 20% STATE 0005					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	125	125						* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	18405	18405					
25200110	SODDING, SALT TOLERANT	SO YD	125	125						* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	790	790					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	34	34						* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	289	289					
40600300	AGGREGATE (PRIME COAT)	TON	169	169						* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	127	127					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	63	63						* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	403	403					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1744	1744						78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	322	322					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1						* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	454	454					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	122	122						△ X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	300	300					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	4144	4144						X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	25	25					
42001300	PROTECTIVE COAT	SO YD	167	167						Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	750	750					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	42285	42285						△ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	20	20					
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SO YD	760	760						Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4					
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SO YD	126	126															
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SO YD	380	380															
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	10	10															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															
67100100	MOBILIZATION	L SUM	1	1															
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1															
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1															
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1															
70300100	SHORT TERM PAVEMENT MARKING	FOOT	4229	4229															
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	182	182															
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	18405	18405															
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	790	790															
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	289	289															
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	127	127															
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	470	470															
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	182	182															

△ Non-participating (100% STATE)  
\* SPECIALTY ITEM