SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: 07A0L 100% STATE 0005	07C0L 50% STATE 50% CITY OF CHICAGO 0005				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	15	15					
25200110	SODDING, SALT TOLERANT	SQ YD	15	15					
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	123	123					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	11	10	1				
40600300	AGGREGATE (PRIME COAT)	TON	106	97	9				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	40	37	3				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	503	503					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	2753	2549	204				
42001300	PROTECTIVE COAT	SQ YD	521	521					
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	1105	1105					
42400800	DETECTABLE WARNINGS	SQ FT	113	113					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	26420	24339	2081				
44000600	SIDEWALK REMOVAL	SQ FT	1105	1105					
44003100	MEDIAN REMOVAL	SQ FT	2172	2172					
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	12852	12852					
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	167	167					
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	100	100					
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	67	67					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	16	16					
60619121	CONCRETE MEDIAN, TYPE SB-6	SQ FT	2618	2618					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	3831	3831					
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	232	232					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	5979	5979					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	587	587					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: 07A0L 100% STATE 0005	07C0L 50% STATE 50% CITY OF CHICAGO 0005				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1506	1506					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	247	247					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6949	6949					
*72000100	SIGN PANEL - TYPE 1	SQ FT	12	12					
*72900100	METAL POST - TYPE A	FOOT	13	13					
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	232	232					
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5979	5979					
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	587	587					
*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	3006	3006					
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1506	1506					
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	247	247					
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	54	54					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	49	49					
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	976	976					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1159	1073	86				
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	64	64					
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	550	550					
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	80	80					
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					

* SPECIALTY ITEMS

FILE NAME = c:\pw_work\pwidot\steedpa\D145963\D185109-sht-plan.dgn	USER NAME = steedpa	DESIGNED	REVISED
		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 10/24/2011	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL 64 (NORTH AVE.)--ELMWOOD AVE. TO RIDGELAND AVE.;
AUSTIN AVE. TO CENTRAL AVE.

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	2011-076-RS	COOK	34	3

CONTRACT NO. 60R02

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT