F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	130 R-2	DUPAGE,KANE	647	2
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

62410

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS AND IDOT STATE STANDARDS
3	GENERAL NOTES AND PROJECT COMMITMENTS
4-15A	SUMMARY OF QUANTITIES
16-27	TYPICAL SECTIONS
28-49	SCHEDULE OF QUANTITIES
50-53	ALIGNMENT, TIES AND CONTROL POINTS
54-72	ROADWAY PLANS
73-84	ROADWAY PROFILES
85-96	ROADWAY DISTRICT 1 DETAILS
97-146	SUGGESTED STAGES OF CONSTRUCTION AND TRAFFIC CONTROL
147-152	TRAFFIC CONTROL DISTRICT 1 DETAILS
153-163	EROSION CONTROL PLANS
164-180	DRAINAGE AND UTILITY PLANS
181-189	DRAINAGE AND UTILITY PROFILES
△1 190-191A	DRAINAGE DETAILS
192	DRAINAGE DISTRICT 1 DETAILS
193-198	CITY OF ST. CHARLES WATER MAIN REPLACEMENT
199-214	SUE UTILITY DRAWINGS
215-233	RIGHT-OF-WAY PLANS
234-238	RIGHT-OF-WAY PLANS (OMITTED)
239-248	INTERSECTION DETAILS
248A	PAVEMENT SEPARATION JOINT DISTRICT 1 DETAIL
249-258	PAVEMENT JOINTING PLANS
259-271	PAVEMENT MARKING PLANS
272-273	PAVEMENT MARKING DISTRICT 1 DETAILS
274-287	EXISTING SIGNING PLANS
288-309	PROPOSED SIGNING PLANS
310-319	LANDSCAPING PLANS
320	GRADING PLANS - SOUTH POWIS ROAD
321-406B	TRAFFIC SIGNAL AND INTERCONNECT PLANS (OMITTED SHEET NO. 376)
407-414	TRAFFIC SIGNAL DISTRICT 1 DETAILS
415-434	ROADWAY LIGHTING PLANS
435-443	LIGHTING DISTRICT 1 DETAILS
444-499	IL ROUTE 64 OVER EJ&E AND UP RAILROADS BRIDGE PLANS (STRUCTURE NO 022-0190)
500-533	RETAINING WALL PLANS
534-535	TEMPORARY STRUCTURE PLANS
536-545	SOIL BORING PLANS
546-607	CROSS SECTIONS - NORTH AVENUE
608-628	CROSS SECTIONS - NORTH AVENUE (OMITTED)
629-635	CROSS SECTIONS - SOUTH POWIS ROAD
636-640	CROSS SECTIONS - NORTH POWIS ROAD
641-647	CROSS SECTIONS - SMITH AND KAUTZ ROAD

STATE STANDARDS

STANDARD	DESCRIPTION
000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
280001-06	TEMPORARY EROSION CONTROL SYSTEMS
406201-01	MAILBOX TURNOUT
420001-07	PAVEMENT JOINTS
420101-04	24' (7.2 m) JOINTED PCC PAVEMENT
420106-04	36' (10.8 m) JOINTED PCC PAVEMENT
420401-08	BRIDGE APPROACH PAVEMENT CONNECTOR
420601-05	24' (7.2m) PCC PAVEMENT
420701-02	PAVEMENT FABRIC
424001-06	PERPENDICULAR CURB RAMPS FOR SIDEWALKS
424006	DIAGONAL CURB RAMPS FOR SIDEWALKS
424011	CORNER PARALLEL CURB RAMPS FOR SIDEWALKS
442201-03	CLASS C AND D PATCHES
483001-04	PCC SHOULDER
515001-03	NAME PLATE FOR BRIDGES
542101-02	REINFORCED CONCRETE END SECTIONS FOR PIPE CULVERTS 15" (375mm) THRU 36" (900mm) DIA. AT RIGHT ANGLES WITH ROADWAY
542116-02	REINFORCED CONCRETE END SECTIONS FOR MULTIPLE (2 & 3) PIPE CULVERTS 15" (375mm) THRU 36" (900mm) DIA. AT RIGHT ANGLES WITH ROADWAY
542201-02	REINFORCED CONCRETE END SECTIONS FOR PIPE CULVERTS 15" (375mm) THRU 36" (900mm) DIA. SKEWED WITH ROADWAY
542301-03	PRECAST REINFORCED CONCRETE FLARED END SECTION
542306-02	PRECAST REINFORCED CONCRETE ELLIPTICAL FLARED END SECTION
542311-03	GRATING FOR CONCRETE FLARED END SECTION (FOR 24" (600mm) THRU 54" (1350mm) PIPE)
542601-03	REINFORCED CONCRETE PIPE ELBOW
602001-02	CATCH BASIN TYPE A
602301-03	INLET - TYPE A
602306-03	INLET - TYPE B
602401-03	MANHOLE TYPE A
602601-02	PRECAST REINFORCED CONCRETE FLAT SLAB TOP
602701-02	MANHOLE STEPS
604001-03	FRAME AND LIDS TYPE 1
604036-02	GRATE TYPE 8
604091-02	FRAME AND GRATE TYPE 24
606001-04	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
606301-04	PC CONCRETE ISLANDS AND MEDIANS
631033-04	TRAFFIC BARRIER TERMINAL, TYPE 6B
635001-01	DELINEATORS
635006-03	REFLECTOR AND TERMINAL MARKER PLACEMENT
664001-02	CHAIN LINK FENCE
701006-03	OFF-ROAD OPERATIONS, 2L, 2W, 15' (4.5 m) TO 24" (600 mm) FROM PAVEMENT EDGE
701101-02	OFF-ROAD OPERATIONS, MULTILANE, 15' (4.5m) TO 24" (600mm) FROM PAVEMENT EDGE
701106-02	OFF-ROAD OPERATIONS, MULTILANE, MORE THAN 15' (4.5m) AWAY
701201-04	LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS >= 45MPH
701326-04	LANE CLOSURE, 2L, 2W, PAVEMENT WIDENING, FOR SPEEDS >= 45MPH
701421-04	LANE CLOSURE, MULTILANE, DAY OPERATIONS ONLY, FOR SPEEDS >= 45 MPH TO 55 MPH
701422-04	LANE CLOSURE, MULTILANE, FOR SPEEDS >= 45 MPH TO 55 MPH
701426-04	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPER., FOR SPEEDS >= 45 MPH
701601-07	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NON TRAVERSABLE MEDIAN
701602-05	URBAN LANE CLOSURE, MULTILANE, 2W WITH BIDIRECTIONAL LEFT TURN LANE
701606-08	URBAN LANE CLOSURE, MULTILANE 2W WITH MOUNTABLE MEDIAN
701701-08	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701801-05	LANE CLOSURE MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
701901-02	TRAFFIC CONTROL DEVICES
704001-07	TEMPORARY CONCRETE BARRIER
720001-01	SIGN PANEL MOUNTING DETAILS
720006-03	SIGN PANEL ERECTION DETAILS
720011-01	METAL POSTS FOR SIGNS, MARKERS & DELINEATORS
720016-03	MAST ARM MOUNTED STREET NAME SIGNS
728001-01	TELESCOPING STEEL SIGN SUPPORT
729001-01	APPLICATIONS OF TYPES A & B METAL POSTS (FOR SIGN AND MARKERS)
731001-01	BASE FOR TELESCOPING STEEL SIGN SUPPORT
780001-03	TYPICAL PAVEMENT MARKINGS
814001-02	HANDHOLES
814006-02	DOUBLE HANDHOLES
857001-01	STANDARD PHASE DESIGNATION DIAGRAMS AND PHASE SEQUENCES
862001-01	UNINTERRUPTABLE POWER SUPPLY (UPS)
873001-02	TRAFFIC SIGNAL GROUNDING & BONDING
877001-05	STEEL MAST ARM ASSEMBLY AND POLE 16' THROUGH 55'
877002-02	STEEL MAST ARM ASSEMBLY AND POLE 56' THROUGH 75'
877006-04	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS
877011-05	STEEL COMB. MAST ARM ASSEMBLY AND POLE 16' THROUGH 55'
877012-02	STEEL COMB. MAST ARM ASSEMBLY AND POLE 56' THROUGH 75'
878001-09	CONCRETE FOUNDATION DETAILS
880001-01	SPAN WIRE MOUNTED SIGNALS AND FLASHING BECON INSTALLATION
880006-01	TRAFFIC SIGNAL MOUNTING DETAILS
886001-01	DETECTOR LOOP INSTALLATIONS
886006-01	TYPICAL LAYOUTS FOR DETECTION LOOPS
601101-01	
△1 353001-04	

NOTES:

1. FOR STATE STANDARDS, USE LATEST REVISION NUMBERS AT THE TIME OF LETTING.
2. ALL WORK ALONG WEST SIDE OF POWIS ROAD AND KEIL ROAD IS TO REMAIN WITHIN THE EXISTING ROW.

AECOM

△1 Rev. 1-9-12 Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 307 (ILLINOIS ROUTE 64)

INDEX OF SHEETS
IDOT STATE STANDARDS

SCALE: VERT: NONE HORIZ: NONE
DATE: NOVEMBER 1, 2011
DRAWN BY: AFC
CHECKED BY: NJH