F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	130 R-2	DUPAGE,KANE	647	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	LUMP SUM TOTAL QUANTITY	ROADWAY 0003 KANE	ROADWAY 0003 DUPAGE	ROADWAY 0003 DUPAGE CONTE	ROADWAY 0005 KANE	TRAFFIC SIGNALS 0021 KANE FOXFIELD COMMONS	TRAFFIC SIGNALS 0021 KANE KIRK ROAD	TRAFFIC SIGNALS 0021 KANE CHARLESTOWNE MALL WEST	TRAFFIC SIGNALS 0021 KANE 38TH AVENUE	TRAFFIC SIGNALS 0021 SMITH / KAUTZ ROAD	TRAFFIC SIGNALS 0021 PHEASANT RUN	TRAFFIC SIGNALS 0021 POWIS ROAD	TRAFFIC SIGNALS 0021 ATLANTIC DRIVE	TRAFFIC SIGNALS 0021 IL ROUTE 59	TRAFFIC SIGNALS 0021 100/ST. CHARLES EVP	TRAFFIC SIGNALS 0021 100/W.C.FPD EVP	INTERCONNECT 0021 KANE NHS	INTERCONNECT 0021 KANE NHS	INTERCONNECT 0021 DUPAGE NHS	LIGHTING 0021 KANE	LIGHTING 0021 DUPAGE	DUPAGE CO. 0010 BRIDGE	DUPAGE CO. 0040 RETAINING WALL	100% CITY OF ST. CHARLES	20% ST. CHARLES SW
				80% FED. 20% STATE	80% FED. 20% STATE	80% FED. 20% STATE	100% ST. CHARLES	100% ST. CHARLES	80% FED. 10% STATE 10% KANE COUNTY	100% ST. CHARLES		80% FED. 10% STATE 10% ST. CHARLES	100% ST. CHARLES	DUPAGE COUNTY 80% FED. 10% STATE 5% DUPAGE 5% W. CHICAGO	80% FED. 10% STATE 10% W.C.	80% FED. 20% STATE	KANE DUPAGE		80% FED. / 20% STATE						KANE CO.	DUPAGE CO. 80% FED. KANE CO.
				CONSTRUCTION FUNDING CODE				TRAFFIC SIGNALS 0021											INTERCONNECT 0021			LIGHTING 0021					
20101100	TREE TRUNK PROTECTION	EACH	40		40																						
20100500	TREE REMOVAL, ACRES	ACRE	0.3		0.3																						
20200100	EARTH EXCAVATION	CU YD	53,183		53,183																						
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	21,590	367	21,223																						
20400800	FURNISHED EXCAVATION	CU YD	101,154		101,154																						
20800150	TRENCH BACKFILL	CU YD	5,132	986	4,146																					34	
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	71,384	2,185	69,145		54																				
* 21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	200,260	7,574	192,686																						
* 21101685	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	27,392	1,216	26,176																						
* 21101805	COMPOST FURNISH AND PLACE, 2"	SQ YD	36,581		36,581																						
* 25000210	SEEDING, CLASS 2A	ACRE	18.8	0.3	18.5																						
* 25000310	SEEDING, CLASS 4	ACRE	7.5		7.5																						
* 25000314	SEEDING, CLASS 4B	ACRE	2.2		2.2																						
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	2,745	57	2,688																						
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	2,745	57	2,688																						
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	2,745	57	2,688																						
* △ 25000775	SELECTIVE MOWING STAKES	EACH	15		15																						
* 25100115	MULCH, METHOD 2	ACRE	28.5	1.4	27.1																						
* 25100630	EROSION CONTROL BLANKET	SQ YD	135,303	3,401	131,902																						
* 25200110	SODDING, SALT TOLERANT	SQ YD	29,838	2,185	27,599		54																				
* 25200200	SUPPLEMENTAL WATERING	UNIT	298.2	21.9	276.3																						
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	16,907	843	16,064																						
28000305	TEMPORARY DITCH CHECKS	FOOT	790		790																						
28000315	AGGREGATE DITCH CHECKS	TON	20		20																						
28000400	PERIMETER EROSION BARRIER	FOOT	30,761	2,936	27,825																						
28000500	INLET AND PIPE PROTECTION	EACH	170		170																						
28000510	INLET FILTERS	EACH	249	28	221																						
28100107	STONE RIPRAP, CLASS A4	SQ YD	113		113																						
28100205	STONE RIPRAP CLASS A3	TON	59.6				59.6 △																				
28200200	FILTER FABRIC	SQ YD	113		113																						
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	5,397	5,397 △																							
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	7,740	278	7,462																						
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SQ YD	169	169 △																							
31200502	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4-1/2"	SQ YD	192,674		192,674																						
35501312	HOT-MIX ASPHALT BASE COURSE, 7"	SQ YD	2,339		2,339																						
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	24,978	1,018	19,932 △		3,428																				
40600300	AGGREGATE (PRIME COAT)	TON	453.7	11.8	303.9		138.0																				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	52.0				52.0																				
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	200.0				200.0																				
X4421000	PARTIAL DEPTH PATCHING	TON	200				200																				
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1983.3	679.3 △			1,304.0																				
40600895	CONSTRUCTING TEXT STRIP	EACH	2				2																				

△ NON-PARTICIPATING

* DENOTES SPECIALTY ITEM

AECOM

△ Rev. 1-9-12

SOQ-01
Rev.

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 307 (ILLINOIS ROUTE 64)

SUMMARY OF QUANTITIES

SCALE: VERT: NONE
HORIZ: NONE
DATE: NOVEMBER 1, 2011

DRAWN BY: AFC
CHECKED BY: NJH