F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	130 R-2	DUPAGE,KANE	647	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

URBAN

KANE COUNTY 100% ST. CHARLES

DuPAGE COUNTY

80% FED/20% STATE

DuPAGE Co. 80% FED/20% ST

KANE

62410

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0003 KANE	ROADWAY 0003 DUPAGE	ROADWAY 0003 DuPAGE CONTE	ROADWAY 0005 KANE	CONSTRUCTION FUNDING CODE TRAFFIC SIGNALS 0021 KANE FOXFIELD COMMONS	KANE KIRK ROAD	CHARLESTOWNE MALL WEST	38TH AVENUE	SMITH / KAUTZ ROAD	PHEASANT RUN	POWIS ROAD	ATLANTIC DRIVE	IL ROUTE 59	100% ST. CHARLES EVP	100% W.C. FPD EVP	INTERCONNECT 0021 KANE NHS	KANE NHS	DUPAGE NHS	LIGHTING 0021 KANE	DUPAGE	0010 BRIDGE	0040 RETAINING WALL	0043 100% CITY OF ST. CHARLES	80% FED 0021 20% ST. CHARLES SW
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	251				251																					
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	614				614																					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	91.0				91.0																					
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	294.8		294.8																							
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	585.1		585.1																							
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	3004.7	1584.7			3,420.0																					
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	155,948		145,794	10,154																						
42001300	PROTECTIVE COAT	SQ YD	199,368	3,363	195,915		90																					
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	2,159		2,159																							
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	5,401	278	5,123																							
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	31,468		950		330																				30,188	
42400800	DETECTABLE WARNINGS	SQ FT	261	94	91		76																					
44000100	PAVEMENT REMOVAL	SQ YD	114,360	1,233	113,127																							
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	20,342				20,342																					
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	2875		2875																							
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	7,801		7,801																							
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	16,125	5,681	10,444																							
44000600	SIDEWALK REMOVAL	SQ FT	10,007	812	8,865		330																					
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	405				405																					
44003100	MEDIAN REMOVAL	SQ FT	8,075	2,349	5,726																							
44004250	PAVED SHOULDER REMOVAL	SQ YD	10,548		10,548																							
44022029	PARTIAL DEPTH REMOVAL 3"	SQ YD	1,180				1,180																					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	180				180																					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	96				96																					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	428				428																					
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	5,695		5,695																							
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	30,879		30,879																							
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1																					1				
50102400	CONCRETE REMOVAL	CU YD	139		139																							
50104400	CONCRETE HEADWALL REMOVAL	EACH	13		13																							
50105220	PIPE CULVERT REMOVAL	FOOT	4,463		4,463																							
50157300	PROTECTIVE SHIELD	SQ YD	4,542																					4,542				
50200100	STRUCTURE EXCAVATION	CU YD	8,018																					980	7,038			
50300225	CONCRETE STRUCTURES	CU YD	2947.3																					1765	1,182.3			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1575.5																					1575.5				
50300260	BRIDGE DECK GROOVING	SQ YD	3,710																					3,710				

* DENOTES SPECIALTY ITEM

AECOM

Rev. 1-9-12

S00-02 Rev

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 307 (ILLINOIS ROUTE 64)

SUMMARY OF QUANTITIES

SCALE: VERT: NONE HORIZ: NONE

DATE: NOVEMBER 1, 2011

DRAWN BY: AFC

CHECKED BY: NJH