F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	130 R-2	DUPAGE,KANE	647	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0003 KANE	ROADWAY 0003 DUPAGE	ROADWAY 0003 DUPAGE CONTE	ROADWAY 0005 KANE	TRAFFIC SIGNALS 0021 KANE FOXFIELD COMMONS	TRAFFIC SIGNALS 0021 KANE KIRK ROAD	TRAFFIC SIGNALS 0021 CHARLESTOWNE MALL WEST	TRAFFIC SIGNALS 0021 38TH AVENUE	TRAFFIC SIGNALS 0021 SMITH / KAUTZ ROAD	TRAFFIC SIGNALS 0021 PHEASANT RUN	TRAFFIC SIGNALS 0021 POWIS ROAD	TRAFFIC SIGNALS 0021 ATLANTIC DRIVE	TRAFFIC SIGNALS 0021 IL ROUTE 59	TRAFFIC SIGNALS 0021 100% ST. CHARLES EVP	TRAFFIC SIGNALS 0021 100% W.C. FPD EVP	INTERCONNECT 0021 KANE N/S	INTERCONNECT 0021 KANE NHS	INTERCONNECT 0021 DUPAGE NHS	LIGHTING 0021 KANE	LIGHTING 0021 DUPAGE	0010 BRIDGE	0040 RETAINING WALL	0043 100% CITY OF ST. CHARLES	0021 80% FED. 20% ST. CHARLES SW
54214713	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 18"	EACH	2		2																							
54214719	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 24"	EACH	1		1																							
54214722	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 27"	EACH	1		1																							
54214725	PRECAST REINFORCED CONCRETE FLARED END SECTION - ELLIPTICAL, EQUIVALENT ROUND-SIZE 30"	EACH	1		1																							
54214731	PRECAST REINFORCED CONCRETE FLARED END SECTION - ELLIPTICAL, EQUIVALENT ROUND-SIZE 36"	EACH	1		1																							
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	6		6																							
54247140	GRATING FOR CONCRETE FLARED END SECTION 27"	EACH	3		3																							
54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	1		1																							
54248130	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 24"	EACH	1		1																							
54248160	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 36"	EACH	1		1																							
54248510	CONCRETE COLLAR	CU YD	35	15	20																							
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	2379		2379																							
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	122		122																							
542A0226	PIPE CULVERTS, CLASS A, TYPE 1 21"	FOOT	48		48																							
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	130		130																							
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	1527	30	1497																							
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	580		580																							
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	75		75																							
550A0130	STORM SEWERS, CLASS A, TYPE 1 27"	FOOT	30		30																							
550A0140	STORM SEWERS, CLASS A, TYPE 1 30"	FOOT	194	44	150																							
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	4176	210	3966																							
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	5429	271	5,158																							
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	1,782	89	1,693																							
550A0400	STORM SEWERS, CLASS A, TYPE 2 21"	FOOT	1,426		1,426																							
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	3,193	1,295	1,898																							
550A0420	STORM SEWERS, CLASS A, TYPE 2 27"	FOOT	1644		1644																							
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	1,185	1,015	170																							
550A4000	STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT	335		335																							
550A4100	STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	257		257																							
550A4200	STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 27"	FOOT	465		465																							
550A4300	STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 30"	FOOT	400	182	218																							
550A4500	STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36"	FOOT	156		156																							
55100500	STORM SEWER REMOVAL 12"	FOOT	1,459	179	1,280																							
55100700	STORM SEWER REMOVAL 15"	FOOT	1,087	513	574																							
55100900	STORM SEWER REMOVAL 18"	FOOT	1025	412	613																							
55101200	STORM SEWER REMOVAL 24"	FOOT	1,667	1,667																								
55101300	STORM SEWER REMOVAL 27"	FOOT	117		117																							
55101400	STORM SEWER REMOVAL 30"	FOOT	651	586	65																							

* DENOTES SPECIALTY ITEM

AECOM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 307 (ILLINOIS ROUTE 64)

SUMMARY OF QUANTITIES

SCALE: VERT: NONE HORIZ: NONE
DATE: NOVEMBER 1, 2011

DRAWN BY: AFC
CHECKED BY: NJH

SOQ-04

Rev. 1-9-12