F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	130 R-2	DUPAGE,KANE	647	8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0003 KANE	ROADWAY 0003 DUPAGE	ROADWAY 0003 DUPAGE CONTE	ROADWAY 0005 KANE	TRAFFIC SIGNALS 0021 KANE FOXFIELD COMMONS	TRAFFIC SIGNALS 0021 KANE KIRK ROAD	TRAFFIC SIGNALS 0021 CHARLESTOWNE MALL WEST	TRAFFIC SIGNALS 0021 38TH AVENUE	TRAFFIC SIGNALS 0021 SMITH / KAUTZ ROAD	TRAFFIC SIGNALS 0021 PHEASANT RUN	TRAFFIC SIGNALS 0021 POWIS ROAD	TRAFFIC SIGNALS 0021 ATLANTIC DRIVE	TRAFFIC SIGNALS 0021 IL ROUTE 59	TRAFFIC SIGNALS 0021 100% ST. CHARLES EVP	TRAFFIC SIGNALS 0021 100% W.C. FPD EVP	INTERCONNECT 0021 KANE NHS	INTERCONNECT 0021 KANE NHS	INTERCONNECT 0021 DUPAGE NHS	LIGHTING 0021 KANE	LIGHTING 0021 DUPAGE	0010 BRIDGE	0040 RETAINING WALL	0043 100% CITY OF ST. CHARLES	0021 80% FED. 20% ST. CHARLES SW
55101600	STORM SEWER REMOVAL 36"	FOOT	124		124																							
56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	24		24																							
58700300	CONCRETE SEALER	SQ FT	2,668																					2,668				
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	180																					180				
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	54		54																							
60103500	PIPE DRAINS, CORRUGATED STEEL 12"	FOOT	100		100																							
60107700	PIPE UNDERDRAINS 6"	FOOT	44,433		44,433																							
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	2,626		2,626																							
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	3		3																							
60201310	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 20 FRAME AND GRATE	EACH	2		2																							
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	174	19	155																							
60204505	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	3	3	0																							
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	49	3	46																							
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	52	15	37																							
60222240	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	2	1	1																							
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6		6																							
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4		4																							
60224459	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2		2																							
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	14		14																							
60237420	INLETS, TYPE A, TYPE 20 FRAME AND GRATE	EACH	12		12																							
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	32	1	31																							
60240215	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	1		1																							
60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	3		3																							
60250200	CATCH BASINS TO BE ADJUSTED	EACH	12	6	6																							
60255500	MANHOLES TO BE ADJUSTED	EACH	28		28																							
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	28		28																							
60265900	VALVE VAULTS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1		1																							
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	5				5																					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	5				5																					
60404950	FRAMES AND GRATES, TYPE 24	EACH	2				2																					
60500040	REMOVING MANHOLES	EACH	39	21	18																							
60500050	REMOVING CATCH BASINS	EACH	43	8	35																							
60500060	REMOVING INLETS	EACH	31	1	30																							
60500205	FILLING CATCH BASINS	EACH	5	5																								
60500305	FILLING INLETS	EACH	12	12																								
60600605	CONCRETE CURB, TYPE B	FOOT	904		904																							
				1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	

CONSTRUCTION FUNDING CODE

URBAN

KANE COUNTY 100% ST. CHARLES

80% FED. 20% STATE

80% FED. 20% State

80% FED. 20% STATE

100% ST. CHARLES

80% FED. 10% STATE 10% KANE CO.

80% FED. 10% STATE 10% ST. CHARLES

100% ST. CHARLES

80% FED. 10% STATE 5% DUPAGE 5% W.C.

80% Fed. 10% State 10% W.C.

80% FED. 20% STATE

DUPAGE COUNTY

80% FED./20% STATE

DUPAGE CO. 80% FED./20% STATE

KANE

KANE

62410

80% FED.

* DENOTES SPECIALTY ITEM

AECOM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 307 (ILLINOIS ROUTE 64)

SUMMARY OF QUANTITIES

SCALE: VERT: NONE HORIZ: NONE

DATE: NOVEMBER 1, 2011

DRAWN BY: AFC

CHECKED BY: NJH

Rev. 1-9-12

S00-05
Rev.