F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	130 R-2	DUPAGE,KANE	647	9
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0003 KANE	ROADWAY 0003 DUPAGE	ROADWAY 0003 DuPAGE CONTE	ROADWAY 0005 KANE	TRAFFIC SIGNALS 0021 KANE FOXFIELD COMMONS	TRAFFIC SIGNALS 0021 KANE KIRK ROAD	TRAFFIC SIGNALS 0021 CHARLESTOWNE MALL WEST	TRAFFIC SIGNALS 0021 38TH AVENUE	TRAFFIC SIGNALS 0021 SMITH / KAUTZ ROAD	TRAFFIC SIGNALS 0021 PHEASANT RUN	TRAFFIC SIGNALS 0021 POWIS ROAD	TRAFFIC SIGNALS 0021 ATLANTIC DRIVE	TRAFFIC SIGNALS 0021 IL ROUTE 59	TRAFFIC SIGNALS 0021 100% ST. CHARLES EVP	TRAFFIC SIGNALS 0021 100% W.C. FPD EVP	INTERCONNECT 0021 KANE NHS	INTERCONNECT 0021 KANE NHS	INTERCONNECT 0021 DUPAGE NHS	LIGHTING 0021 KANE	LIGHTING 0021 DUPAGE	0010 BRIDGE	0040 RETAINING WALL	0043 100% CITY OF ST. CHARLES	0021 20% ST. CHARLES SW
60602800	CONCRETE GUTTER, TYPE B	FOOT	185		185																						
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B - 6.12	FOOT	1,870		1,870																						
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B - 6.24	FOOT	32,318	4,466	27,852																						
60607400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B - 9.24	FOOT	500		500																						
60620000	CONCRETE MEDIAN, TYPE SB - 6.24	SQ FT	16,518	3,940	12,578																						
60621200	CONCRETE MEDIAN, TYPE SB - 9.24	SQ FT	1,596		1,596																						
63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	2		2																						
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2		2																						
63200310	GUARDRAIL REMOVAL	FOOT	2,419		2,419																						
66400305	CHAIN LINK FENCE, 6'	FOOT	514		514																						
66408000	CHAIN LINK GATES, 6' X 20' DOUBLE	EACH	1		1																						
66408200	CHAIN LINK GATES, 6' X 24' DOUBLE	EACH	1		1																						
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	3,578		3,578																						
66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1		1																						
66900530	SOIL DISPOSAL ANALYSIS	EACH	7		7																						
~~67000400~~	~~ENGINEER'S FIELD OFFICE, TYPE A~~	~~CAL MO~~	~~18~~		~~18~~																						
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	18		18																						
67100100	MOBILIZATION	L SUM	1		0.8		0.2																				
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1				1																				
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1				1																				
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1		1																						
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1		1																						
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1		0.8		0.2																				
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1		0.8		0.2																				
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1		1																						
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		0.8		0.2																				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1		0.8		0.2																				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	300		300																						
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	40	20	20																						
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2,530				2,530																				
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	990				990																				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6,890				6,890																				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	9,520		4,000		5,520																				
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	120				120																				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,000				1,000																				

* DENOTES SPECIALTY ITEM

AECOM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 307 (ILLINOIS ROUTE 64)

SUMMARY OF QUANTITIES

SCALE: VERT: NONE HORIZ: NONE
DATE: NOVEMBER 1, 2011
DRAWN BY: AFC
CHECKED BY: NJH

SOQ-06