F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	130 R-2	DUPAGE,KANE	647	10
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

URBAN

KANE COUNTY 100% ST. CHARLES

DUPAGE COUNTY

80% FED./20% STATE

DUPAGE CO. 80% FED./10% STATE

KANE CO. 62410 KANE CO.

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0003 KANE	ROADWAY 0003 DUPAGE	ROADWAY 0003 DUPAGE CONTE	ROADWAY 0005 KANE	TRAFFIC SIGNALS 0021 FOXFIELD COMMONS	KIRK ROAD	CHARLESTOWNE MALL WEST	38TH AVENUE	SMITH / KAUTZ ROAD	PHEASANT RUN	POWIS ROAD	ATLANTIC DRIVE	IL ROUTE 59	100% ST. CHARLES EVP (KANE)	100% W.C. FPD EVP (DUPAGE)	INTERCONNECT 0021 KANE NHS	KANE NHS	DUPAGE NHS	LIGHTING 0021 KANE	DUPAGE	0010 BRIDGE	0040 RETAINING WALL	0043 100% CITY OF ST. CHARLES	0021 80% FED. 20% ST. CHARLES SW
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	670				670																				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	67,304	6,167	60,287		850																				
70400100	TEMPORARY CONCRETE BARRIER	FOOT	4,000		4,000																						
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	4,000		4,000																						
* 72000100	SIGN PANEL - TYPE 1	SQ FT	1,428.9	174.5	1,254.4																						
* 72000200	SIGN PANEL - TYPE 2	SQ FT	423.3	60.0	363.3																						
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	66	3	63																						
* 72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	14	4	10																						
* 72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	248.4	69.2	179.2																						
* 72400320	REMOVE SIGN PANEL - TYPE 2	SQ FT	125.5		125.5																						
* 72900100	METAL POST - TYPE A	FOOT	1,814.5	187.0	1,627.5																						
* 72900200	METAL POST - TYPE B	FOOT	2,417.4	190.5	2,226.9																						
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1409.9	419.9			990																				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8,328	1,438			6,890																				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	8,101	2,581			5,520																				
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	120				120																				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,342	342			1,000																				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	845	175			670																				
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	2,804.1		2,731.3	72.8																					
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	54,614		54,614																						
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	12,087		11,180	907																					
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	6,961		6,693	268																					
* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	1,031		1,031																						
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,823	0	1,442		381																				
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	34		34																						
* 78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	160		160																						
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2		2																						
78300100	PAVEMENT MARKING REMOVAL	SQ FT	18,550	1,030	17,520																						
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	342				342																				
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	3																				3				
* 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1																				1				
* 80500010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	4								1	1	2														
* 80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	2											1	1												
* 81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	12,882					38			945	936	1,119	1,468	857					1,063	6,256						
* 81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	137						27	5	45	15	26		19												
				1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24

* DENOTES SPECIALTY ITEM

AECOM

Rev. 1-9-12

SOQ-07
Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 307 (ILLINOIS ROUTE 64)

SUMMARY OF QUANTITIES

SCALE: VERT: NONE HORIZ: NONE
DATE: NOVEMBER 1, 2011

DRAWN BY: AFC
CHECKED BY: NJH