F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	130 R-2	DUPAGE,KANE	647	12
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

URBAN

KANE COUNTY 100% ST. CHARLES

DUPAGE COUNTY

80% FED./20% STATE

DUPAGE CO. 80% FED./20% STATE

KANE CO. 62410 KANE CO. 80% FED

	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0003 KANE	ROADWAY 0003 DUPAGE	ROADWAY 0003 DU PAGE CONTE	ROADWAY 0005 KANE	TRAFFIC SIGNALS 0021 FOXFIELD COMMONS	KIRK ROAD	CHARLESTOWNE MALL WEST	38TH AVENUE	SMITH / KAUTZ ROAD	PHEASANT RUN	POWIS ROAD	ATLANTIC DRIVE	IL ROUTE 59	100% ST. CHARLES EVP	100% W.C. FPD EVP	INTERCONNECT 0021 KANE NHS	KANE NHS	DUPAGE NHS	LIGHTING 0021 KANE	DUPAGE	0010 BRIDGE	0040 RETAINING WALL	0043 100% CITY OF ST. CHARLES	0021 20% ST. CHARLES SW
*	87301215	ELECTRICAL CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	3,354					460	639	552	468	960	275														
*	87301225	ELECTRICAL CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	6,767						653	566	1,430	2,165	1,322		631												
*	87301245	ELECTRICAL CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	13,077								2,012	3,970	2,928		4,167												
*	87301255	ELECTRICAL CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	8,216								1,951	2,215	2,315		535	1,200											
*	87301305	ELECTRICAL CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	12,326								2,881	4,219	2,273		2,953												
*	87301805	ELECTRICAL CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	581								106	113	322		40												
*	87301900	ELECTRICAL CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	3,429								779	807	1,026		817												
*	87302225	ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 3C	FOOT	907											907													
*	87302245	ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 5C	FOOT	5,330											5,330													
*	87302505	ELECTRIC CABLE AERIAL SUSPENDED,SERVICE, NO. 6 2 C	FOOT	106											106													
*	87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	3						1	1		1															
*	87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	2								1				1												
*	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	5								2		2		1												
*	87601200	PEDESTRIAN PUSH-BUTTON POST, GALVANIZED STEEL, TYPE II	EACH	2					2																			
*	87700120	STEEL MAST ARM ASSEMBLY AND POLE 16 FT.	EACH	2												2												
*	87700160	STEEL MAST ARM ASSEMBLY AND POLE 24 FT.	EACH	1												1												
*	87700190	STEEL MAST ARM ASSEMBLY AND POLE 30 FT.	EACH	1								1																
*	87700250	STEEL MAST ARM ASSEMBLY AND POLE 42 FT.	EACH	1												1												
*	87702718	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 46 FT. AND 30 FT.	EACH	1										1														
*	87702980	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 50 FT.	EACH	1								1																
*	87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 55 FT.	EACH	1								1																
*	87703030	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 60 FT.	EACH	2												2												
*	87703040	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 62 FT.	EACH	1										1														
*	87703090	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 70 FT.	EACH	1										1														
*	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	52						4	4	16	4	16		8												
*	87800150	CONCRETE FOUNDATION, TYPE C	FOOT	16								4	4	4		4												
*	87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	30												30												
*	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	114								55	16	30		13												
*	87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	159									71	46		42												
*	87900200	DRILL EXISTING HANDHOLE	EACH	13					2	1	1										2	7						
*	87900205	DRILL EXISTING HEAVY DUTY HANDHOLE	EACH	6																							6	
*	88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	62					4	6	5	8	14	10		15												
*	88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	9					4	1							4											
*	88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	35					4	4	5	5	8	8		1												
*	88030210	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	3							1	1				1												

* DENOTES SPECIALTY ITEM

AECOM

Rev. 1-9-12

SOQ-09

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 307 (ILLINOIS ROUTE 64)

SUMMARY OF QUANTITIES

SCALE: VERT: NONE HORIZ: NONE
DATE: NOVEMBER 1, 2011

DRAWN BY: AFC
CHECKED BY: NJH