| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 307 | 130 R-2 | DUPAGE,KANE | 647 | 14 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

# SUMMARY OF QUANTITIES

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | ROADWAY 0003 KANE | ROADWAY 0003 DUPAGE | ROADWAY 0003 DUPAGE CONTE | ROADWAY 0005 KANE | FOXFIELD COMMONS | KIRK ROAD | CHARLESTOWNE MALL WEST (100% ST. CHARLES) | 38TH AVENUE | TRAFFIC SIGNALS 0021 SMITH / KAUTZ ROAD | PHEASANT RUN | POWIS ROAD | ATLANTIC DRIVE | IL ROUTE 59 | 100% ST. CHARLES EVP | 100% W.C. FPD EVP (KANE DUPAGE) | INTERCONNECT 0021 KANE NHS | KANE NHS | DUPAGE NHS | LIGHTING 0021 KANE | LIGHTING 0021 DUPAGE | BRIDGE (DUPAGE CO. 80% FED./20% STATE) | RETAINING WALL | 0043 100% CITY OF ST. CHARLES (KANE CO.) | 0021 20% ST. CHARLES SW (KANE CO. 80% FED.) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| X2070304 | POROUS GRANULAR EMBANKMENT, SPECIAL | CU YD | 497 | | | | | | | | | | | | | | | | | | | | | 497 | | | | |
| X2130010 | EXPLORATION TRENCH, SPECIAL | FOOT | 500 | | 500 | | | | | | | | | | | | | | | | | | | | | | | |
| X4021000 | TEMPORARY ACCESS (PRIVATE ENTRANCE) | EACH | 10 | | 10 | | | | | | | | | | | | | | | | | | | | | | | |
| X4022000 | TEMPORARY ACCESS (COMMERCIAL ENTRANCE) | EACH | 37 | 1 | 36 | | | | | | | | | | | | | | | | | | | | | | | |
| X4023000 | TEMPORARY ACCESS (ROAD) | EACH | 13 | 1 | 12 | | | | | | | | | | | | | | | | | | | | | | | |
| X4400100 | PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH) | SQ YD | 2,670 | | | | 2,670 | | | | | | | | | | | | | | | | | | | | | |
| X4400110 | TEMPORARY PAVEMENT REMOVAL | SQ YD | 9,904 | 37 | 9,867 | | | | | | | | | | | | | | | | | | | | | | | |
| Δ X5537800 | STORM SEWERS TO BE CLEANED 12" | FOOT | 793 | 0 | 53 | | 740 | | | | | | | | | | | | | | | | | | | | | |
| Δ X5537900 | STORM SEWERS TO BE CLEANED 15" | FOOT | 382 | 382 | 0 | | | | | | | | | | | | | | | | | | | | | | | |
| Δ X5538200 | STORM SEWERS TO BE CLEANED 24" | FOOT | 188 | 188 | 0 | | | | | | | | | | | | | | | | | | | | | | | |
| Δ X5538400 | STORM SEWERS TO BE CLEANED 30" | FOOT | 578 | 0 | 578 | | | | | | | | | | | | | | | | | | | | | | | |
| X5620035 | WATER SERVICE CONNECTION 1 1/2" | EACH | 1 | | | | | | | | | | | | | | | | | | | | | | | 1 | | |
| X5640150 | FIRE HYDRANT ASSEMBLY COMPLETE | EACH | 5 | | | | | | | | | | | | | | | | | | | | | | | 5 | | |
| X6020096 | MANHOLES, TYPE A, 6'-DIAMETER, WITH 2 TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE | EACH | 8 | | 8 | | | | | | | | | | | | | | | | | | | | | | | |
| X6030310 | FRAMES AND LIDS TO BE ADJUSTED (SPECIAL) | EACH | 22 | | | | 22 | | | | | | | | | | | | | | | | | | | | | |
| X6640300 | CHAIN LINK FENCE REMOVAL | FOOT | 621 | | 621 | | | | | | | | | | | | | | | | | | | | | | | |
| X6700410 | ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL) | CAL MO | 24 | | 24 | | | | | | | | | | | | | | | | | | | | | | | |
| X6640308 | CHAIN LINK GATES (SPECIAL) | EACH | 1 | | 1 | | | | | | | | | | | | | | | | | | | | | | | |
| X7010216 | TRAFFIC CONTROL AND PROTECTION, (SPECIAL) | L SUM | 1 | | 1 | | | | | | | | | | | | | | | | | | | | | | | |
| X7030025 | WET REFLECTIVE TEMPORARY TAPE, TYPE III, LETTERS AND SYMBOLS | SQ FT | 2,031 | 353 | 1,678 | | | | | | | | | | | | | | | | | | | | | | | |
| X7030030 | WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH | FOOT | 176,423 | 14,127 | 162,296 | | | | | | | | | | | | | | | | | | | | | | | |
| X7030040 | WET REFLECTIVE TEMPORARY TAPE, TYPE III, 6 INCH | FOOT | 4,910 | 1,415 | 3,495 | | | | | | | | | | | | | | | | | | | | | | | |
| X7030050 | WET REFLECTIVE TEMPORARY TAPE, TYPE III, 12 INCH | FOOT | 94 | | 94 | | | | | | | | | | | | | | | | | | | | | | | |
| X7030055 | WET REFLECTIVE TEMPORARY TAPE, TYPE III, 24 INCH | FOOT | 1,521 | 198 | 1,323 | | | | | | | | | | | | | | | | | | | | | | | |
| X7200054 | REMOVE, STOCKPILE AND REPLACE SIGN PANEL AND SIGN PANEL ASSEMBLY (SPECIAL) | EACH | 19 | 2 | 17 | | | | | | | | | | | | | | | | | | | | | | | |
| X7330064 | SIGN SUPPORT SPECIAL | EACH | 4 | | 4 | | | | | | | | | | | | | | | | | | | | | | | |
| ~~X8100205~~ | ~~TRENCH AND BACKFILL FOR ELECTRICAL WORK (SPECIAL)~~ | ~~FOOT~~ | ~~210~~ | | | | | | | | | | | | | | | | | | | | | | | ~~210~~ | | |
| * X8210015 | TEMPORARY LUMINAIRE, SODIUM VAPOR, 400 WATT (HIGH PRESSURE) | EACH | 27 | | | | | | | | | | | | | | | | | | | 18 | 9 | | | | | |
| * X8250070 | TEMPORARY LIGHTING CONTROLLER (INSTALL ONLY) | EACH | 1 | | | | | | | | | | | | | | | | | | | | 1 | | | | | |
| * X8570226 | FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL | EACH | 8 | | | | | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | | | | | | | | | | | | | |
| * X8730250 | ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED | FOOT | 5,135 | | | | | | | | | | | 1,366 | | | 3,138 | 631 | | | | | | | | | | |
| * X8730255 | ELECTRIC CABLE AERIAL SUSPENDED NO. 20 3/C, TWISTED, SHIELDED | FOOT | 1,163 | | | | | | | | | | | 1,163 | | | | | | | | | | | | | | |
| Z0001050 | AGGREGATE SUBGRADE 12" | SQ YD | 200,260 | 7,574 | 192,686 | | | | | | | | | | | | | | | | | | | | | | | |
| Z0004552 | APPROACH SLAB REMOVAL | SQ YD | 361 | | 361 | | | | | | | | | | | | | | | | | | | | | | | |
| Z0013798 | CONSTRUCTION LAYOUT | L SUM | 1 | | 1 | | | | | | | | | | | | | | | | | | | | | | | |
| Δ Z0018500 | DRAINAGE STRUCTURES TO BE CLEANED | EACH | 6 | | | | 6 | | | | | | | | | | | | | | | | | | | | | |

Δ NON-PARTICIPATING (100% STATE)

* DENOTES SPECIALTY ITEM

AECOM

Δ Rev. 1-9-12

SOQ-11
Rev.

| REVISIONS NAME | DATE |
|---|---|
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 307 (ILLINOIS ROUTE 64)

SUMMARY OF QUANTITIES

SCALE: VERT: NONE HORIZ: NONE
DATE: NOVEMBER 1, 2011
DRAWN BY: AFC
CHECKED BY: NJH