

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	130 R-2	DUPAGE, KANE	647	15A
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

62410

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY		CONSTRUCTION FUNDING CODE										INTERCONNECT		LIGHTING		DUPAGE CO.		KANE CO.		KANE CO.			
				0003		TRAFFIC SIGNALS										0021		0021		0010		0040		0043		0021	
				KANE	DUPAGE	100% ST. CHARLES	FOXFIELD COMMONS	KIRK ROAD	CHARLESTOWNE MALL WEST	38TH AVENUE	SMITH/KALTZ ROAD	PHEASANT RUN	POWIS ROAD	ATLANTIC DRIVE	IL ROUTE 59	100% ST. CHARLES EVP	100% W.C. FPD EVP	KANE NHS	KANE NHS	DUPAGE NHS	KANE	DUPAGE	BRIDGE	RETAINING WALL	CITY OF ST. CHARLES	20% ST. CHARLES SW	
X0327369	SANITARY SEWER, DUCTILE IRON, 10"	FOOT	20																								
X0327368	SANITARY SEWER, DUCTILE IRON, 12"	FOOT	20	20																							
X0327371	PLUG EXISTING PIPE	CU YD	67	51	16																						
*XX004907	GATE VALVE 12" WITH VAULT, 5' DIAMETER	EACH	5																					5			
*XX007558	GATE VALVE 6" WITH VAULT, 4' DIAMETER	EACH	1																					1			
X8302405	LIGHT POLE, ALUMINUM, 20 FT. M.H., 6 FT. MAST ARM	EACH	32																					32			
X8302415	LIGHT POLE, ALUMINUM, 20 FT. M.H., TWIN 6 FT. MAST ARM	EACH	15																					15			
XX006653	FENCE (SPECIAL)	FOOT	5,081		5,081																						
*81026464	CONDUIT ENCASED, REINFORCED CONCRETE, 6" DIA., PVC 3 WIDE X 4 HIGH	FOOT	210																					210			
*X8100053	CONDUIT ENCASED, 6" DIA., GALVANIZED STEEL	FOOT	12																					12			
*81304520	JUNCTION BOX EMBEDDED IN STRUCTURE 18"X8"X8"	EACH	4																					4			
*X8250506	LIGHTING CONTROLLER, SPECIAL	EACH	3																					3			
*56103550	DUCTILE IRON WATER MAIN, CLASS 52, 12"	FOOT	2,114																						2,114		
*Z0045450	PRESSURE CONNECTION 12" WITH VAULT 5' DIAMETER	EACH	1																						1		
*X0327367	STEEL CASING PIPE, BORE & JACK 24"	FOOT	140																						140		
*X5640050	CAP EXISTING FIRE HYDRANT	EACH	4		4																						
*X0800025	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, SPAN WIRE MOUNTED	EACH	24																								
*87302705	ELECTRICAL CABLE AERIAL SUSPENDED, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 IC	FOOT	106																								
*X8000020	EMERGENCY VEHICLE PREEMPTION DETECTOR SUPPORT, PARAPET MOUNTED	EACH	1																								
*87702726	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS 48 FT. AND 26 FT.	EACH	1								1																
*87702742	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 50 FT. AND 22 FT.	EACH	1																								
*87704555	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 55 FT. AND 32 FT.	EACH	1																								
*87704642	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 64 FT. AND 32 FT.	EACH	1																								
*87704740	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 68 FT. AND 40 FT.	EACH	1																								
*87704844	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 70 FT. AND 44 FT.	EACH	1																								
*X8710012	FIBER OPTIC CABLE IN CONDUIT (INSTALL ONLY)	FOOT	1000																						1000		
	WALL MOUNTED SIGN SUPPORT FOR TYPE 1 PANEL (SPECIAL)	EACH	1		1																						
*X8620200	UNINTERRUPTIBLE POWER SUPPLY, SPECIAL	EACH	8					1	1	1	1	1	1	1	1	1											
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	322																						322		
X4024100	TEMPORARY ACCESS (WINTERIZE)	SQ YD	5769	353	5416																						

* DENOTES SPECIALTY ITEM



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.P. ROUTE 307 (ILLINOIS ROUTE 64)

SUMMARY OF QUANTITIES

SCALE: VERT: NONE
 HORIZ: NONE
 DATE: NOVEMBER 1, 2011

DRAWN BY: AFC
 CHECKED BY: NJH

Rev. 1-9-12

SOQ-13