F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	130 R-2	DUPAGE,KANE	647	46
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

62410

PIPE SCHEDULES - NORTH AVENUE

PIPE NO.	UP STREAM STR. NO.	UP STREAM INVERT	DOWN STREAM STR. NO.	DOWN STREAM INVERT	PIPE LENGTH (FEET)	PIPE DIA. (INCHES)	PIPE SLOPE (%)	PAY ITEM DESCRIPTION	TRENCH BACKFILL (CY)
P260	S 260	758.61	S 261	758.39	50	12	0.44	STORM SEW CL A 2 12	48.80
P 261	S 261	758.39	S 262	758.31	20	12	0.44	STORM SEW CL A 2 12	0.00
P 262	S 262	758.31	S 262A	756.66	55	21	3.00	STORM SEW CL A 2 21	0.00
P 263	S 263	758.35	S 262	758.31	10	12	0.44	STORM SEW CL A 2 12	0.00
P264A	S 264A	758.64	S 263	758.35	65	12	0.44	STORM SEW CL A 2 12	70.50
P262A	S 262A	756.66	RST 06	756.55	60	24	0.17	STORM SEW CL A 2 24	67.00
P 264	RST 06	756.55	FES 07	756.46	55	24	0.17	STORM SEW CL A 2 24	8.10
P 270	S 270	757.96	S 271	757.87	20	12	0.44	STORM SEW CL A 2 12	0.00
P 271	S 271	755.86	FES 08	755.60	80	15	0.32	STORM SEW WM REQ 18	12.20
P 272	S 272	758.11	S 271	758.07	10	12	0.44	STORM SEW CL A 2 12	0.00
P 273A	S 273A	756.50	S 274	756.42	20	12	0.44	STORM SEW CL A 2 12	0.00
P 274	S 274	756.42	S 271	755.86	175	15	0.32	STORM SEW CL A 2 15	0.00
P 275	S 275	756.46	S 274	756.42	10	12	0.44	STORM SEW CL A 2 12	0.00
P 276	S 276	757.06	S 277	756.98	20	12	0.44	STORM SEW CL A 2 12	0.00
P 277	S 277	756.98	S 274	756.42	175	15	0.32	STORM SEW CL A 2 15	0.00
P 278	S 278	757.02	S 277	756.98	10	12	0.44	STORM SEW CL A 2 12	0.00
P 285A	S 285A	755.02	S 286	754.93	20	12	0.44	STORM SEW CL A 2 12	0.00
P 286	S 286	754.93	S 289	754.37	175	15	0.32	STORM SEW CL A 2 15	0.00
P 287	S 287	754.98	S 286	754.93	10	12	0.44	STORM SEW CL A 2 12	0.00
P 288	S 288	754.46	S 289	754.37	20	12	0.44	STORM SEW CL A 2 12	0.00
P 289	S 289	754.37	S 291	754.00	117	15	0.32	STORM SEW CL A 2 15	42.00
P 290	S 290	754.42	S 289	754.37	10	12	0.44	STORM SEW CL A 2 12	0.00
P290A	S290A	754.64	S 290	754.42	50	12	0.44	STORM SEW CL A 2 12	15.80
P 291	S 291	754.00	FES 09	753.75	78	15	0.32	STORM SEW WM REQ 18	5.60
P 292	S 292	754.03	S 291	754.00	6	12	0.44	STORM SEW CL A 2 12	0.00
P 293	S 293	754.37	S 294	754.35	5	12	0.44	STORM SEW CL A 2 12	0.00
P 294	S 294	754.35	S 291	754.00	109	15	0.32	STORM SEW CL A 2 15	35.90
P 301	S 301	754.08	S 302	754.04	10	12	0.44	STORM SEW CL A 2 12	0.00
P 302	S 310	753.62	RST 07	753.54	52	27	0.15	STORM SEW WM REQ 27	18.30
P 302A	RST 07	753.54	FES 10	753.50	24	27	0.17	STORM SEW CL A 2 27	0.80
P 303	S 303	753.90	S 304	753.86	8	12	0.44	STORM SEW CL A 2 12	0.00
P303A	S 303A	753.96	S 303	753.90	15	12	0.44	STORM SEW CL A 2 12	3.70
P304	S 302	754.04	S 304	753.86	119	27	0.15	STORM SEW CL A 2 27	24.80
P 305	S 305	753.94	S 304	753.90	8	12	0.44	STORM SEW CL A 2 12	0.00
P 306	S 306	754.01	S 303	753.90	26	12	0.44	STORM SEW CL A 2 12	0.00
P 308	S 308	754.05	S 305	753.94	26	12	0.44	STORM SEW CL A 2 12	0.00
P 309A	S 309A	753.69	S 310	753.62	15	12	0.44	STORM SEW CL A 2 12	0.00
P 310	S 304	753.86	S 310	753.62	157	27	0.15	STORM SEW CL A 2 27	0.00
P 311	S 311	753.69	S 310	753.62	15	12	0.44	STORM SEW CL A 2 12	0.00
P 312	S 312	753.97	S 313	753.88	20	12	0.44	STORM SEW CL A 2 12	0.00
P 313	S 313	753.88	S 310	753.62	174	27	0.15	STORM SEW CL A 2 27	0.00
P 314	S 314	753.93	S 313	753.88	10	12	0.44	STORM SEW CL A 2 12	0.00
P 315	S 315	754.27	S 316	754.18	20	12	0.44	STORM SEW CL A 2 12	0.00
P 316	S 316	754.18	S 313	753.88	200	27	0.15	STORM SEW CL A 2 27	0.00
P 317	S 317	754.23	S 316	754.18	10	12	0.44	STORM SEW CL A 2 12	0.00
P318	S 318	754.56	S 316	754.18	225	24	0.17	STORM SEW CL A 2 24	95.10
P 318A	S 318A	754.74	S 319	754.63	25	12	0.44	STORM SEW CL A 2 12	0.00
P 319	S 319	754.63	S 318	754.56	15	12	0.44	STORM SEW CL A 2 12	7.50
P 321	S 321	754.84	S 318	754.56	165	24	0.17	STORM SEW CL A 2 24	117.10
P 322	S 322	756.18	S 323	756.16	6	12	0.44	STORM SEW CL A 2 12	0.00
P 323	S 323	756.16	S 321	756.10	13	12	0.44	STORM SEW CL A 2 12	4.40
P 324A	S 324A	757.16	S 325	757.12	10	12	0.44	STORM SEW CL A 2 12	0.00

1

PIPE NO.	UP STREAM STR. NO.	UP STREAM INVERT	DOWN STREAM STR. NO.	DOWN STREAM INVERT	PIPE LENGTH (FEET)	PIPE DIA. (INCHES)	PIPE SLOPE (%)	PAY ITEM DESCRIPTION	TRENCH BACKFILL (CY)
P 325	S 325	757.12	S 321	756.10	204	21	0.50	STORM SEW CL A 2 21	63.10
P 326	S 326	757.16	S 325	757.12	10	12	0.44	STORM SEW CL A 2 12	0.00
P 327A	S 327A	759.60	S 328	759.51	20	12	0.44	STORM SEW CL A 2 12	0.00
P 328	S 328	758.28	S 325	757.12	231	18	0.50	STORM SEW CL A 2 18	0.00
P 329	S 329	759.63	S 328	759.59	10	12	0.44	STORM SEW CL A 2 12	0.00
P 330	S 330	761.29	S 331	761.20	20	12	0.44	STORM SEW CL A 2 12	0.00
P 331	S 331	759.40	S 328	758.28	225	15	0.50	STORM SEW CL A 2 15	0.00
P 332	S 332	761.29	S 331	761.25	10	12	0.44	STORM SEW CL A 2 12	0.00
P 333A	S 333A	762.97	S 334	762.88	20	12	0.44	STORM SEW CL A 2 12	0.00
P 334	S 334	760.53	S 331	759.40	225	15	0.50	STORM SEW CL A 2 15	0.00
P 335	S 335	762.96	S 334	762.92	10	12	0.44	STORM SEW CL A 2 12	0.00
P 336	S 336	764.65	S 337	764.61	9	12	0.44	STORM SEW CL A 2 12	0.00
P 337	S 337	761.65	S 334	760.53	225	15	0.50	STORM SEW CL A 2 15	0.00
P 338	S 338	764.47	S 337	764.43	9	12	0.44	STORM SEW CL A 2 12	0.00
P 339	S 339	765.87	S 340	765.84	6	12	0.44	STORM SEW CL A 2 12	0.00
P 340	S 340	762.50	S 337	761.65	169	15	0.50	STORM SEW CL A 2 15	0.00
P 341	S 341	765.78	S 340	765.74	9	12	0.44	STORM SEW CL A 2 12	0.00
P 350	S 350	769.74	S 351	769.70	9	12	0.44	STORM SEW CL A 1 12	0.00
P 350A	S 350A	769.70	S 352	769.50	45	12	0.44	STORM SEW CL A 1 12	4.00
P 351	S 351	769.70	S 352A	769.46	75	15	0.32	STORM SEW CL A 1 15	0.00
P 352	S 352	769.50	S 352A	769.46	9	12	0.44	STORM SEW CL A 1 12	0.00
P 352A	S 352A	769.46	S 354A	769.06	125	15	0.32	STORM SEW CL A 2 15	0.00
P 353	S 353	769.50	S 352A	769.46	9	12	0.44	STORM SEW CL A 1 12	0.00
P 354	S 354	769.10	S 354A	769.06	10	12	0.44	STORM SEW CL A 2 12	0.00
P 354A	S 354A	769.06	FES 11	768.82	75	15	0.32	STORM SEW WM REQ 18	3.20
P 355	S 355	769.10	S 354A	769.06	10	12	0.44	STORM SEW CL A 2 12	0.00
P 356	S 356	769.61	S 357	769.54	17	12	0.44	STORM SEW CL A 2 12	0.00
P 357	S 357	769.54	S 354A	769.06	150	15	0.32	STORM SEW CL A 2 15	0.00
P 358	S 358	769.58	S 357	769.54	10	12	0.44	STORM SEW CL A 2 12	0.00
P 372	S 372	770.68	S 373	770.60	20	12	0.44	STORM SEW CL A 2 12	0.00
P 373	S 373	770.60	S 376	770.20	125	15	0.32	STORM SEW CL A 2 15	0.00
P 374	S 374	770.64	S 373	770.60	10	12	0.44	STORM SEW CL A 2 12	0.00
P 375	S 375	770.28	S 376	770.20	20	12	0.44	STORM SEW CL A 2 12	0.00
P 376	S 376	770.20	RST 08	770.04	50	24	0.32	STORM SEW CL A 2 24	16.30
P 376A	RST 08	770.04	FES 12	769.94	30	24	0.32	STORM SEW CL A 2 24	1.00
P 377	S 377	770.84	S 378	770.76	20	12	0.44	STORM SEW CL A 2 12	0.00
P 378	S 378	770.76	S 376	770.20	175	21	0.32	STORM SEW CL A 2 21	0.00
P 379	S 379	770.80	S 378	770.76	10	12	0.44	STORM SEW CL A 2 12	0.00
P 380A	S 380A	771.32	S 380	771.24	20	12	0.44	STORM SEW CL A 2 12	0.00
P 380	S 380	771.24	S 378	770.76	150	21	0.32	STORM SEW CL A 2 21	0.00
P 381	S 381	771.28	S 380	771.24	10	12	0.44	STORM SEW CL A 2 12	0.00
P 382	S 382	771.77	S 383	771.68	20	12	0.44	STORM SEW CL A 2 12	0.00
P 383	S 383	771.68	S 380	771.24	140	21	0.32	STORM SEW CL A 2 21	0.00
P 383A	S 383A	771.73	S 383	771.68	10	12	0.44	STORM SEW CL A 2 12	0.00
P 384	S 384	773.27	S 385	773.18	20	12	0.44	STORM SEW CL A 2 12	0.00
P 385	S 385	773.18	S 383	771.68	150	18	1.00	STORM SEW CL A 2 18	0.00
P 385A	S 385A	773.23	S 385	773.18	10	12	0.44	STORM SEW CL A 2 12	0.00
P 386	ES 386	777.05	S 387	776.98	15	12	0.44	STORM SEW CL A 2 12	7.70
P 387	S 387	776.98	S 385	775.18	180	15	1.00	STORM SEW CL A 2 15	75.70
P 389	ES 389	781.58	S 391	781.54	9	12	0.44	STORM SEW CL A 2 12	0.00
P 390	S 390	781.65	S 391	781.54	25	12	0.44	STORM SEW CL A 2 12	0.00
P 391	S 391	781.54	S 387	778.98	256	15	1.00	STORM SEW CL A 2 15	75.10

SCHD-18

REVISIONS	
NAME	DATE
1 ADDENDUM NO. 1	12/23/11

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 307 (ILLINOIS ROUTE 64)

SCHEDULE OF DRAINAGE QUANTITIES

SCALE: VERT: NONE HORIZ: NONE
DATE: NOVEMBER 1, 2011

DRAWN BY: AFC
CHECKED BY: NJH

AECOM