

SUMMARY OF QUANTITIES

F.A.P. RTE. 307	SECTION 130 R-2	COUNTY DUPAGE,KANE	TOTAL SHEETS 647	SHEET NO. 5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

80% FED. 20% STATE
 100% PRIVATE ENTITY
 80% FED. 20% STATE ST. CHARLES
 100% ST. CHARLES
 80% FED. 10% STATE 10% ST. CHARLES
 100% ST. CHARLES
 80% FED. 20% STATE
 100% ST. CHARLES
 80% FED. 20% STATE
 100% ST. CHARLES
 100% ST. CHARLES

KANE COUNTY 100% ST. CHARLES
 DUPAGE COUNTY

80% FED./20% STATE
 DuPage Co. 80% FED./20% STATE
 KANE KANE 62410

URBAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION FUNDING CODE																KANE	KANE						
				ROADWAY 0003				TRAFFIC SIGNALS 0021				INTERCONNECT 0021				LIGHTING 0021											
				KANE	DUPAGE	DUPAGE CONTE	KANE	KANE FOXFIELD COMMONS	KANE KIRK ROAD	CHARLESTOWNE MALL WEST	38TH AVENUE	SMITH / KAUTZ ROAD	PHEASANT RUN	POWIS ROAD	ATLANTIC DRIVE	IL ROUTE 59	100% ST. CHARLES EVP	80% ST. CHARLES EVP	KANE NHS	KANE NHS	DUPAGE NHS	KANE	DUPAGE	BRIDGE	RETAINING WALL	0043 CITY OF ST. CHARLES	80% FED. 20% ST. CHARLES SW
4060082	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	251				251																				
4060085	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	614				614																				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	91.0				91.0																				
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	294.8		294.8																						
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	585.1		585.1																						
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	4,459.7	1,039.7			3,420.0																				
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	151,363	5,569	135,640	10,154																					
42001300	PROTECTIVE COAT	SQ YD	204,796	8,938	195,768	90																					
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	2,159	2,159																							
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	5,401	278	5,123																						
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	31,138		950	330																				29,858	
42400800	DETECTABLE WARNINGS	SQ FT	261	94	91	76																					
44000100	PAVEMENT REMOVAL	SQ YD	114,360	1,233	113,127																						
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	20,342			20,342																					
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	2875		2875																						
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	7,801		7,801																						
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	16,125	5,681	10,444																						
44000600	SIDEWALK REMOVAL	SQ FT	10,007	812	8,865	330																					
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	405			405																					
44003100	MEDIAN REMOVAL	SQ FT	8,075	2,349	5,726																						
44004250	PAVED SHOULDER REMOVAL	SQ YD	10,548		10,548																						
44022029	PARTIAL DEPTH REMOVAL 3"	SQ YD	1,180			1,180																					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	180			180																					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	96			96																					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	428			428																					
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	5,695		5,695																						
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	30,879		30,879																						
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1																						1		
50102400	CONCRETE REMOVAL	CU YD	139		139																						
50104400	CONCRETE HEADWALL REMOVAL	EACH	13		13																						
50105220	PIPE CULVERT REMOVAL	FOOT	4,463		4,463																						
50157300	PROTECTIVE SHIELD	SQ YD	4,542																						4,542		
50200100	STRUCTURE EXCAVATION	CU YD	8,018																						980	7,038	
50300225	CONCRETE STRUCTURES	CU YD	2,947.3																						1,765	1,182.3	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1575.5																						1575.5		
50300260	BRIDGE DECK GROOVING	SQ YD	3,710																						3,710		

* DENOTES SPECIALTY ITEM



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.P. ROUTE 307 (ILLINOIS ROUTE 64)

SUMMARY OF QUANTITIES

50Q-02
 REV

SCALE: VERT: NONE
 HORIZ: NONE
 DATE: NOVEMBER 1, 2011
 DRAWN BY: AFC
 CHECKED BY: NJH