F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	130 R-2	DUPAGE,KANE	647	274
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

62410

EXISTING SIGN SCHEDULE
NORTH AVE

COUNTY	LABEL	STATION	OFFSET	EXISTING MOUNTING	SIGN DESCRIPTION	REMAIN IN PLACE	REMOVE SIGN PANEL ASSEMBLY TYPE A	REMOVE SIGN PANEL ASSEMBLY TYPE B	REMOVE SIGN PANEL TYPE 1	REMOVE SIGN PANEL TYPE II	REM, STOCKPILE AND REPLACE SIGN PANEL AND SIGN PANEL ASSEMBLY (SPECIAL)
						EACH	EACH	EACH	SQ FT	SQ FT	EACH
KANE	100	3265+44	69' LT	POST	CHARLESTOWN MALL EXIT	1					
	101	3265+54	63' LT	TS POLE	#3				5.0		
	102			TS MAST ARM	LEFT TURN SIGNAL				5.0		
	103	3265+76	79' LT	TS POLE	STOP (EMERGENCY)				6.3		
	104	3265+37	12' LT	POST	LEFT TURN ONLY (DUAL)	1					
	105			POST	KEEP RIGHT (SYMBOL)	1					
	106	3266+36	97' LT	POST	KEEP RIGHT (SYMBOL)	1					
	107			POST	LEFT TURN ONLY	1					
	108	3267+02	70' LT	TS MAST ARM	LEFT TURN SIGNAL				5.0		
	109			TS POLE	STOP (EMERGENCY)				6.3		
	110	3267+26	76' LT	POST	CHARLESTOWN MALL ENTER	1					
	111	3266+96	2' RT	POST	KEEP RIGHT (SYMBOL)			1			
	112			POST	LEFT TURN ONLY						
	113	3266+99	5' RT	TS MAST ARM	LEFT TURN SIGNAL				5.0		
	114	3266+92	50' RT	TS POLE	38TH AV				9.0		
	115			TS POLE	#3				5.0		
	116	3266+74	59' RT	TS POLE	STOP (EMERGENCY)				6.3		
	117	3266+49	183' RT	LIGHT POLE	ST. CHARLES CHAMBER OF COMMERCE (L. ARROW)	1					
	118			LIGHT POLE	NO PARKING ANY TIME	1					
	119	3265+86	64' RT	TS MAST ARM	LEFT TURN SIGNAL				5.0		
	120			TS POLE	STOP (EMERGENCY)				6.3		
	121	3265+17	79' RT	POST	NO PARKING THIS BLOCK	1					
	122	3265+05	114' RT	POST	NO PARKING THIS BLOCK	1					
	123	3265+95	165' RT	POST	CLASS II TRUCK ROUTE	1					
	124			POST	NO PARKING ANY TIME	1					
	125			POST	ST. CHARLES CHAMBER OF COMMERCE (R. ARROW)	1					
	126	3265+82	157' RT	POST	STOP	1					
	127	3269+93	55' RT	POST	RIGHT TURN ONLY		1				
	128	3274+84	70' LT	POST	NO TRESPASSING						1
	129	3276+65	97' LT	POST	TOYS R US	1					
	130	3276+89	46' LT	POST	SPEED LIMIT 45		1				
	131	3279+19	46' LT	POST	WEST			1			
	132			POST	ILLINOIS 64						
	133	3280+10	12' LT	POST	KEEP RIGHT (SYMBOL)			1			
	134			POST	LEFT TURN ONLY						
	135	3280+01	13' RT	UTILITY WIRE	LEFT ON GREEN ARROW ONLY				5.0		
	136	3278+41	48' RT	LIGHT POLE	PACE BUS STOP 801						1
	137	3276+90	46' RT	POST	SPEED LIMIT 45		1				
	138	3273+78	98' RT	POST	STOP			1			
	139			POST	RIGHT TURN ONLY						
DUPAGE	140	3281+11	164' LT	LIGHT POLE	NO PARKING THIS BLOCK				1.5		
	141	3280+23	84' LT	UTILITY POLE	SMITH RD					11.0	
	142			UTILITY POLE	SMITH RD					11.0	
	143			UTILITY POLE	#2				5.0		
	144	3281+51	64' LT	LIGHT POLE	#2				5.0		
	145			LIGHT POLE	STOP (EMERGENCY)				6.3		
	146	3281+74	58' LT	POST	RIGHT TURN ONLY		1				
	147	3282+17	61' LT	LIGHT POLE	KANE COUNTY						1
	148			LIGHT POLE	CALL 911 EMERGENCY CELLULAR						1
	149	3283+66	58' LT	LIGHT POLE	WATER CONSERVATION REGULATIONS (ETC.)						1
	150	3281+46	6' LT	UTILITY WIRE	LEFT ON GREEN ARROW ONLY				5.0		
	151	3281+31	53' RT	LIGHT POLE	#2				5.0		
	152			LIGHT POLE	KAUTZ RD				6.8		
	153			LIGHT POLE	KAUTZ RD				6.8		
	154	3281+52	12' RT	POST	KEEP RIGHT (SYMBOL)			1			
	155			POST	LEFT TURN ONLY (DUAL)						
	156	3282+20	52' RT	LIGHT POLE	EAST				2.0		
	157			LIGHT POLE	ILLINOIS 64				9.0		
	158			LIGHT POLE	DUPAGE 18 COUNTY				9.0		
	159	3281+08	98' RT	UTILITY POLE	#2				5.0		
	200	3292+63	33' LT	POST	SPEED LIMIT 45		1				
	201			POST	NO PARKING ANY TIME						
	202	3293+75	32' LT	POST	NO LEFT TURN		1				

SHEET SUBTOTALS	**15**	**6**	**5**	**135.6**	**22**	**5**
KANE COUNTY TOTALS	15	3	4	69.2	0	2
DUPAGE COUNTY TOTALS	0	3	1	66.4	22	3

ESNS-1

AECOM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 307 (ILLINOIS ROUTE 64)

EXISTING SIGNING SCHEDULES

SCALE: VERT: NONE HORIZ: NONE
DATE: MAY 13, 2011

DRAWN BY: JWM
CHECKED BY: RMG