F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	130 R-2	DUPAGE,KANE	647	290
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

62410

PROPOSED SIGN SCHEDULE
NORTH AVE

COUNTY	LABEL	STATION	OFFSET	PROPOSED MOUNTING	SIGN DESCRIPTION	MUTCD SIGN CODE	PANEL DIMENSION	SIGN PANEL TYPE 1	SIGN PANEL TYPE 2	REM, STOCKPILE AND REPLACE SIGN PANEL AND SIGN PANEL ASSEMBLY (SPECIAL)	METAL POST TYPE A	METAL POST TYPE B	WALL MOUNTED SIGN SUPPORT FOR TYPE 1 PANEL (SPECIAL)
								SQ FT	SQ FT	EACH	FOOT	FOOT	EACH
	P-425	3348+45.51	88.9' L	MAST ARM	ILLINOIS ROUTE 64 NORTH AV	STREET SIGN	72x24		12.0				
					LEFT ON GREEN ARROW ONLY	R10-5	30x36	7.5					
	P-426	3349+40	12' R	POST	LEFT TURN ONLY	R5-L	30x36	7.5			27.0		
	P-427	3349+15.5	12' R	POST	KEEP RIGHT	R4-7	24x30	5.0				13.5	
	P-428	3348+96.5	82.8' R	MAST ARM	POWIS RD	STREET SIGN	48x24	8.0					
					LEFT ON GREEN ARROW ONLY	R10-5	30x36	7.5					
	P-429	3348+96.5	82.8' R	TRAFFIC POLE	ILLINOIS 64	M1-I100	24x24	4.0					
					EAST	M3-2	24x12	2.0					
	P-430	3348+83	147' R	POST	LEFT, STRAIGHT, AND RIGHT TURN ONLY	R3-8b	54x30		11.3			27.0	
	P-432	3348+78	122' R	POST	DUPAGE 18 COUNTY	M1-6	24x24	4.0			28.0		
					END CLASS II TRUCK ROUTE	R5-I101	12x18	1.5					
	P-433	3348+15	175' R	POST	SPEED LIMIT 45	R2-1	36x48		12.0			30.0	
	P-434	3348+10	152' R	POST	DO NOT PASS	R4-1	24x30	5.0			29.0		
					BEGIN CLASS II TRUCK ROUTE	R5-I101	12x18	1.5					
	P-435	3342+50	74.0' R	EXISTING	DIESEL EMISSION TEST STATION (RIGHT ARROW)		36x48			1			
	P-436	3344+00	77' R	EXISTING	C.D.L. TRUCK-BUS TESTING CENTER (RIGHT ARROW)		36x48			1			
	P-437	3348+19	197' R	EXISTING	WEST CHICAGO 25,700		36x48			1			
	P-439	3347+49.7	95.7' R	MAST ARM	ILLINOIS ROUTE 64 NORTH AV	STREET SIGN	72x24		12.0				
					LEFT ON GREEN ARROW ONLY	R10-5	30x36	7.5					
	P-440	3347+49.7	95.7' R	POST	DUPAGE 18 COUNTY	M1-6	24x24	4.0				13.5	
					BEGIN	M4-11	24x6	1.0					
	P-442	3340+50	73.0' R	POST	SPEED LIMIT 45	R2-1	36x48		12.0			30.0	
	P-443	3339+00	73.0' R	POST	POWIS RD	STREET SIGN	48x24	8.0				26.0	
	P-444	3347+08.6	85.6' L	MAST ARM	LEFT ON GREEN ARROW ONLY	R10-5	30x36	7.5					
	P-445	3348+68.9	77.9' L	MAST ARM	LEFT ON GREEN ARROW ONLY	R10-5	30x36	7.5					
	P-446	3348+96.5	82.8' R	MAST ARM	LEFT ON GREEN ARROW ONLY	R10-5	30x36	7.5					
	P-447	3347+25.2	78.5' R	MAST ARM	LEFT ON GREEN ARROW ONLY	R10-5	30x36	7.5					
	P-500	3351+48	12' R	POST	LEFT TURN ONLY	R3-5L	30x36	7.5			27.0		
	P-501	3359+75	64.6' L	WALL	(EMERGENCY VEHICLE PREEMPTION DEVICE)	W3-3		0.0			7.0		1
	P-502	3360+50	64.6' R	WALL	TRUCK CROSSING	W11-10	36x36	9.0					1
	P-503	3360+50	1' L	POST	POWIS RD	STREET SIGN	48x24	8.0				26.0	
	P-504	3364+50	64.6' L	WALL	SPEED LIMIT 45	R2-1	36x48		12.0				1
	P-505	3364+50	64.6' R	WALL	SPEED LIMIT 50	R2-1	36x48		12.0				1
	P-506	3368+16	9' L	POST	ONE WAY	R6-2R	24x30	5.0				13.5	
	P-507	3367+72	9' R	POST	ONE WAY	R6-2R	24x30	5.0				13.5	
	P-508	3369+00	73' R	POST	SIDE ROAD	W2-2R	36x36	9.0				31.7	
					REQUE RD (ADVANCE STREET NAME PLAQUE)	W16-8	30x8	1.7					
	P-509	3372+00	73' L	POST	TRUCK CROSSING	W11-10	36x36	9.0				30.4	
	P-510	3372+59	9' R	POST	ONE WAY	R6-2R	24x30	5.0				13.5	
DUPAGE	P-511	3375+00	73.6' R	POST	RIGHT TURN ONLY	R3-5R	30x36	7.5			27.0		
	P-512	3375+01	0' R	POST	KEEP RIGHT	R4-7	24x30	5.0				13.5	
	P-513	3376+19	12' R	POST	KEEP RIGHT	R4-7	24x30	5.0				13.5	
	P-514	3376+13	76.3' R	POST	STOP	R1-1	30x30	6.3				13.5	
	P-515	3376+62	12' R	POST	U-TURN AND LEFT TURN ONLY	R3-5	30x36	7.5				34.0	
					NO U-TURN FOR TRUCKS OVER 23'	R10-16	30x36	7.5					
	P-516	3376+15	72.9' R	POST	REQUE RD	STREET SIGN	42x12	3.5				26.0	
					NORTH AV	STREET SIGN	36x12	3.0					
	P-517	336050	57' L	POST	POWIS RD	STREET SIGN	48x24	8.0				26.0	
	P-600	3380+00	73' L	POST	SPEED LIMIT 50	R2-1	36x48		12.0			30.0	
	P-601	3381+36	9' R	POST	ONE WAY	R6-2R	24x30	5.0				13.5	
	P-602	3384+00	73' L	POST	SIDE ROAD	W2-2L	36x36	9.0				31.7	
					REQUE RD (ADVANCE STREET NAME PLAQUE)	W16-8	30x8	1.7					
	P-603	3385+66	0	POST	KEEP RIGHT	R4-7	24x30	5.0				13.5	
	P-604	3386+81	12' R	POST	KEEP RIGHT	R4-7	24x30	5.0				13.5	
	P-605	3387+20	12' R	POST	LEFT TURN ONLY	R3-5L	30x36	7.5			27.0		
	P-606	3389+80	4.9' R	POST	LEFT TURN ONLY	R3-5L	30x36	7.5			27.0		
	P-607	3386+67	72' R	POST	STOP	R1-1	30x30	6.3				13.5	
	P-608	3386+72	72' R	POST	CONTE PKWY	STREET SIGN	42x12	3.5				26.0	
					NORTH AV	STREET SIGN	36x12	3.0					
	P-609	3385+55	70' R	POST	RIGHT TURN ONLY	R3-5R	30x36	7.5			27.0		
	P-610	3381+65	72' R	POST	STOP	R1-1	30x30	6.3				13.5	
	P-611	3381+65	89' R	POST	RIGHT TURN ONLY	R3-5R	30x36	7.5			27.0		
	P-612	3381+70	72' R	POST	MARKETING DR	STREET SIGN	48x12	4.0				26.0	
					NORTH AV	STREET SIGN	36x12	3.0					
	P-613	3380+00	73' R	POST	SPEED LIMIT 50	R2-1	36x48		12.0			30.0	
	P-614	3378+00	73' R	POST	SIDE ROAD	W2-2R	36x36	9.0				31.7	
					CONTE PKWY (ADVANCE STREET NAME PLAQUE)	W16-8	24x8	1.4					
	P-615	3379+09	6' R	POST	U-TURN AND LEFT TURN ONLY	R3-5	30x36	7.5				34.0	
					NO U-TURN FOR TRUCKS OVER 23'	R10-16	30x36	7.5					
	P-700	3392+47	8' R	POST	ONE WAY	R6-2R	24x30	5.0				13.5	
	P-701	3394+00	73' L	POST	SIDE ROAD	W2-2L	36x36	9.0				31.7	
					CONTE PKWY (ADVANCE STREET NAME PLAQUE)	W16-8	24x8	1.4					
	P-702	3398+50	73' L	POST	SPEED LIMIT 50	R2-1	36x48		12.0			30.0	
	P-703	3399+70	73' L	POST	STOP	R1-1	30x30	6.3				13.5	
	P-704	3399+77	90' L	POST	RIGHT TURN ONLY	R3-5R	30x36	7.5			27.0		
	P-705	3400+23	73' L	POST	DO NOT ENTER	R5-1	36x36	9.0			27.0		
	P-706	3399+90	8.0' L	POST	ONE WAY	R6-2R	24x30	5.0				13.5	
	P-707	3401+25	5' L	POST	KEEP RIGHT	R4-7	24x30	5.0				13.5	
	P-708	3403+25	5.0' R	POST	KEEP RIGHT	R4-7	24x30	5.0				13.5	
	P-709	3403+59	5.0' R	POST	LEFT TURN ONLY	R3-5L	30x36	7.5			27.0		

AECOM

PSNS-3

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 307 (ILLINOIS ROUTE 64)

PROPOSED SIGNING SCHEDULES

SCALE: VERT: NONE HORIZ: NONE
DATE: NOVEMBER 1, 2011

DRAWN BY: AFC
CHECKED BY: NJH