

LEGEND


- EXISTING R.O.W.
- PROPOSED R.O.W.
- PROPOSED PERMANENT EASEMENT
- PROPOSED TEMPORARY EASEMENT
- TIE POINT +
- BENCHMARK ▲

NOTE:

COORDINATES ARE BASED ON THE PUBLISHED METRIC COORDINATE VALUES AT FOUND GEODETIC SURVEY CONTROL MONUMENT "MCH31 1A", P.I.D. AJ2855, OF N.613,205.182-E.303,895.917. SURFACE COORDINATES ARE SHOWN IN U.S. SURVEY FEET. ELEVATIONS ARE ON NAVD 88 DATUM.

PROPOSED R.O.W. AND EASEMENTS
COORDINATE TABLE

POINT #	DESCRIPTION	STATION	OFFSET	NORTHING	EASTING
129	PROPOSED R. O. W.	269+57.50	50.83' LT	2,014,506.31	996,870.85
130	PROPOSED R. O. W.	269+57.50	74.83' LT	2,014,506.27	996,960.85
131	PROPOSED R. O. W.	273+00.00	74.49' LT	2,014,848.77	996,860.11
132	PROPOSED R. O. W.	273+00.00	64.49' LT	2,014,848.81	996,870.11
133	PROPOSED R. O. W.	276+56.17	64.15' LT	2,015,204.97	996,869.33
134	PROPOSED R. O. W.	273+43.49	85.55' RT	2,014,892.77	997,020.01
135	PROPOSED R. O. W.	273+43.48	75.55' RT	2,014,892.73	997,010.01
136	PROPOSED R. O. W.	277+25.91	75.92' RT	2,015,275.16	997,009.18
357	TEMPORARY EASEMENT	271+00.00	84.69' LT	2,014,648.74	996,850.54
358	TEMPORARY EASEMENT	271+00.00	74.69' LT	2,014,648.77	996,860.54
359	TEMPORARY EASEMENT	274+50.06	64.35' LT	2,014,998.87	996,869.78
360	TEMPORARY EASEMENT	274+50.09	89.35' LT	2,014,998.81	996,844.78
361	TEMPORARY EASEMENT	276+56.19	89.15' LT	2,015,204.92	996,844.33



FILE NAME =	USER NAME = dte	DESIGNED - KWH	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ALIGNMENT, TIES AND BENCHMARKS	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
Y:\2278 Virginia Klassen\cad\sheet\05-Align\mentTiesAndBenchmarks\2278-shit-ATB-03.dgn	mentTiesAndBenchmarks\2278-shit-ATB-03.dgn	DRAWN - AKW	REVISED -			3887	96-00209-01-PV	McHENRY	271	23	
PLOT SCALE = 100.0000' / in.		CHECKED - GAB	REVISED -			SCALE: 1" = 100'		SHEET NO. 3 OF 3 SHEETS		STA. 269+00 TO STA. 279+44.88	
PLOT DATE = 10/24/2011		DATE - 10/24/11	REVISED -			FED. ROAD DIST. NO.		ILLINOIS		FED. AID PROJECT HPP-406(1003)	
						CONTRACT NO. 63553					