SUMMARY OF QUANTITIES				0004 ROADWAY SKOKIE 70% STU 15% STATE 15% LA (RECON-STRUCTION)	0004 ROADWAY SKOKIE 70% STU 30% STATE (REHAB.- STA. 127+31.09 TO 135+97)	0004 ROADWAY SKOKIE 100% STATE (RESURF- STA. 120+50 TO 127+31.09)	0043 ROADWAY IN-LINE DETENTION 70% STU 30% LA	0021 LIGHTING SKOKIE 70% STU 30% LA	0021 SIGNALS SOUTH MALL ENTRANCE 70% STU 30% STATE	0021 SIGNALS MIDDLE MALL ENTRANCE 70% STU 30% STATE	0021 SIGNALS NORTH MALL ENTRANCE 70% STU 30% STATE	0021 SIGNALS OLD ORCHARD 70% STU 15% STATE 15% LA	0021 SIGNALS INTERCONNECT 70% STU 30% STATE	0043 WATER, SIDEWALK & ITEMS SKOKIE NON-PART 100% LA	0021 SIGNALS EMERGENCY VEHICLE PREEMPTION 100% LA
CODE NO	PAY ITEM	UNIT	QUANTITY												
60500060	REMOVING INLETS	EACH	12	5	5	2									
60500405	FILLING VALVE VAULTS	EACH	10											10	
60600605	CONCRETE CURB, TYPE B	FOOT	317	52	36	229									
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	4,772	3,485		1,287									
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	296	296											
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	553	553											
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	2,566	2,096	470										
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	8,042	4,263	819	2,960									
60624600	CORRUGATED MEDIAN	SQ FT	2,727	2,439	111	177									
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	1	1											
66900200	* NON-SPECIAL WASTE DISPOSAL	CU YD	~~100~~ 1,137	~~100~~ 1,137											
66900450	* SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1											
66900530	* SOIL DISPOSAL ANALYSIS	EACH	~~9~~ 5	~~9~~ 5											
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12											
67100100	MOBILIZATION	L SUM	1	1											
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2,200	2,200											
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	7,000	7,000											
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	100,000	100,000											
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	18,000	18,000											
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	800	800											
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	3,000	3,000											
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	25,000	25,000											
70400100	TEMPORARY CONCRETE BARRIER	FOOT	2,005				2,005								
72000100	• SIGN PANEL - TYPE 1	SQ FT	273	190	34.0	49.0									
72400100	• REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	10	6	2	2									
72400310	• REMOVE SIGN PANEL - TYPE 1	SQ FT	152	140.5	5.0	6.5									
72400500	• RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	4	4											
72400710	• RELOCATE SIGN PANEL - TYPE 1	SQ FT	8	8.0											
72900100	• METAL POST - TYPE A	FOOT	364	248	66	50									
72900200	• METAL POST - TYPE B	FOOT	52	52											
78000100	• THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	291	291											
78000200	• THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4,743	4,743											
78000400	• THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,979	1,979											
78000600	• THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	158	158											

• SPECIALTY ITEM

TranSystems
1475 EAST WOODFIELD ROAD, SUITE 600
SCHAUMBURG, ILLINOIS 60173
(847) 605-9600

FILE NAME = g:\CHBG\0045\Road\Sheets\0045-G-1DM-Sum0tyaht	USER NAME = CEComin	DESIGNED CEC	REVISED △1 ADDENDUM #1 (12/22/2011)	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	U.S. ROUTE 41 (SKOKIE BOULEVARD) SUMMARY OF QUANTITIES
		DRAWN CEC	REVISED -		
	PLOT SCALE = 100.000 ' / IN.	CHECKED DWB	REVISED -		
	PLOT DATE = 10/25/2011	DATE 10/26/2011	REVISED -		SCALE: NONE · SHEET NO. 4 OF 8 SHEETS · STA. · TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
350	00-00243-00-CH	COOK	142	7
		CONTRACT NO. 63566		
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT		