

SUMMARY OF QUANTITIES			ILL ROUTE 43 (HARLEM AV) AT ISHNALA DRIVE					
NO.	CODE NO	ITEM DESCRIPTION	UNIT	TOTAL	ROADWAY IMPROVEMENTS TYPE 0004	TRAFFIC SIGNALS TYPE 0021	INTERCONNECT TYPE 0021	TRAINEES TYPE 0042
81.	87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT	EACH	1		1		
82.	87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT	EACH	1		1		
83.	87700270	STEEL MAST ARM ASSEMBLY AND POLE, 46 FT	EACH	2		2		
84.	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16		16		
85.	87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4		
86.	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	50		50		
87.	87900200	DRILL EXISTING HANDHOLE	EACH	2		1	1	
88.	88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	6		6		
89.	88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	4		4		
90.	88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	4		4		
91.	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4		4		
92.	88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINIUM	EACH	10		10		
93.	88500100	INDUCTIVE LOOP DETECTOR	EACH	8		8		
94.	88600100	DETECTOR LOOP, TYPE I	FOOT	846		846		
95.	88700200	LIGHT DETECTOR	EACH	2		2		
96.	88700300	LIGHT DETECTOR AMPLIFIER	EACH	1		1		
97.	88800100	PEDESTRIAN PUSH-BUTTON	EACH	4		4		
98.	89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	1,091		1,091		
* * *	B2005616	TREE, PYRUS CALLERYANA BRADFORD (BRAD FORD CALLERY PEAR), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	4	4			
100.	X6063401	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.12	FOOT	230	230			
101.	X8570225	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1		1		
102.	X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	340		340		
* * *	XX006188	REMOVE AND RE-ERECT SEGMENTAL BLOCK RETAINING WALL	FOOT	250	250			
104.	Z0033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	1			1	
105.	Z0076600	TRAINEES	HOURL	500				500

* * * SPECIALTY ITEMS

FILE NAME = 2806-240-PR6.dwg	USER NAME = GHA	DESIGNED - BVS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES ILL RTE 43 (HARLEM AVENUE) ROAD IMPROVEMENTS			F.A.P. RTE 348	SECTION 10-00047-00-TL	COUNTY COOK	TOTAL SHEETS 30	SHEET NO. 3
	PLOT SCALE = 1"=1"	DRAWN - BVS	REVISED -		SCALE: N.T.S.	SHEET NO.	OF	SHEETS	STA.	TO STA.	CONTRACT # 63626	
	PLOT DATE = 10/17/2011	CHECKED - WCG	REVISED -		GHA #2806.242							
		DATE - 11/10/2011	REVISED -		ILLINOIS FED. AID PROJECT							