



SCHEDULE OF QUANTITIES

ITEM	UNIT	TOTAL
CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	2825
CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	450
HANDHOLE	EACH	3
TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	2800
TRANSCEIVER - FIBER OPTIC	EACH	6
ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	5580
FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	5730



FILE NAME = 28_D23301-sh1-ts03.dgn
 USER NAME = USER8291
 PLOT SCALE = 1:100
 PLOT DATE = 8/29/2011

DESIGNED - LC	REVISED -
DRAWN - LC	REVISED -
CHECKED - CF	REVISED -
DATE - 08/16/11	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**INTERCONNECT SCHEMATIC
 SHERIDAN ROAD - CHICAGO AVENUE TO CENTRAL STREET**

SCALE: N.T.S. SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE. 2853	SECTION 10-00258-00-TL	COUNTY COOK	TOTAL SHEETS 38	SHEET NO. 28
CONTRACT NO. 63630			ILLINOIS FED. AID PROJECT	