SUMMARY OF QUANTITIES

STU Funding 70% Federal, 30% Local

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE 0004 ROADWAY	0021 TRAFFIC SIGNALS & LIGHTING	0040 BRIDGE & RETAINING WALL
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	7	7	-	-
60404950	FRAMES AND GRATES, TYPE 24	EACH	3	3	-	-
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	1	1	-	-
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	1	1	-	-
60500040	REMOVING MANHOLES	EACH	8	8	-	-
60500050	REMOVING CATCH BASINS	EACH	5	5	-	-
60500060	REMOVING INLETS	EACH	30	30	-	-
60500070	REMOVING MANHOLES TO MAINTAIN FLOW	EACH	9	9	-	-
60500090	REMOVING INLETS TO MAINTAIN FLOW	EACH	13	13	-	-
60600605	CONCRETE CURB, TYPE B	FOOT	695	695	-	-
60603500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06	FOOT	324	324	-	-
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	15,778	15,778	-	-
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	3,548	3,548	-	-
60618740	CONCRETE MEDIAN, TYPE M-2.12	SQ FT	136	136	-	-
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	2,680	2,680	-	-
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	18	18	-	-
67100100	MOBILIZATION	L SUM	1	1	-	-
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	-	-
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1	-	-
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1	-	-
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1	-	-
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	-	-
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	-	-
70300100	SHORT TERM PAVEMENT MARKING	FOOT	14,700	14,700	-	-
70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	38	38	-	-
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	53,000	53,000	-	-
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	250	250	-	-
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	700	700	-	-
72000100	SIGN PANEL - TYPE 1	SQ FT	1,248	1,238	10	-
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	71	71	-	-
72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	16	16	-	-
72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	331	331	-	-
72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	1	1	-	-

* INDICATES SPECIALTY ITEM

SUMMARY OF QUANTITIES

STU Funding 70% Federal, 30% Local

	CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE 0004 ROADWAY	0021 TRAFFIC SIGNALS & LIGHTING	0040 BRIDGE & RETAINING WALL
	72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	8	8	-	-
	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	2,116	2,116	-	-
	73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	10	10	-	-
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,862	1,862	-	-
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	41,072	41,072	-	-
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5,690	5,690	-	-
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,830	1,830	-	-
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	865	865	-	-
*	78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	109	109	-	-
*	78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	20	20	-	-
*	78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	419	419	-	-
*	78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	175	175	-	-
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	68	68	-	-
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	360	360	-	-
*	80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	-	1	-
*	80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	-	1	-
*	80500010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	1	-	1	-
*	80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	4	-	4	-
*	81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	5,864	-	5,864	-
*	81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	234	-	234	-
*	81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	1,125	-	1,125	-
*	81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	1,694	-	1,694	-
*	81400100	HANDHOLE	EACH	23	-	23	-
*	81400200	HEAVY-DUTY HANDHOLE	EACH	18	-	18	-
*	81400300	DOUBLE HANDHOLE	EACH	10	-	10	-
*	81400730	HANDHOLE, COMPOSITE CONCRETE	EACH	10	-	10	-
*	81603035	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	6,709	-	6,709	-
*	81603100	UNIT DUCT, 600V, 4-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	1,091	-	1,091	-
*	81700215	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 2-1/C NO. 10	FOOT	730	-	730	-
*	82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	33	-	33	-
*	82500350	LIGHTING CONTROLLER, BASE MOUNTED, 240VOLT, 100AMP	EACH	1	-	1	-
*	84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	26	-	26	-
*	84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	3	-	3	-

* INDICATES SPECIALTY ITEM

COPYRIGHT © 2011 BY BAXTER & WOODMAN, INC.
STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
LICENSE NO.: 184-001113 EXPIRES 4/30/2013
10/31/2011 11:43:57 AM
...\plotdriver\PDF22x34.pltPAGESETUP
...\SHEETS\060670-PH2-S00.sht
I:\Crystal Lake\PROJECT\060670\CADD-SURVEY\DRAWINGS\UDCN\060670-PH2-S00.sht

BAXTER & WOODMAN Consulting Engineers

DESIGNED	TAO	REVISED	-
DRAWN	MAC	REVISED	-
CHECKED	TAO	REVISED	-
DATE	10/31/11	FILE	060670-PH2-S00.sht

STATE OF ILLINOIS
ORCHARD DRIVE IMPROVEMENTS

SUMMARY OF QUANTITIES

SCALE: | STA. | TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2836	06-00090-00-FP	COOK	200	6
		CONTRACT NO. 63635		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT	M-8003(661)	