

SUMMARY OF QUANTITIES

SPECIALTY ITEM	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
					80% FEDERAL 20% STATE		NON-PARTICIPATING 100% LOCAL	
					ROADWAY 0004 URBAN	BRIDGE 0011 URBAN	TRAINEES 0042 URBAN	
	54215550	METAL END SECTIONS 15"	EACH	2				2
	54247090	GRATING FOR CONCRETE FLARED END SECTION 12"	EACH	1	1			
	542C0220	PIPE CULVERTS, CLASS C, TYPE 1 15"	FOOT	68				68
	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	10	10			
	550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	214	214			
	59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	45		45		
	60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	1	1			
	60107600	PIPE UNDERDRAINS 4"	FOOT	177	177			
	60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1			
	60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1			
	60235300	INLETS, TYPE A, TYPE 1 FRAME, CLOSED LID	EACH	1	1			
	60500050	REMOVING CATCH BASINS	EACH	1	1			
*	63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	300	300			
*	63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4			
*	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4			
	63200310	GUARDRAIL REMOVAL	FOOT	376	376			
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8			
	67100100	MOBILIZATION	L SUM	1	1			
	72000100	SIGN PANEL - TYPE 1	SQ FT	7	7			
	72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	2	2			
*	78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	5,983	3080			2903
*	78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	72	16			56
*	78200410	GUARDRAIL MARKERS, TYPE A	EACH	11	11			
*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4			
*	A2000616	TREE, ACER PLATANOIDES (NORWAY MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	3	3			
*	A2002316	TREE, BETULA NIGRA (RIVER BIRCH), 2" CALIPER, BALLED AND BURLAPPED	EACH	2	2			
*	A2002716	TREE, CARYA OVATA (SHAGBARK HICKORY), 2" CALIPER, BALLED AND BURLAPPED	EACH	2	2			
*	A2005116	TREE, JUGLANS NIGRA (BLACK WALNUT), 2" CALIPER, BALLED AND BURLAPPED	EACH	8	8			
*	A2006416	TREE, QUERCUS ALBA (WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	2	2			
*	A2006516	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	2	2			
*	A2007816	TREE, TILIA AMERICANA (AMERICAN LINDEN/ BASSWOOD), 2" CALIPER, BALLED AND BURLAPPED	EACH	3	3			
*	A2008466	TREE, ULMUS AMERICANA (AMERICAN ELM), 2" CALIPER, BALLED AND BURLAPPED	EACH	3	3			

FILE NAME = \\A:\Projects\2010\100025 Burr-Ferguson\1\Drawn\Shd\Sht\5003.dgn



USER NAME = #USER#	DESIGNED - KMA	REVISED -
	DRAWN - NDP	REVISED -
PLOT SCALE =	CHECKED - SBP	REVISED -
PLOT DATE = 11/17/2011	DATE - 10/24/11	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 5 OF 76 SHEETS STA. TO STA.

T.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
194	08-14117-00-BR	KANE	76	5
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 63645	