

# PAVEMENT REMOVAL SCHEDULE

LOCATION	40600982	40600990	44000100	44000157	44000200
	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	PAVEMENT REMOVAL	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	DRIVEWAY PAVEMENT REMOVAL
	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)
<b>MAINLINE</b>					
7+00.00 - 8+00.00	25.00	25.0	36.0	345.0	
8+00.00 - 8+50.00			143.0		
8+50.00 - 9+00.00			128.2		
9+00.00 - 9+50.00			129.1		
9+50.00 - 10+00.00			128.6		
10+00.00 - 10+50.00			129.2		
10+50.00 - 11+06.50			145.4		
<b>BRIDGE</b>					
11+64.50 - 12+00.00			68.3		
12+00.00 - 12+50.00			90.8		
12+50.00 - 13+00.00			126.4		
13+00.00 - 13+50.00			126.3		
13+50.00 - 14+00.00			127.4		
14+00.00 - 14+50.00			128.7		
14+50.00 - 15+00.00			129.0		
15+00.00 - 15+50.00			128.9		
15+50.00 - 15+70.00			128.4		
15+70.00 - 16+00.00			51.0		7.0
16+00.00 - 16+50.00					
16+50.00 - 17+00.00					
17+00.00 - 17+50.00					
17+50.00 - 18+00.00					26.0
18+00.00 - 18+50.00					
18+50.00 - 19+00.00					
19+00.00 - 19+50.00					
19+50.00 - 20+00.00					
20+00.00 - 20+50.00					
20+50.00 - 21+00.00					
21+00.00 - 21+50.00					
21+50.00 - 22+00.00					
22+00.00 - 22+50.00	27.9				
22+50.00 - 23+00.00	68.8				
23+00.00 - 23+40.00	79.9				
<b>ENTRANCE</b>					
9+62.00					304.6
<b>TOTAL</b>	<b>202</b>	<b>25</b>	<b>1,945</b>	<b>345</b>	<b>338</b>

# STRIPING AND GUARDRAIL SCHEDULE

LOCATION	63000001	63100087	63100167	78008210	78008270	78200410	78201000
	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	TRAFFIC BARRIER TERMINAL, TYPE 6A	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	GUARDRAIL MARKERS, TYPE A	TERMINAL MARKER - DIRECT APPLIED
	(FOOT)	(EACH)	(EACH)	(FOOT)	(FOOT)	(EACH)	(EACH)
<b>MAINLINE</b>							
6+60.00 - 7+00.00				160	16		
7+00.00 - 8+00.00				155			
8+00.00 - 8+50.00				200			
8+50.00 - 9+00.00				200			1
9+00.00 - 9+50.00			1	200			
9+50.00 - 10+00.00	50.7			200		2	
10+00.00 - 10+50.00	49.3		1	200		1	1
10+50.00 - 11+06.50		2		226		1	
<b>Bridge</b>							
11+64.50 - 12+00.00		2		232			
12+00.00 - 12+50.00	48.2			142			
12+50.00 - 13+00.00	106.8			200		3	
13+00.00 - 13+50.00	45.0			200		3	
13+50.00 - 14+00.00			1	200		1	2
14+00.00 - 14+50.00			1	200			
14+50.00 - 15+00.00				200			
15+00.00 - 15+50.00				200			
15+50.00 - 15+70.00				80			
15+70.00 - 16+00.00				120			
16+00.00 - 16+50.00				200			
16+50.00 - 17+00.00				200			
17+00.00 - 17+50.00				200			
17+50.00 - 18+00.00				200			
18+00.00 - 18+50.00				200			
18+50.00 - 19+00.00				200			
19+00.00 - 19+50.00				200			
19+50.00 - 20+00.00				200			
20+00.00 - 20+50.00				200			
20+50.00 - 21+00.00				200			
21+00.00 - 21+50.00				200			
21+50.00 - 22+00.00				200			
22+00.00 - 22+50.00				68			
22+50.00 - 23+00.00					56.0		
23+00.00 - 23+40.00							
<b>TOTAL</b>	<b>300</b>	<b>4</b>	<b>4</b>	<b>5,983</b>	<b>72</b>	<b>11</b>	<b>4</b>

FILE NAME = \\projects\2010\180025 burrfarson\Acadd\Civil\Drawn\Schedule.dgn



USER NAME = #USER#	DESIGNED - KMA	REVISED -
DRAWN - NDP	CHECKED - SBP	REVISED -
PLOT SCALE =	DATE - 10/24/11	REVISED -
PLOT DATE = 10/19/2011		

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES	
SCALE:	SHEET NO. 11 OF 76 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
194	08-14117-00-BR	KANE	76	11
CONTRACT NO. 63645				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				